




Elevation 6 - View 01

Not To Scale



Elevation 6 - View 02

Not To Scale



Elevation 7 - View 01

Not To Scale



Elevation 7 - View 02

Not To Scale

NOTE
Include Fix Brick skirting to all walls, coping stones, letter canopy + supports, railings, floor fix - to remove walls and roof.

REPAIR WORKS LEGEND
E3404 - Carefully locate down any blockwork and concrete frame avoiding damage to floor levels.
E3405 - Movement joints - Remove any inappropriate material and replace with new grout mortar to fill space. Blockwork - Colour to match surrounding blockwork. Contractor to provide sample for approval.
Cloud - Carefully remove later addition fixtures and fittings including all associated cabling and conduit, make good walls.
E3407 - Investigate wall condition behind existing plaster coating to remove cause of staining. Include for remedial works as required - scope of works to be reviewed.
E3408 - Removal damaged plaster as investigate condition of wall. Include for remedial works as required - add for new plaster finish to match existing texture and composition.
E3409 - NBS Potential for new light fittings in this location. To be reviewed with MEP designer. Lighting designer prior to removal.


COPYRIGHT RESERVED:
The Copyrights to all designs and drawings are the property of Seven
Reproduction or use for any purpose other than that authorised by Seven
forbidden.

- GENERAL NOTES:
1. All dimensions to be checked on site, The Contractor shall verify and be
for all dimensions.
 2. DO NOT scale the drawing - The drawing must not be scaled for any purpose,
to written dimensions only.
 3. Any queries or doubts, drawing errors, omissions or divergences shall be
to Seven Architecture without delay and prior to works being carried out.
 4. This drawing is subject to statutory approvals.
 5. All works are to be in accordance with the planning approval and my
approved Local Authorities planning correspondence including drawings,
documents and reports.
 6. All works are to comply with the Building Regulations, British Standards, Code
Practice and any Local Statutory requirements.
 7. All works are to comply with current Health & Safety Legislation, HSE
recommendations / guidance and the current CDM regulations.
 8. All architectural drawings are to be read in conjunction with the relevant
architectural specifications and outline specification sheets.
 9. All the details and setting-out drawings to be read in conjunction with the
consultants and subcontractor drawings.
 10. All details and setting-out drawings are design intent only. Final arrangement
subject to design development and coordination with Design Team
relevant subcontractors.

REV.	DESCRIPTION:	DATE:	DRAWN:	CHECK:
P01	Issued For Planning	06/10/25	RS	RS

THIS DRAWING IS SUBJECT TO ALL
NECESSARY STATUTORY APPROVALS

DRAWING SCALE: NTS



CLIENT:
Hopwood Hall College



PROJECT TITLE:
HCO Millnrow Chapel Conversion

PROJECT NO:
20765

DRAWING TITLE:
Internal Repair Works - Elevations 3 of 5

DRAWING NO:

PROJECT	ORIGIN	ZONE	LEVEL	TYPE	ROLE	NO.#	REVISION
HCO	SEV	ZZ	ZZ	DR	A	00152	P01

SUITABILITY DESCRIPTION (S2) Suitable for Information

REVISION DESCRIPTION PLANNING

seven.

SEVENARCHITECTURE.CO.UK

Unit 1.3 Wauk Mill
51 Bengal St
MANCHESTER
M4 6LN
t: 0161 236 5655

Studios at:

Clarendon House
Victoria Avenue
HARRINGTON
HE1 1JD
t: 01423 709 807

Y Neuadd Llyrd
Dolwyddelan
CONWY
LL25 0SJ
t: 01286 875120