

**NOTE**  
  
Include Fix  
Brick skirting to all walls, coping stones, later canopy + supports, railings, floor fix - to remove walls and fix.

**REPAIR WORKS LEGEND**  
  
E3b05 - Carefully locate down rag blockwork and concrete frame avoiding damage to blockwork.  
E3b05 - Movement joints - Remove any inappropriate material and replace with new aggregate mortar to fill gaps. Colour - Colour to match surrounding blockwork. Contractor to provide sample for approval.  
E3b05 - Carefully remove later addition fixtures and fittings including all associated ceiling and conduit, make good walls.  
E3b05 - Attention to be made as part of proposed scheme - refer to proposed drawings.  
E3b05 - Investigate wall condition behind existing plaster coating to make cause of staining. Include for remedial works as required - scope of works to be.  
E3b05 - Attention to be made as part of proposed scheme - refer to proposed drawings.  
E3b05 - Removal damaged plaster as investigate condition of wall / ceiling. Include for remedial works as required - refer to proposed drawings to match existing texture and composition.

- COPYRIGHT RESERVED:**  
The Copyrights to all designs and drawings are the property of Seven  
Reproduction or use for any purpose other than that authorised by Seven  
is forbidden.
- GENERAL NOTES:**
1. All dimensions to be checked on site, The Contractor shall verify and be for all dimensions.
  2. DO NOT scale the drawing - The drawing must not be scaled for any purpose, to written dimensions only.
  3. Any queries or doubts, drawing errors, omissions or divergences shall be to Seven Architecture without delay and prior to works being carried out.
  4. This drawing is subject to statutory approvals.
  5. All works are to be in accordance with the planning approval and my approved Local Authorities planning correspondence including drawings, documents and reports.
  6. All works are to comply with the Building Regulations, British Standards, Code Practice and any Local Statutory requirements.
  7. All works are to comply with current Health & Safety Legislation, HSE recommendations / guidance and the current CDM regulations.
  8. All architectural drawings are to be read in conjunction with the relevant architectural specifications and outline specification sheets.
  9. All the details and setting-out drawings to be read in conjunction with the consultants and subcontractor drawings.
  10. All details and setting-out drawings are design intent only. Final arrangement subject to design development and coordination with Design Team relevant subcontractors.

| REV. | DESCRIPTION:        | DATE:    | DRAWN: | CHECK: |
|------|---------------------|----------|--------|--------|
| P01  | Issued For Planning | 06/10/25 | RS     | RS     |

\*Include for re-fixing 2no. loose plinth stones to chapel walls



Elevation 4b

Not To Scale

Brick Skirting Detail - Include for Cleaning to remove salts and re-pointing areas with missing or defective mortar - assume 50%



Elevation 4b

Not To Scale

Include for removal of carpet tiles to chapel area.



Elevation 4b

Not To Scale


Blockwork: Include for re-pointing to areas of missing or defective pointing - assume 25%



Elevation 4a

Not To Scale


Blockwork: Include for re-pointing to areas of missing or defective pointing - assume 25%



KEY PLAN (NTS):

THIS DRAWING IS SUBJECT TO ALL NECESSARY STATUTORY APPROVALS

DRAWING SCALE: NTS



Elevation 5c

Not To Scale



Elevation 5b

Not To Scale

Remove later addition fixtures and fittings and make good to walls behind.

Blockwork: Include for re-pointing to areas of missing or defective pointing - assume 25%



Elevation 5a

Not To Scale

Blockwork: Include for re-pointing to areas of missing or defective pointing - assume 25%

Stone Skirting-repoint areas with missing or defective mortar - applies to all skirtings

CLIENT:  
Hopwood Hall College



PROJECT TITLE:  
HCO Millnrow Chapel Conversion

PROJECT NO:  
20765

DRAWING TITLE:  
Internal Repair Works - Elevations 2 of 5

DRAWING NO:

| PROJECT | ORIGIN | ZONE | LEVEL | TYPE | ROLE | NO.#  | REVISION |
|---------|--------|------|-------|------|------|-------|----------|
| HCO     | SEV    | ZZ   | ZZ    | DR   | A    | 00151 | P01      |

SUITABILITY DESCRIPTION (S2) Suitable for Information

REVISION DESCRIPTION PLANNING

seven.

SEVENARCHITECTURE.CO.UK

Unit 1.3 Wauk Mill  
51 Bengal St  
MANCHESTER  
M4 6LN  
t: 0161 236 5655

Clarendon House  
Victoria Avenue  
HARRINGTON  
HE1 1JD  
t: 01423 709 807

Studios at :  
Y Neuadd Llyrd  
Dolwyddelan  
CONWY  
LL25 0SJ  
t: 01286 875120