

RTAG03 – Dormer Window methodology – HV Joinery

- *Carefully remove existing beads and DGU's.*
- *Replace the bottom section of each Jamb and Mullion with Sapele hardwood sections on every bank of windows making sure all rot is removed.*
- *Replace the full cill on each bank of windows with a Sapele hardwood cill.*
- *Carefully reinstate existing glass using existing beads.*
- *The works are to be carried out working on one Jamb or mullion at one time to ensure the structural integrity of the roof stays intact.*
- *1 coat of primer included on all replacement timber and all joints.*





