

Planting Schedule

Proposed Trees								
Name	Form	Age	Girth (cm)	Height (cm)	Clear Stem	Root cdm	Spacing	No.
Acer campestre 'William Caldwell'	Standard (heavy)	3X	12 - 14	350 - 425	min 200	RB	As shown	09
Alnus glutinosa	Standard (heavy)	3X	12 - 14	350 - 425	175 - 200	RB	As shown	02
Sorbus aucuparia 'Sheenwater Seedling'	Standard (heavy)	3X	12 - 14	350 - 425	175 - 200	RB	As shown	03


NOTES:

1. This drawing is to be read in conjunction with all relevant contract documentation from the design team, with any conflicting information to be brought to the attention of Davis Landscape Ltd in writing before commencing on site.
2. The contractor is to check and verify all levels and dimensions before construction. Any discrepancies are to be brought to the attention of Davis Landscape Ltd in writing before commencing on site.
3. All dimensions in mm, unless otherwise stated.
4. Do not scale from this drawing.
5. All sub base and concrete specification, fixings, brackets & the like to Engineers' details & specification.
6. We are not liable for the detailed design of above ground drainage, ground drainage, sub-bases, foundations, retaining structures, fall from height barriers and building waterproofing details.
7. All proprietary products shall be installed in accordance with manufacturers written instructions.
8. Submit Shop drawings for Davis Landscape Ltd approval before constructing any bespoke landscape item.

Key:

- Proposed trees.
- Refer planting schedule for tree species.

All the trees should be sourced from reputable UK suppliers.



Rev	Description	Date	By

Davis Landscape Architecture
15 Iliffe Yard, London, SE17 3QA
020 7277 1035
mail@davisla.com | www.davisla.com

Client
Poise Group

Job Title
Village Hotel, Bury

Drawing Title
Planting Plan

Scale : 1:100 @A0 Drawn : CK

Date : 22.07.2024 Checked : JD

Drawing No. : L1053L01 Rev. : -