

KEY

- ROAD GULLY
- S/W GULLY
- RAIN WATER PIPE
- MANHOLE
- GREASE TRAP
- SVP
- F/W GULLY
- F/W DRAIN
- S/W DRAIN
- ASSUMED LINE
- 150MM CAST IRON ASSUMED BREATHER PIPE

DRAIN DIAMETERS MAY NOT BE EXACT AS THEY HAVE NOT BEEN MEASURED DUE TO THE DEPTH OF THE MANHOLES

HEAVILY SILTED

clock tower

PIPE PROTRUDING UNABLE TO PASS

300MM

90 DEGREE BEND UNABLE TO GET CAMERA UNIT PAST

300MM

375MM

450MM

450MM DIA APPROX.

EGG SEWER LARGE OBSTRUCTION

EGG SEWER UNABLE TO SURVEY FULL LENGTH

450MM DIA APPROX.

HIGH PRESURE WATER JETTED THEN DYE TESTED. UNABLE TO GET PAST TIGHT TRAP. WOULD REQUIRE A SMALL EXCAVATION IN FRONT FOR ACCESS.ON ANY OF THE LIGHT WELL GULLIES.

ROCHDALE TOWN HALL. BASEMENT PLAN.

ATTEMPTED TO CCTV SURVEY NUMEROUS DOWNSPOUTS. ALL SURVEYED HAVE A GULLY BELOW GROUND

MH NO.	INVERT (MM)	OPENING (MM)	BOTTOM (APPROX MM)
1	2260	600X450	1500X1500
2	2600	600X450	2000X1500
3	5500	550X550	1500X1000
4	1350	600X450	2000X1000
5	1040	600X450	1500X1000
6	1080	600X450	2000X1000
7	970	600X450	1500X1000
8	580	600X450	1500X1000
9	1780	600X450	700X550
10	2000	600X450	700X550
11	260	600X450	600X450
12	370	600X450	700X500
12A	3800	550X550	650X650
13	4150	550X550	650X650