



Detailed GA Elevation - North East
1 : 100

NOTE:
1. DO NOT SCALE OFF THIS DRAWING.
2. ANY DISCREPANCIES TO BE REPORTED IMMEDIATELY TO THE ARCHITECT.
3. ALL DIMENSIONS TO BE SITE CHECKED & VERIFIED BY THE CONTRACTOR PRIOR TO THE MANUFACTURE OR ORDER OF ANY MATERIALS OR GOODS.

MATERIALS KEY:
Proposed Materials

- 1 Staffordshire blue blue brick (to match ex) laid in stretcher bond
- 2 Curtain wall system with clear glazing
- 3 Tentel 60 with Flat Cap curtain walling with clear glazing, grey opaque glass spandrel panels and projecting orange ppc fins
- 4 Grey coloured Flat Terracotta Tile 22mm thick. 900mm x 200mm
- 5 Omitted
- 6 Glazed Balustrade
- 7 Curtain walling system with clear glazing and blanking panels
- 8 GRC Concrete Columns
- 9 Freestanding keyclamp Balustrade to roof
- 10 PPC Aluminium External Fire Escape Door
- 11 PPC Aluminium Louvred Vents Colour to match Terracotta Tile

Existing Materials

- a Blue/grey brick laid in stretcher bond
- b Grey terracotta rainscreen cladding, stack bonded
- c PPC aluminium framed window and curtain walling systems
- d Orange coloured transparent window film
- e SSG transoms
- f PPC aluminium coloured aerofoil fins - 300mm projection fixed to curtain walling mullions
- g Doubled glazed insulated spandrel panels
- h PPC aluminium louvre panels
- j High quality finish concrete encased steel columns
- k Roof lights

PR6	Louvres added to elevations	01.09.23
PR5	GA Elevations updated materials legend	31.08.23
PR4	Stage 4 Issue	23.08.23
PR3	Elevations updated with latest curtain wall changes	15.08.23
PR2	General updated to stage 4 information	01.08.23
PR1	Updates to Sections and Elevations	03.07.23
Rev	Description	Date

STAGE 4 - PRELIMINARY		
Rochdale Sixth Form College College Road, Rochdale, OL12 6HY		
Detailed Elevations - North East		
DRAWING NUMBER 3940-ABW-ZZ-ZZ-DR-A-2820		
DATE 07/03/23	REVISION PR6	STATUS PURPOSE OF ISSUE
SCALE As indicated		
ABW architects Ltd. architecture.building.workshop		A1 © 01/09/2023 14:38:17