




Local conditions may dictate the use of sheet piles driven to a suitable designed depth below bed level of the watercourse. Alternatively a concrete toe beam together with stone pitching to the bank of the watercourse as shown on Typical detail D must be used.

NOTES


1. All dimensions in millimetres
2. Generally the angle between the direction of flow of the receiving watercourse and the outfall pipe should be 45°
3. All reinforced concrete edges to be finished with a 25 x 25 fillet
4. Min cover to reinforcement in the top face of the base slab to be 40
5. The bed and opposite bank of the watercourse may,in certain circumstances need to be protected by 225 to 300 thick uncoursed rubble pitching laid on a 100 thick bed of FND2 concrete (Note 8)and pointed in Class M1 Mortar. The stone for pitching shall consist of large smooth faced stones roughly dressed square and shall be of a hard durable and inert material. Bunter sandstone, Keuper waterstones and Carboniferous shales and mudstones are not to be used
6. An Outlet Grille as shown on Typical Detail G must be provided on all outfalls where the pipe size exceeds 450mm. Where pipe diameters are 375 to 450, 20 dia. stainless steel bars are to be provided across outlet at max. 120mm c/c leaving 100mm max. clear opening
7. Where outlets have a flap valve, a special detailed grille must be provided on all outlets 375mm diameter and above
8. Secure handrailing shall be supplied where a person may fall 2 metres or more or where a fall of less than 2 metres carries an increased risk of injury due to the landing surface
9. FND2 to be used for soil conditions Sulphate class 1 only. Designated mix references FND3, FND4A & FND4B to be used in soil conditions with sulphate classes 3,4A and 4B respectively (refer to specification clause 4.3.1)

CIVIL / STRUCTURAL DESIGN RISK MANAGEMENT

Abnormal or unusual residual risks associated with the design outcomes shown on this drawing are:-

RSK LDE LTD has followed its Design Risk Management process for Hazard Elimination and Risk reduction in developing the designs shown on this drawing. Abnormal or unusual residual risks may be shown above where it is considered that such risk may not normally be expected by competent persons engaged on work of this nature or type.

225 to 300 thick uncoursed random rubble pitching on 100 thick Grade FND2 (Note 4) concrete and pointed in Class M1 mortar



TYPICAL DETAIL F
TYPICAL OUTFALL DETAIL TYPE 3
(MAXIMUM PIPE SIZE 225mm)

NOTES

All dimensions in millimetres

1. The bed and opposite bank of the watercourse may in certain circumstances, need to be protected by 225 to 300 thick uncoursed rubble pitching laid on 100 thick bed of FND2 concrete (Note 4) and bed of FND2 concrete (Note 4) and pointed in Class M1 mortar. The stone for pitching shall consist of large smooth faced stones roughly dressed square and shall be of a hard durable and inert material. Bunter sandstones, Keuper waterstones and carboniferous shales and mudstones are not to be used
2. Maximum diameter 225mm
3. FND2 to be used for soil conditions sulphate class 1 only. Designated mix references FND3, FND4A & FND4B to be used in soil conditions with sulphate classes 3,4A and 4B respectively (refer to specification clause 4.3.1)

P1	12.07.21	First Issue		JA	MS
Rev.	Date	Amendment	Drawn	Chkd.	Appd.
RSK LAND & DEVELOPMENT ENGINEERING LTD Spring Lodge 172 Chester Road Helstby Cheshire, WA6 0AR United Kingdom Tel: +44 (0) 1928 726006 Fax: +44 (0) 1928 725633 Email: ld@rsk.co.uk Web: www.rsk.co.uk					
Client					
Kellen Homes					
Project Title					
Don Street Middleton					
Drawing Title					
Drainage Construction details Sheet 10 of 10					
Drawn	Date	Checked	Date	Approved	Date
JA	JULY '21	MS	JULY '21		
Scale	Orig Size		Dimensions		
NTS	A1				
Project No. 882333			Drawing File		
Drawing No. 40-15-10				Rev.	P1