SUTHERLAND ROAD

19

12

LB

ESS

Chy

Manhole Schedule

Ref	Cover Level	Invert Level
SW1	22.850	22.080
SW2	22.850	21.480
SW3	21.850	21.250
SW4	21.850	21.000
SW5	22.850	22.125
SW6	22.850	21.550
SW7	22.300	21.600
SW8	21.850	20.950
SW9	21.850	20.825
SW10	22.550	21.850
SW11	22.550	21.550
SW12	22.200	21.500
SW13	22.200	20.850
SW14	21.650	20.900
SW15	21.650	20.600
SW16	22.550	20.615
SW17	23.000	21.800
SW18	22.000	20.340
SW19	21.800	20.125
MH21	TBC	To suit Extg IL

NOTES.

1. REFER TO SK02 FOR GENERAL NOTES
2. LEVELS & ARRANGEMENT SUBJECT TO:
   - RWP & SWP FINAL LOCATIONS
   - DETAILED DESIGN
   - SI REPORT
   - AGREEMENT WITH BROWNHILL & UU.
   - FURTHER ECTV OF PRIVATE DRAINAGE ON BROWNHILL SITE.

PIPES MARKED * IDENTIFIED TO PROVIDE ATTENUATION IF REQUIRED. SIZE TO BE CONFIRMED SUBJECT TO DETAILED DESIGN & SOAKAWAY ASSESSMENT. INITIAL SIZE 600 ø.

MANHOLE MARKED # PROPOSED HYDROBRAKE

SHORT PIPES TO GULLEYS ALL 100 ø

EXISTING MANHOLE FOR PRIVATE COMBINED SYSTEM. CL ~20.3 IL ~19.4

Browhill Learning Community

Darnhill Site

PRELIMINARY

WML CONSULTING

Project: SUTHERLAND RD, HEYWOOD
Drg Title: SURFACE WATER DRAINAGE
Job No: 7985 By: RJ
Drg No: SK03 Rev: –
Date: 30/11/18 Scale: NTS