

NOTES

The existing building measured survey has been undertaken by Salford Archaeology and all reference to this information is referenced directly from the associated drawings.

KEY

Coloured areas of hatch on interior elevations indicate existing fixtures, fittings or built fabric, proposed to be removed, as below:

- (Light Pink) - Existing to be removed, viewed in elevation.
- (Dark Red) - Existing to be removed, cut through by plane of view.
- (Red Stripe) - Existing to be removed, above

GENERAL DEMOLITION NOTES

All demolition to be carried out in accordance with Price & Myers recommendations for propping and temporary support.

Existing MEP
All redundant services to be removed and all holes to be filled with like for like. Refer to Max Fordham proposals as required.

Remove wired glass and asphalt roof. R9m

Remove slates, lead valleys and coping stones from fire station roof and retain for future reuse.

