



PLANTING SCHEDULE

SPECIFICATION: PROVIDE 2NO. PRUNUS 'KURSAR' SMALL FLOWERING SINGLE STEM CHERRY TREES - REF: T1 & T2, TO BE PLANTED AT 400CM CRS SUPPLIED SIZE 150-200CM, ROOT TYPE 12L POT

PLANTING: REMOVE GRASS, THEN DIG A SQUARE HOLE AS DEEP AS THE ROOT MASS AND TWICE AS WIDE. TO HELP THE TREE ESTABLISH, SPRINKLE ROOT GROW IN THE HOLE. REMOVE THE POT, GENTLY LOOSEN THE ROOTS AND PLACE INTO THE PLANTING HOLE. MIX 50% OF THE ORIGINAL SOIL WITH 50% COMPOST, FILL IN THE HOLE AND FIRM AROUND GENTLY. AVOID BANKING THE SOIL UP AROUND THE COLLAR OF THE TREE. EACH TREE TO HAVE A WEATHERPROOF STAKE, BUCKLE TIE & VENTILATED RABBIT/STRIMMER GUARD.

AFTERCARE: WATER CHERRY TREES WELL AND REGULARLY WATER THROUGH THE FIRST SPRING / SUMMER, INCREASING IN PERIODS OF HOT OR DRY WEATHER. ONCE PLANTED, KEEP THE AREA FREE OF ANY WEEDS.




REFERENCE TREE IMAGE

FUSION BY DESIGN
All design work and information provided on this drawing must under NO circumstances be reproduced in any form without the prior written approval by Fusion by design.
NOTE TO ALL CONTRACTORS:-
Under NO circumstances must dimensions be scaled from this drawing. All contractors must be responsible for taking and checking all dimensions upon visiting site. All contractors must advise the DESIGNER immediately, in writing, of any discrepancies.
This drawing is to be read in conjunction with the bill of quantities / specification and any related drawing. The contractor must ensure that all items detailed on this drawing are included when tendering even if not covered by the specification. The Designer must be advised in writing of all such items. Any discrepancies between drawings and specification must be resolved with the Designer prior to commencing works.
All structural work must be carried out in strict accordance with the drawing and calculations provided by the appointed Structural Engineer. All structural work must be inspected at all relevant stages by both the Structural Engineer and Building Inspector, any changes or alterations must have their express written approval. Any costs incurred due to either claims for damages, loss of trade, etc by failing to do so will be the sole liability of the contractor.
All works must be carried out in strict accordance with all Local Authority, British & European Standards. If in doubt, it is the responsibility of the contractor to contact all relevant parties.
Under the guidance of CDM 2015, the designer will not commence work in relation to a project unless satisfied that the client is aware of their duties duty owned and obligated to them under these regulations. This drawing precludes Fusion by Design Ltd., from the role of Principal Designer unless otherwise contractually engaged.

B.	DL	TREE PLANTING SCHEDULE ADDED.	28.07.23
A.	DL	PATIO TREE REMOVED.	14.04.23

Revision



FUSION BY DESIGN - FABRIC HOUSE
HOLLY PARK MILLS, WOODHALL LANE, LEEDS LS28 5QS
Telephone 0113 2047788 Fax 0113 2047866
E-Mail info@fusionbydesign.co.uk Web www.fusionbydesign.co.uk

Client
J.W. LEES
Job Title
**PACK HORSE INN,
ELBUT LANE, BIRTLE ROAD
BURY, BL9 6UR**
Drawing Title
**PROPOSED GROUND FLOOR /
SITE PLAN**

Scale 1:100	Drawing No 4002-PL02	Revision B
Date JULY 2023		
Drawn By DL		