TREE PLANTING

	Species	Spec	Total
Aa	Amelanchier arborea 'Robin Hill'	Multi-stem, 3-3.5m height	**9**
Ac	Acer campestre	12-14cm girth	4
Acg	Acer campestre globosum	Multi-stem, 3-3.5m height	5
Aprr	Acer platanoides 'Royal Red'	18-20 cm girth	1
Bp	Betula pendula	12-14 cm girth	8
Cb	Carpinus betulus	12 - 14 cm girth	5
Cbff	Carpinus betulus 'frans fontaine'	18-20 cm girth	9
Cj	Cercidiphyllum japonicum	18-20 cm girth	1
Ck	Cornus kousa	18-20 cm girth	2
Gt	Gledista triacanthos	18-20 cm girth	1
Pc	Pyrus calleryana chanticleer	18-20 cm girth	8
Pp	Parrottia persica	18-20 cm girth	1
Qr	Quercus robur	12 - 14 cm girth	7

NB: All Trees except multi-stem are to be supplied with min 2m clear stem

WETLAND SHRUB PLANTING MIX - 15sq.m Planted in groups of 3 - 5.

10	Alchemilla mollis	3L		4/sq.m	6
15	Crocosmia 'Lucifer'	3L		4/sq.m	9
15	Deschampsia cespitosa	3L		4/sq.m	9
5	Helenium autumnale	1-3L		4/sq.m	3
10	Iris 'Tropic Night'	3L		4/sq.m	6
5	Lythrum virgatum	3L	30-40	4/sq.m	3
5	Matteuccia struthiopteris	1-3L		4/sq.m	3
15	Molinia caerulea	3L	30-40	4/sq.m	9
10	Persicaria affinis 'Superba'	1-3L		4/sq.m	6
10	Rudbeckia 'Goldsturm'	2L		4/sq.m	6
					60

12 - 14 girth native tree
18 - 20 girth ornamental tree
Multi-stem shrub
Ornamental shrub planting mix
Wetland shrub planting mix
Wildflower turf
Wilflower seed
Wetland seed
Native hedge

1 nr Qr
1 nr Cb
3nr Bp
1 nr Ac
1 nr Bp
1 nr Acrr
1 nr Pp
3 nr Aa
1 nr Cj
1 nr Gt
1 nr Ck
1 nr Acg
9 nr Cbff
8 nr Pc
C/B
TH

Ornamental shrub mix- 171sq.m Planted in groups of 5 - 10.

2	Achillea filipendulina 'Gold Plate'	1-3L		5/sq.m	17
2	Alchemilla mollis	3L		5/sq.m	17
	Allium 'Globemaster'	Bulb	Planted in groups of 20		140
5	Astrantia Major	3L		5/sq.m	43
2	Carex buchanii	2L		5/sq.m	17
2	Carex 'ice dance'	2L		5/sq.m	17
5	Deschampsia cespitosa 'Bronzeschleier'	1-3L		5/sq.m	43
5	Echinacea purpurea	1-3L		5/sq.m	43
5	Festuca glauca 'Elija Blue'	3L		5/sq.m	43
2	Hebe 'Emerald Gem'	5L		5/sq.m	17
5	Helenium 'Moerheim Beauty'	3L		5/sq.m	43
2	Heuchera 'Palace Purple'	3L		5/sq.m	17
5	Hosta plantaginea	2L		5/sq.m	43
5	Hakonecloa macra aureola	3L		5/sq.m	43
5	Hakonecloa macra nicolas	3L		5/sq.m	43
5	Hakonecloa macra	3L		5/sq.m	43
6	Lavandula angustifolia 'Vera'	3L		5/sq.m	51
5	Liriope muscari	2L		5/sq.m	43
5	Ophiopogon planiscapus	2L		5/sq.m	43
5	Persicaria affinis 'Superba'	3L		5/sq.m	43
5	Phlomis tuberosa 'Amazone'	1-3L		5/sq.m	43
2	Salvia nemorosa 'Caradonna'	2L		5/sq.m	17
5	Sedum spectabile 'Autumn Joy'	3L		5/sq.m	43
5	Stipa tenuissima	3L		5/sq.m	43
5	Verbena bonariensis	2L		5/sq.m	43
100					**998**

Hedge planting- 103lm

	Species	Pot	Height	% Mix	Total
	Crataegus monogyna	BR	40-60	50	154
	Corylus avellana	BR	20-40	25	77
	Prunus spinosa	BR	20-40	25	77
Plant at 3 per lm in a double staggered row (rows 300mm apart)					308

Wildflower Turf - 201sq.m
Landscape 34 by Wildflower Turf or similar

Wildflower seed - 815sq.m
Emorsgate EM1 or similar. Sown at 4g /m2

Wetland meadow seed - 1120sq.m
Emorsgate EM8 or similar. Sown at 4g /m2

DEP LANDSCAPE ARCHITECTURE LTD
2 COMMERCIAL STREET
MANCHESTER, M15 4RQ
T: 0161 2419878
E: info@dep.co.uk
W: www.dep.co.uk

Client
Saper and Co Ltd

Project
Smithy Bridge Care Home

Description
Planting Plan

Status
Planning

Scale 1:100@A1
Drawn BH
Job number 4557
Drawing number 14
Date Oct 20
Revision

Copyright DEP Landscape Architecture Ltd

All levels and dimensions to be checked on site by contractor prior to commencement; Any variations to be reported to the client. This drawing is to be read in conjunction with all others relating to the project and all information derived accordingly; any anomolies to be reported to the client. Do not scale from this drawing. Use figured dimensions only. Work shown on this drawings to be carried out in accordance with current British Standards and Codes of Practice.

© Copyright to DEP Landscape Architecture Limited. The information shown on this drawing shall not be reproduced or copied in any form without prior written consent from DEP Landscape Architecture Limited.