

# SECTION 104 & 38 NOTES

- All adoptable drainage works have been designed and are to be constructed in accordance with current Design & Construction Guidance & local practices
- All clay pipe work shall be Extra Strength Clayware to B.S. EN 295:1991 Part 1
- All precast concrete pipework shall be to the class stated on the drawings in accordance with BS EN 1916:2002. All manholes and chambers shall be to BS EN 1917:2002
- The Contractor may elect to use reinforced PVC pipes as covered by BS 4660:2000 & BS EN 1401-1 Structured wall upvc pipes to comply with w14 4-35-01 up to and including 300mm. (By prior agreement with adopting authority) MAX. PIPE LENGTH TO BE 3.0m
- All levels relate to an Ordnance Datum.
- This drawing is to be read in conjunction with all other relevant drawings.
- House drainage connections to sewers must be 150mm Ø and unless otherwise stated laid to the dragout invert level shown.
- Levels given on drag out chambers are incoming pipe levels.
- House drainage runs to be kept within the curtilage of the plot they serve wherever possible.
- The Contractor shall be responsible for ensuring that any existing invert levels indicated on drawings are correct before work commences.
- The Contractor should satisfy himself as to the position and depth of any existing Statutory Undertakers plant which could effect the works before the works are commenced.
- Road gully connections are to be 150mm Ø connecting either directly to manholes shown, or to sewer runs using pre-formed junctions.
- All connections to adoptable sewers shall be by manufactured junction pipes. Saddle connections will not be permitted.
- All sewers for adoption with greater than 1.20 metres cover in roads or 0.9m metres cover in fields shall have Class S granular bed and surround.
- Any sewer for adoption with less than 1.2 metres cover in roads or 0.9 metres cover in fields shall have a minimum of 150mm ST4 concrete surround. Flexibility shall be maintained by the provision of Flexcoll or similar approved joint filler breaks in the concrete surround at each pipe joints

ALL PIPES TO HAVE CLASS 'S' BED AND SURROUND UNLESS SHOWN OTHERWISE  
ALL CONCRETE PIPES TO BE CLASS 120  
ALL CLAY PIPES TO BE EXTRA STRENGTH VITRIFIED CLAY  
ALL UPVC PIPES TO COMPLY WITH BS 4660:2000 & BS EN 1401-1  
STRUCTURED WALL UPVC PIPES TO COMPLY WITH W14 4-35-01  
MAX. PIPE LENGTH TO BE 3.0m

FOUNDATIONS TO BE DESIGNED / CONSTRUCTED TO TAKE INTO ACCOUNT THE PROXIMITY AND DEPTH OF ADJACENT SEWERS AND DRAINS IN ACCORDANCE WITH SFA 7TH EDITION PART B

OUTSIDE OF NEW SEWERS TO BE LOCATED 1.0m MINIMUM FROM KERBLINES OUTSIDE OF MANHOLE CHAMBERS TO BE LOCATED 0.5m MINIMUM FROM KERBLINES

CONTRACTOR TO BE AWARE OF AND TAKE APPROPRIATE ACTION TO ENSURE DE-STABILISATION OF ANY EXISTING STRUCTURES, TREES, EMBANKMENTS OR OTHER FEATURES DOES NOT OCCUR AS A RESULT OF ANY EXCAVATIONS WORKS UNDERTAKEN IN ACCORDANCE WITH THE DESIGN SHOWN ON THIS DRAWING. IF CONTRACTOR IS UNSURE ABOUT ANY ASPECT OF THE ABOVE HE SHOULD SEEK ADVICE BEFORE COMMENCING EXCAVATION WORK.

ALL STORAGE MANHOLES ON THE TANK SEWER WILL NEED TO BE CONCRETE SURROUNDED AS THEY ARE WATER RETAINING.

THE OFF SITE SEWER CONNECTION(S) HAVE BEEN DESIGNED TO TIE IN WITH THE EXISTING SEWERS AND WHILST IT IS ANTICIPATED NO CLASHES WITH EXISTING SERVICES WILL OCCUR, DUE TO THE INHERENT INACCURACIES IN DEPTHS OF EXISTING SERVICES THIS CANNOT BE GUARANTEED

REFA WOULD ADVISE THE CLIENT TO EMPLOY A SUITABLY EXPERIENCED COMPANY TO UNDERTAKE A SURVEY ALONG THE ROUTE OF THE CONNECTIONS TO ASCERTAIN THE EXISTENCE AND PROXIMITY OF ANY SERVICES AND ADVISE REFA OF ANY POTENTIAL CLASHES TO ASCERTAIN IF DESIGN CHANGES NEED BE MADE.

DUE TO THE NEED FOR OFF SITE SEWER WORKS IT IS STRONGLY ADVISED THAT THESE INVESTIGATIONS ARE UNDERTAKEN PRIOR TO ANY CONSTRUCTION ON SITE TO ALLOW DESIGN CHANGES TO BE MADE.

REFA WILL NOT BE HELD RESPONSIBLE FOR ANY ABORTIVE WORKS IF THIS PROCEDURE IS NOT FOLLOWED

ALL EXISTING MANHOLE INVERT LEVELS ARE TO LOCATED AND SURVEYED PRIOR TO START ON SITE TO ENSURE THAT THEY ARE CORRECT AND ALSO TO ENSURE THAT LEVEL CLASHES ARE AVOIDED AND THAT INTERPOLATED INVERT LEVELS ARE CORRECT. ANY DISCREPANCY TO BE REPORTED TO REFA PRIOR TO START TO ENABLE ANY CHANGES TO BE MADE TO DESIGN THAT PROVE NECESSARY

## CIVILS DESIGN RISK MANAGEMENT

Abnormal or unusual residual risks associated with the design outcomes shown on this drawing are:-

- EXISTING SERVICES
- WORKING ON EXISTING HIGHWAY AND IN AREAS WHERE MEMBERS OF PUBLIC MAY HAVE ACCESS
- DANGER OF COLLAPSE TO ALL EXCAVATIONS - RISK TO BE ASSESSED AND MANAGED BY CONTRACTOR IN ACCORDANCE WITH HSE GUIDANCE
- WORKING ADJACENT TO EXISTING WATERCOURSE OR LIVE FOUL SEWER (WELL'S DISEASE)
- WORKING ADJACENT TO EXISTING GAS MAIN. ALL WORKS WITHIN EASEMENT TO BE TO STATUTORY BODIES GUIDANCE
- WORKING ADJACENT TO EXISTING ADOPTED SURFACE WATER SEWER

REFA Ltd has followed its Design Risk Management process for Hazard Elimination and Risk reduction in developing the designs shown on this drawing. Abnormal or unusual residual risks may be shown above where it is considered that such risk may not normally be expected by competent persons engaged on work of this nature or type

PLEASE NOTE THAT THIS DRAWING IS ISSUED FOR INFORMATION/TENDER PURPOSES ONLY UNTIL TECHNICAL APPROVAL HAS BEEN GRANTED. ANY WORK UNDERTAKEN PRIOR TO TECHNICAL APPROVAL BEING GRANTED IS AT THE CLIENTS RISK.

SCALE IN METRES  
0 5 10 20 30 40 50

BENCH MARK INFORMATION  
Refer to Topographical survey by others

IF THE CLIENT OR CONTRACTOR IDENTIFIES ANY DISCREPANCIES BETWEEN THE DRAWINGS PRODUCED BY REFA FOR THIS PROJECT THEN THEY SHOULD CONTACT REFA IMMEDIATELY AND BEFORE ANY WORKS COMMENCE OR PROCEED IF IN DOUBT ASK !!!

PROPOSED SURFACE WATER SYSTEM DESIGNED TO CATER FOR EVENTS UP TO AND INCLUDING THE 1% AEP + 45%CC 10% URBAN CREEP TO PRIVATE AREAS WITH NO PREDICTED SURFACE FLOODING.

TOTAL SURFACE WATER DISCHARGE RATE FOR FULL FULL DEVELOPMENT IS RESTRICTED TO GREEN FIELD GBAR FIGURE = 21.7L/SEC.

## HYDROBRAKE INFORMATION

| HYDROBRAKE DETAILS     |                         |
|------------------------|-------------------------|
| MH No.                 | SHB1                    |
| TYPE                   | SHB-0441-1370-1700-1370 |
| DESIGN HEAD (m)        | 1.1                     |
| MAX. FLOW (litres/sec) | 137.0                   |
| ORIFICE DIA. (mm)      | 441                     |
| SURROUNDING SURFACE    | YES                     |

| HYDROBRAKE DETAILS     |                         |
|------------------------|-------------------------|
| MH No.                 | SHB2                    |
| TYPE                   | SHB-0100-2170-2100-2170 |
| DESIGN HEAD (m)        | 2.1                     |
| MAX. FLOW (litres/sec) | 217                     |
| ORIFICE DIA. (mm)      | 190                     |
| SURROUNDING SURFACE    | YES                     |

ATTENUATION POND TO CATER FOR ALL EVENTS UP TO AND INCLUDING 1 IN 100 YEAR +45%CC EVENTS.  
BASE LEVEL = 119.550m AOD  
TOP WATER LEVEL 120.534m AOD  
LOWEST BANK LEVEL 121.050m  
GIVING 510mm FREEBOARD.  
1 IN 3 SIDE SLOPES

REINFORCED EARTH SLOPES REQUIRED TO POND AREA TO SPECIALISTS DESIGN

EXISTING GAS MAIN  
15m EASEMENT IN PLACE FOR EXISTING GAS MAIN.  
ALL AS-BUILT LEVELS OF GAS MAIN TO BE CONFIRMED.  
PW & SW SEWERS ARE PASSING UNDER THE GAS MAIN.  
CONSENT REQUIRED FROM THE RELEVANT STATUTORY BODIES.  
ALL SIDES AND LEVELS TO BE CHECKED BY CONTRACTOR BEFORE ANY ON SITE SEWERS ARE LAID TO ENABLE DESIGN CHANGES TO SEWER TO BE MADE AS REQUIRED

SURFACE WATER SEWER  
EXISTING INVERT LEVEL = 119.300m (300mm) TAKEN FROM OFF-SITE DESIGN BY OTHERS. TO BE CHECKED BY CONTRACTOR BEFORE ANY ON SITE SEWERS ARE LAID TO ENABLE DESIGN CHANGES TO BE MADE AS REQUIRED

FOUL SEWER  
EXISTING INVERT LEVEL = 117.800m (150mm) TAKEN FROM OFF-SITE DESIGN BY OTHERS. TO BE CHECKED BY CONTRACTOR BEFORE ANY ON SITE SEWERS ARE LAID TO ENABLE DESIGN CHANGES TO BE MADE AS REQUIRED

THIS DRAWING IS BASED ON PLANNING LAYOUT PROVIDED BY CLIENT  
DRAWING NUMBER: BHM302/SK01  
REVISION: L  
CLIENT TO ENSURE THE ABOVE LAYOUT IS CURRENT BEFORE USING THIS DRAWING FOR CONSTRUCTION PURPOSES

# GENERAL

- All adoptable sewers and associated works are to comply fully with "Design and Construction Guidance" & Local Practices
- All highway works to be to adoptable standards and to comply fully with the Local Authority specification.
- All private drainage works are to comply fully with part H of the Building Regulations
- All existing invert levels to be checked by the Contractor at the start of works and any discrepancies notified to REFA. All levels are based on topographical survey information provided by others.
- All materials to bear the relevant B.S./Kitemark and comply fully with the specifications. All concrete & concrete products must use Sulphate resistant cement (unless the site investigation report proves that sulphate attack from soils and groundwater will not occur)
- All opening notices etc. as required under highways acts etc. are to be obtained prior to commencement of works. All works are to be inspected by L.A., NHBC or Relevant Water Authority as applicable.

## CDM REGULATIONS 2015

In line with the above regulations we are obliged to inform the Client of their responsibilities under section CDM 15/1, and residual risks that may be encountered in the construction of these works. All design work has been carried out with Health and Safety aspects given full consideration. Wherever possible risks have been eliminated from the design, however due to the very nature of this type of work it is not possible to remove all the risks from the design. We would also respectfully remind the Client of his obligations to take all reasonable steps in ensuring that only competent Contractors who have a valid safety policy are employed. They should also provide satisfactory responses at tender stage as to the manner in which they will deal with the elements of risk involved in this type of work and in particular those highlighted by REFA below:-

- Support / treatment for ALL excavation work.
  - Guarding to edges of excavations to prevent people, materials and vehicles falling into excavation.
  - Guarding of excavations outside working hours to prevent unauthorised access.
  - Undermining to adjacent roads or structures.
  - Confined space operations.
  - Dealing with existing services.
  - Traffic management on existing highways.
  - Procedure to be followed in event of accident or emergency.
  - Method of working where contaminated ground is present on site.
  - Confirmation will be required that all operatives are adequately trained, copies of relevant training certificates to be supplied.
- The above list is by no means exhaustive but it does highlight operations that present a risk to contractors and the general public. For clarification on any item please contact REFA.

|   |                                                          |    |          |
|---|----------------------------------------------------------|----|----------|
| D | BACKDROPS ADDED TO S2 AND S4 DRAG OUTS - RETAINERS ADDED | EB | 15.04.25 |
| C | F1 POSITION REVISED. PLOT 10-11 FFL REVISED              | RF | 08.04.25 |
| B | REVISED FFL'S                                            | EB | 31.03.25 |
| A | REVISED TO NEW LAYOUT REV N                              | RF | 25.02.25 |

| rev | Revision details | RevBy | Date |
|-----|------------------|-------|------|
|     |                  |       |      |

| worksafe designer SSIIP SAFETY SCHEMES IN PROCUREMENT |  |
|-------------------------------------------------------|--|
| www.smasistd.com                                      |  |

| Drawing Status |             |
|----------------|-------------|
| Draft          | Comments    |
| Issued         | Information |
|                | Approval    |
|                | As Built    |

Client

RUSSELL HOMES

Job title  
HARESHILL ROAD,  
SOUTH HEYWOOD - PH6

Drawing title  
ROAD & MAIN  
DRAINAGE LAYOUT

REFA CONSULTING ENGINEERS  
CIVIL • STRUCTURAL  
GEOTECHNICAL • ENVIRONMENTAL

45 Bridgeman Terrace  
Wigan, Lancs  
WN1 1TT  
Tel: (01942) 826020  
Fax: (01942) 230816

|            |             |       |       |       |    |
|------------|-------------|-------|-------|-------|----|
| Date       | 13.02.25    | Scale | 1:500 | Drawn | RF |
| DRAWING No | 24183/100/1 | Rev   | D     |       |    |

© This drawing is the property of REFA and should not be copied, used or its contents divulged without prior written consent.