

ref	hazard	date

 CAREFULLY REMOVE LOOSE/SPALLING STONE AND RE-DRESS TO MATCH ADJACENT STONEMWORK AND TO CLEAN STRAIGHT LINE.

 CAREFULLY CUT OUT COMPROMISED STONE WORK AND INSTALL NEW STONE WORK TO MATCH EXISTING.

 RESIN / STITCH REPAIR TO STONE OR COPING

INDENT REPAIR TO THE STONEMWORK. REQUIREMENT FOR INDENT WORKS TO BE REVIEWED ON SITE WITH CONTRACTOR PRIOR TO WORKS COMMENCING.

NEW LEAD COVER FLASHING CUT INTO THE STONE - ROOF PLAN - (SEE DETAILS).

LOCALISED DEEP PACKING AND REPOINTING TO OPEN JOINT IN BRICKWORK, ENSURE PERPS ARE KEPT OPEN AT MAX 900C/C. INSERT PERP VENTS.

— OPEN MOVEMENT LINE / DISPLACEMENT.

AREA TO BE CAREFULLY RAKED OUT AND RE-POINTED TO BRICKWORK.

ALL STONework POINTING TO BE CAREFULLY
RE-POINTED (SEE SPECIFICATION AND NOTES)

WORKS TO IRONWORK/GUTTERS (READ WITH DRAWINGS 2215.57.403,404 & 405.

THIS SECTION OF THE ENTRANCE
GABLE AND PIERS IS TO BE
DISMANTLED AS DETAILS AND TO
ENGINEER'S DETAILS. STONE
REPAIRS AS NOTED

THIS SECTION OF THE ENTRANCE
GABLE PIERS IS TO BE DISMANTLED
AS DETAILS AND TO ENGINEER'S
DETAILS. STONE REPAIRS AS NOTED

WF02

WF02

WF06

← THIS SECTION OF THE ENTRANCE GABLE AND PIERS IS TO BE DISMANTLED AS DETAILS AND TO ENGINEER'S DETAILS. STONE REPAIRS AS NOTED

WFO4

LEVEL 1

LEVEL 1

LEVEL 1

LEVEL 1


LEVEL 0

LEVEL C

LEVEL C

LEVEL C

SECTION D-D



P2	TEXT RE-SIZED	AGR	09.11.23
P1	INNITAL ISSUE		
ref	revision	by	date



Architects
Consulting Engineer
Quantity Surveyors

21 Silverwell Street
Bolton
BL1 1PR
t: 01204 525321
email@bghbolton.co.uk
www.bghbolton.co.uk

Bradshaw Gass & Hope LLP

client

Rochdale Borough Council

project

Milnrow Library, 57 Newhey Road,
Milnrow, Rochdale OL16 3NP

drawing

EXISTING SECTIONS A-A TO D-D
PROPOSED WORKS

drawn by	AR	date	APR 2023
checked by	AR	date	APR 2023

scale	1:20	A1
dwg no	2215.57.406	rev P2