AS PROPOSED ELEVATIONS



As Proposed Front Elevation A

11560



As Proposed LHS Elevation (C)



As Proposed RHS Elevation (D)



As Proposed Rear Elevation (B)

Note:
Contractor is to verify all dimensions and levels on site prior to site works commencement. Under no circumstances are any dimensions or levels to be scaled from this drawing number for the purpose of manufacturing components. Contractor to report any discrepancies to the Designer.

PROPOSED MATERIALS KEY:

1. Coursed Sandstone Masonry Walls.
2. New Slate Roof Tile Covering (Grey).
3. uPVC framed triple glazed windows (Grey).
4. uPVC framed triple glazed Bi-folding doors (Grey).
5. uPVC Composite External Front Door (Grey).
6. Velux Rooflights (Black).
7. Composite Garage Door (Grey).
8. uPVC fascia and rainwater goods (Black).
9. Coursed Sandstone Saw-cut Window Cills and Heads.
10. Sandstone Masonry Wall and Oak Framed Storm Porch.
11. New Code 7 Led Dressed Dormer Cheeks with Hipped Roof
12. uPVC framed Obscured glazed windows (Grey).

REVISION	DESCRIPTION	DATE
A	PLANNING	MAR 21

SCALE		SIGNATURE	DATE
1:50	DRAWN	TB	MAR 2021
ORIGINAL SIZE A1	CHECKED	MAB	MAR 2021
	APPROVED	MAB	MAR 2021

This drawing is copyright and may not be reproduced or made use of unless expressly agreed by M Bradbury Consulting Ltd

CLIENT

The Bungalow
Hillcrest Road
Rochdale
OL11 2QB

PROJECT

New Build Dormer Bungalow

Bradbury CONSULTING CHARTERED SURVEYORS
59 Wilmslow Road, Handforth, Cheshire, SK9 3EN
WEB: www.bradbury-consulting.co.uk TEL: 01625 522 209

TITLE

AS PROPOSED ELEVATIONS

JOB NUMBER

2020.075

DRAWING NUMBER

PL07