30 NO. CEANOTHUS REPENS
40 NO. CHOISYA DEWITTEANA
30 NO. SKIMMEA JAPONICA
17 NO. EUONYMUS FORTUNEI EMERALD AND GOLD
16 NO. CEANOTHUS REPENS

12 NO. PIERIS JAPONICA
12 NO. VIBURNUM DAVIDII
40 NO. EUONYMUS FORTUNEI EMERALD AND GOLD

18 NO. VIBURNUM DAVIDII
55 NO. EUONYMUS FORTUNEI EMERALD AND GOLD

55 NO. CEANOTHUS REPENS

30 NO. SKIMMEA JAPONICA
22 NO. PIERIS JAPONICA
16 NO. SKIMMEA JAPONICA

30 NO. SKIMMEA JAPONICA
24 NO. VIBURNUM DAVIDII

60 NO. CEANOTHUS REPENS

18 NO. CEANOTHUS REPENS
20 NO. AUCUBA JAPONICA
26 NO. CHOISYA DEWITTEANA
26 NO. CEANOTHUS REPENS

28 NO. AUCUBA JAPONICA
33 NO. CHOISYA DEWITTEANA
10 NO. AUCUBA JAPONICA

33 NO. CHOISYA DEWITTEANA
40 NO. PITTOSPORUM TENUIFOLIUM
30 NO. PITTOSPORUM TENUIFOLIUM
28 NO. SKIMMEA JAPONICA

H3 50M
H3 80M

N

0m 10m 20m
SCALE 1:200

## KEY:

- PROPOSED SPECIMEN TREE
  SPECIES AS ANNOTATED
  REFER TO PLANT SCHEDULE FOR SPECIFICATION AND CODE
- PROPOSED AMENITY SHRUB PLANTING
  HATCHES DENOTE SPECIES SEPARATION
  SPECIES AS ANNOTATED - SEE PLANT SCHEDULE FOR SPECIFICATION
- PROPOSED LAWN AREAS TO BE TURFED
  CLIENT MAY OPT TO SEED LARGER AREAS
- PROPOSED SPECIES RICH LAWN TO PUBLIC OPEN SPACE
  TO BE SOWN WITH MIX 'PRO FLORA 3 - DAMP SOILS FROM DLF OR SIMILAR APPROVED SOWING RATE 5 G/M$^2$ IN ACCORDNACE WITH DLF RECOMMENDATIONS
- H1 PROPOSED ORNAMENTAL HEDGE TYPE 1
  DENSITIES AS PER PLANT SCHEDULE
  BUXUS SEMPERVIRENS 4 PLANTS/LIN M
- H2 PROPOSED ORNAMENTAL HEDGE TYPE 2
  DENSITIES AS PER PLANT SCHEDULE
  GRISSELINEA LITTORALIS 3 PLANTS/LIN M
- H3 NATIVE HEDGEROW - HEDGE TYPE 3
  SEE PLANT SCHEDULE FOR SPECIES MIX AND SPECIFICATION
  PLANTED AT 5 PLANTS/LIN M IN A DOUBLE STAGGERED ROW

SOFT LANDSCAPE SPECIFICATION NOTES:

- ALL PLANTING/TURF AREAS TO BE PREPARED BY REMOVING ANY DETRITUS/CONSTRUCTION MATERIALS AND STONE/ROCK/BRICK GREATER THAN 40MM DIAM. AREA SHALL BE CLEARED OF WEEDS USING A TRANSLOCATED HERBICIDE AND CULTIVATED TO A DEPTH OF 300MM. WHERE EXISTING SOIL IS POOR QUALITY TOPSOIL SHALL BE IMPORTED.
- ALL PLANTS SUPPLIED SHALL COMPLY WITH BS3936: PARTS 1 TO 10 AS RELEVANT, BS 4043 AND THE NATIONAL PLANT SPECIFICATION, PUBLISHED BY THE HORTICULTURAL TRADES ASSOCIATION.
- ALL LAWN AREAS TO BE CULTIVATED TO A DEPTH OF 150MM PRIOR TO LAYING OF TURF. IF THE EXISTING SOIL IS POOR QUALITY - TOPSOIL SHOULD BE IMPORTED.
- ALL SHRUB PLANTING AREAS TO RECEIVE A 50MM LAYER OF ORGANIC SOIL CONDITIONER (GRO CHAR OR SIMILAR APPROVED) AND BE CULTIVATED TO A DEPTH OF 300MM PRIOR TO PLANTING.
- ALL IMPORTED TOPSOIL MUST COMPLY WITH BS 3882:2015
- ALL PLANTS ARE TO RECEIVE SLOW RELEASE FERTILISER TO THE PITS. SIDES OF PITS TO BE LOOSENED PRIOR TO PLANTING.
- ALL PLANTS TO BE WELL WATERED IN AT PLANTING.
- ALL PLANTING AREAS TO BE MULCHED WITH 75MM TO 100MM DEPTH OF BARK CHIP.


**Squareyard**
Landscape Architecture - Urban Design - Masterplanning

Email - studio@yd2.co.uk
Web - www.yd2.co.uk
Tel - 07514 281 452

Address:
Suite 10 - Hardman Business Centre,
New Hall Hey Road,
Rossendale


**GENERAL NOTES:**

1. DIMENSIONS GOVERN
2. ALL DIMENSIONS ARE IN MILLIMETERS UNLESS NOTED OTHERWISE ON THE DRAWINGS
3. ALL DIMENSIONS SHALL BE VERIFIED ON SITE PRIOR TO ANY CONSTRUCTION
4. YD2 SHALL BE NOTIFIED OF ANY DISCREPANCIES

DRAWING NOTES:

| REV | DESCRIPTION | DRAWN | CHECKED | DATE |
|---|---|---|---|---|
| (-) | FIRST ISSUE - ISSUED FOR PLANNING APPLICATION | MG | AV | 02/07/2024 |

PROJECT TITLE
**CASTLETON SIDINGS**
ROCHDALE

DRAWING TITLE
**DETAILED PLANTING PLAN**
SHEET 4 OF 8

SCALE @ A1
1:200

DATE
JUN 2024

PROJECT NUMBER
YD2_22_015

DRAWING No.
YD2_CS_LP104

REVISION
(-)