

NOTE:
1. DO NOT SCALE OFF THIS DRAWING.
2. ANY DISCREPANCIES TO BE REPORTED IMMEDIATELY TO THE ARCHITECT.
3. ALL DIMENSIONS TO BE SITE CHECKED & VERIFIED BY THE CONTRACTOR PRIOR TO THE MANUFACTURE OR ORDER OF ANY MATERIALS OR GOODS.

MATERIALS KEY:
Proposed Materials

- 1
- Staffordshire blue blue brick (to match ex) laid in stretcher bond
- 2
- Curtain wall system with clear glazing
- 3
- Tental 60 with Flat Cap curtain walling with clear glazing, grey opaque glass spandrel panels and projecting orange ppc fins
- 4
- Grey coloured Flat Terracotta Tile 22mm thick. 900mm x 200mm
- 5
- Omitted
- 6
- Glazed Balustrade
- 7
- Curtain walling system with clear glazing and blanking panels
- 8
- GRC Concrete Columns
- 9
- Freestanding keyclamp Balustrade to roof
- 10
- PPC Aluminium External Fire Escape Door
- 11
- PPC Aluminium Louvred Vents Colour to match Terracotta Tile

Existing Materials

- a
- Blue/grey brick laid in stretcher bond
- b
- Grey terracotta rainscreen cladding, stack bonded
- c
- PPC aluminium framed window and curtain walling systems
- d
- Orange coloured transparent window film
- e
- SSG transoms
- f
- PPC aluminium coloured aerofoil fins - 300mm projection fixed to curtain walling mullions
- g
- Doubled glazed insulated spandrel panels
- h
- PPC aluminium louvre panels
- j
- High quality finish concrete encased steel columns
- k
- Roof lights

PR5	Louvres added to elevations	01.09.23
PR4	GA Elevations updated materials legend	31.08.23
PR3	Stage 4 Issue	23.08.23
PR2	General updated to stage 4 information	01.08.23
PR1	Updates to Sections and Elevations	03.07.23

Rev	Description	Date
-----	-------------	------

STAGE 4 - PRELIMINARY

Rochdale Sixth Form College
College Road, Rochdale, OL12 6HY

Detailed Elevations - North

DRAWING NUMBER
3940-ABW-ZZ-ZZ-DR-A-2821

DATE	REVISION	STATUS
07/03/23		
SCALE	PURPOSE OF ISSUE	
As indicated		

