notes:

1. DO NOT SCALE FROM THIS DRAWING - USE FIGURED DIMENSIONS ONLY.
2. TO BE READ IN CONJUNCTION WITH ALL OTHER CONSULTANTS / SPECIALISTS DRAWINGS. REPORT ANY DISCREPANCIES BEFORE AFFECTED WORK COMMENCES.
3. ALL SETTING OUT DIMENSIONS TO BE CHECKED ON SITE BY CONTRACTOR BEFORE WORK COMMENCES.




First Floor Existing and Removal Works

1. Renew roof coverings to bay as per drawing HOH-SEV-XX-XX-DR-A-04003

Rebuild section of wall. Allow for 6m$^2$ new.

New timber floor required to first floor and second floor. Floor is to be suspended off a wall plate with joist pockets filled in with masonary to match existing. Details as per S.E designs.

N

0 1 2 3 4 5

| REVISIONS | | | | | |
|---|---|---|---|---|---|
| C02 | CONSTRUCTION_ISSUE | 07/07/2022 | SMG | LM |
| C01 | CONSTRUCTION_ISSUE | 28/04/2022 | SMG | LM |
| T01 | FIRST_ISSUE | 30/11/21 | SMG | LM |
| | | DATE; | DRAWN; | CHECK |

| | |
|---|---|
| CLIENT | Rochdale Borough Council |
| PROJECT | HOH - Hopwood Hall |
| TITLE | Proposed First Floor Plan |
| NUMBER | HOH-SEV-XX-01-DR-A-02004 |
| REVISION | C02 |
| STATUS | CONSTRUCTION |
| SCALE | 1:100 @A1 |
| DATE | 16/11/21 |
| DRAWN BY | SMG |
| CHECKED BY | SG |

seven.

SEVENARCHITECTURE.CO.UK

Studios at :
Unit 1.3, Waulk Mill, 51 Bengal Street,
**MANCHESTER,** M4 6LN
**t :** 0161 236 5655

Clarendon House, Victoria Avenue,
**HARROGATE,** HG1 1DY
**t :** 01423 709 807

24 Greville Street,
**LONDON** , EC1N 8SS
**t :** 0203 036 0691