


File name: C:\USERS\GK12623\WSP\0365\03 SOUTH HEYWOOD - WORK IN PROGRESS\03 DRAWINGS\PRIMARY SUBSTATIONS\SOHW-PSS-ENAB-DR-D-0103.DWG, printed on 16 December 2024 16:01:45, by: Clete, Kyle



DO NOT SCALE

- NOTES
- DO NOT SCALE FROM THIS DRAWING.
 - DRAWING TO BE PRINTED IN COLOUR.
 - ALL DIMENSIONS ARE IN METRES UNLESS OTHERWISE STATED.
 - THE TOPOGRAPHICAL SURVEY UPON WHICH THIS DESIGN IS BASED HAS BEEN PROVIDED BY A THIRD PARTY AND SHOULD BE CHECKED ON SITE FOR ACCURACY.
 - THE WORKS SHALL BE CARRIED OUT IN ACCORDANCE WITH DESIGN MANUAL FOR ROADS AND BRIDGES SPECIFICATION FOR HIGHWAY WORKS.
 - FOR INFORMATION ON EXISTING STATUTORY UNDERTAKERS EQUIPMENT REFER TO UTILITY DRAWINGS. CONTRACTOR TO CONFIRM LOCATION OF ALL UTILITIES PRIOR TO CONSTRUCTION.

ELEVATIONS TABLE			
NUMBER	MINIMUM ELEVATION	MAXIMUM ELEVATION	COLOR
1	-2.578	-1.500	
2	-1.500	-1.000	
3	-1.000	-0.500	
4	-0.500	0.000	
5	0.000	0.500	
6	0.500	1.000	
7	1.000	1.500	
8	1.500	2.351	

UNTIL TECHNICAL APPROVAL HAS BEEN OBTAINED FROM THE RELEVANT LOCAL AUTHORITIES OR STATUTORY BODIES, IT SHOULD BE UNDERSTOOD THAT ALL DRAWINGS ARE ISSUED AS PRELIMINARY AND NOT FOR CONSTRUCTION. SHOULD THE CONTRACTOR AND / OR EMPLOYER COMMENCE WORK PRIOR TO APPROVAL BEING GIVEN, IT IS ENTIRELY AT THEIR OWN RISK

P03	16/12/2024	KC	SCALE BAR ADDED	DW	DW
P02	21/11/2024	DS	RETAINING WALL DETAILS UPDATED	DW	DW
P01	18/07/2024	DS	FIRST ISSUE	DW	DW
REV	DATE	BY	DESCRIPTION	CHK	APP

DRAWING STATUS: S2 - FOR INFORMATION



8 First Street, Manchester, M15 4GU, UK
T+ 44 (0) 161 200 5000
wsp.com

CLIENT: RUSSELLS SOUTH HEYWOOD LIMITED

ARCHITECT: AEW ARCHITECTS

SITE/PROJECT: SOUTH HEYWOOD PRIMARY SUBSTATION

TITLE: ENABLING WORKS
PROPOSED ISOPACHYTE ANALYSIS

SCALE @ A1: 1:500	CHECKED: DW	APPROVED: DW
PROJECT NO: 70103659	DESIGNED: SS	DRAWN: SS
DATE: NOVEMBER 24		REV: P03

DRAWING No: SOHW-WSP-PSS-ENAB-DR-D-0103

© WSP UK Ltd

CUT FILL ANALYSIS SUMMARY				
WORKS ELEMENT	AREA(sq.m)	CUT (Cu.m)	FILL (Cu.m)	NET (Cu.m)
Primary substation	6479	2006	1904	102(Cut)
Topsoil (Assumed depth 150mm)				
Topsoil to be stripped	6479	972	0	972(Cut)

