Caldershaw Centre
Caldershaw Centre
Development Site
Unmade
Concrete
Ramp
see insert for drainage survey to the N of this yard
150ø>>
IC
G
ST
BT
Tarmac
UU MH
CL: ~152.25
IL: ~148.57
<<600ø CO foul sewer
MH
CL: 152.19
IL: 147.09
<<900ø culvert
Wall
TP
I/R
UU MH 8506
CL: 149.28
IL: 145.62
<<300ø
exg 900 dia pc culvert, line confirmed by survey
<<900ø PCC culvert
exg 900 dia stone culvert line confirmed by survey
<<900ø sq stone culvert
stone /brwk MH a.2000x1200, IL 3900 bGL
MH chamber app. 2000 x 1200 x 3900dp
Caldershaw Mills Service Road
450 dia CO foul sewer
exg stone chamber app. 10000 x 1200 x 4500deep
u/g chamber, CL 147.1, IL 142.85
exg 150mm dia pvc land drain line and location unknown
exg 300 x 300 masonry culvert line and location unknown
Water seepage from from bank
assumed line of exg 900 dia stone culvert
assumed line of exg stone culvert
exg 900 dia stone culvert
exg 1400 dia stone culvert
<<900ø stone culvert
MH not connected to culvert below??
MH
CL: ??
IL: ??
<<100ø
<<225ø
<<225ø (900ø culvert at lower level
100ø>>
MH
CL to IL: 600
IC back drop chamber on to culvert.
CL:~153.55
IC IL: ~150.80 (2750)
culvert IL: 147.75 (5800)
Steps
Grass
Kerb

T J BOOTH ASSOCIATES
CONSULTING CIVIL & GEOTECHNICAL ENGINEERS

20A Eastgate Street
Rochdale
Lancashire
OL16 1DH
Tel:01706 868288

IQBAL / CALDERSHAW CENTRE

Existing drainage survey

FILE NAME dwg–tjba–iqbal–caldershaw centre–040913.dwg

SCALE: 1 : 250 @ A1

AMENDMENTS/ ISSUES

ISSUE	REASON/ CHANGE	DATE	BY
1	drainage survey jan 2017, insert added	feb 2017	ds
0	original for discussion	Jul 2014	ds