






The existing building measured survey has been undertaken by Salford Archaeology and all reference to this information is referenced directly from the associated drawings.

Coloured areas of hatch on interior elevations indicate proposed fixtures, fittings or built fabric, proposed to be inserted, as below:




Health and safety risk item



30 minute fire rated compartment line. -
Assumed existing structure meets 60
minutes fire compartmentation. Any
existing holes to be filled and new
penetrations to be sealed to meet 60
minutes requirement.

Existing fire compartment line (target 60 minutes fire rating). No modifications proposed. Any existing holes to be filled and new penetrations to be sealed to meet 60 minutes requirement.

All new wall construction to comply with required fire rating.



Asbestos: All known asbestos to be removed.

Risk of uncovering unknown asbestos during works.

Works to existing structure: All works to existing structure to be carried out in accordance with structural engineers details and to be sufficiently propped during works.

Existing services: All existing unused services to be removed.

[illegible][illegible]