





transport planning

t 0161 464 9495
e info@modetransport.co.uk
w www.modetransport.co.uk



Rochdale Refuse Vehicle
Overall Length 9.925m
Overall Width 2.450m
Overall Body Height 3.814m
Min Body Ground Clearance 1.366m
Track Width 2.450m
Lock to lock time 4.00s
Kerb to Kerb Turning Radius 9.500m



DB32 Fire Appliance
Overall Length 8.680m
Overall Width 2.180m
Overall Body Height 3.452m
Min Body Ground Clearance 0.337m
Max Track Width 2.171m
Lock to lock time 6.00s
Kerb to Kerb Turning Radius 7.910m

- notes:
1. this drawing is to be read in conjunction with all other relevant drawings, any discrepancies errors or omissions to be brought to the attention of overseeing organisation.
 2. all dimensions to be checked before commencement of work on site.
 3. all dimensions in metres unless otherwise stated.
 4. the design is subject to approval of rochdale council.
 5. drawing based on topographical survey.

issue/revision		
i/r	date	issued description
	23/08/2023	

client: kwick build ltd / tyson construction
project: former phoenix works
project number: J327673
scale: 1:500@A3
drawing title:
swept path analysis
drawing number:
J32-7673-PS-001