

NOTES




proposed rear elevation

proposed side elevation




proposed side elevation




proposed front elevation

porch side elev



proposed ground floor plan



proposed first floor plan

hipped roof member

new roof to comprise: blue/grey natural slates to match existing suitable for min. pitch 30° laid to manufacturer's recommendations on 25x38mm tsw, battens on glidevale vp400 protect underlay on 38x25mm tan s/w, battens on timber trussed rafters at 600mm ctrs fixed to manufacturers recommendations, 300mm quilt laid at right angles between and over over bottom cord of trussed rafter in two layers with 12.5mm plasterboard fixed to underside. to achieve u value of 0.15w/m²/K.


22mm T&G boarding on 175 x 50 C16 floor joists at 400mm ctrs with 12mm plasterboard & skim to u/s 100mm glass quilt sound insulation between floor joists with a density of 10-11kg/m3 to give min 40dB rating to whole of floor plate of extension

cavity wall construction to comprise; 100mm brickwork to external to match extg; 100mm cavity containing 90mm rigid board insulation Thermaclass Cavity Wall 21 or similar; 10mm residual cavity to be kept clear of mortar droppings ; 100mm topcrete standard cellular 7n blocks internally, blockwork to have 13mm plaster finish

dpc min 150mm above ground level

75mm thick proprietary quick drying screed with oriented strand reinforcement on building paper on 100mm GA4000 Celotex (or similar) rigid insulation on 125mm insitu concrete slab with A142 mesh reinforcement on zedex visqueen gas membrane on 50mm sand blinding on min. 150mm well consolidated hardcore in layers not exceeding 150mm. to acheive max u value of 0.18W/m².K.

foundations to consist of concrete strip footings to satisfaction of building control officer, dense concrete block work below ground level and cavities fully filled with foamglas insulation.



proposed section

Proposed Finishes
Walls - Roughcast render to match extg
Roofs - interlocking conc tiles and PVCu fascias and rainwater goods all to match extg
Windows & Doors - Double glazed PVCu to match extg

GENERAL BUILDING REGULATION NOTES

1. All work to be carried out to the satisfaction of the Local Authority.
2. 32x6mm M.S. straps to be fixed as lateral restraint to roof joist / wall/wall intersections (ie) where rafters run parrallel to walls to comply with Schedule 7.
3. Roof void to be vented to CP144 Part 3 1970.
4. Cavity barriers required to comply with Reg E.14.
5. Where new cavity walls meet existing, cavities are to be connected.
6. All cavities closed to comply with Bldg Regs.
7. All external door & window openings to have horiz & vertical dpc's.
8. Window sizes to give min 1/20th floor area of room for natural ventilation and 1/10th floor area of room for natural light.
9. Lintols to window & door openings to be patent metal combined lintols (Catnic CN12(b) or similar 3crs lintol.)
10. New rainwater goods to match existing (ie): hr gutters & rwp's into trapped gullies.
11. Existing heating system extended into new area.
12. All foundations to comply with Bldg Regs.
13. All foundations within 1m of drain to be taken down to invert of drain.
14. Roof ventilators to be provided at the abutment with any extg wall Reg F2
15. Coursing to match existing.
16. Concrete lintols to be provided in walls where drains pass through.
17. New drainage under building to be encased in 150mm min concrete.
18. New drainage to be 'Hepsleve' or similar using flexible joints.
19. All dimensions to be checked on site.
20. 12.5mm Fireline plasterboard to encase steelwork to 30mis fire resistanca

SPECIFICATION NOTES

FOUNDATIONS:
New foundations to be 600x150mm min thick strip footings taken down min 750mm below ground level

FLOOR TO NEW EXTENSION:
to comprise 75mm thick proprietary quick drying screed with oriented strand reinforcement on building paper on 100mm GA4000 Celotex (or similar) insulation board on 125mm insitu RC concrete slab on visqueen zedex 2000 gauge gas membrane on 50mm sand blinding on min. 150mm well consolidated hardcore in layers not exceeding 150mm. To achieve max u value of 0.18W/m².K.

EXTERNAL WALLS:
Cavity wall construction: 100mm brickwork externally to match existing; 100mm cavity containing 90mm rigid board insulation Thermadass Cavity Wall 21 or similar: 10mm residual cavity to be kept clear of mortar droppings; 100mm thick blockwork (7N/mm2 strength, 1400kg/m3 density, 0.51W/mK thermal conductivity); blockwork to have plaster finish internally all to achieve u value of 0.18w/m².k
All cavities to be closed at top of walls with rockwool rockclose and around openings with insulated thermabate cavity closers. stainless steel wall ties with insulation retaining clips at max. 750mm centres horiz and 450mm staggered centres vertically. hyload or similar dpc, cavity trays to all interruptions of cavity. New walls connected to existing walls with stainless steel movement connectors, bolted to existing and built into new walls.

ABUTMENT:
insert type X remedial cavity trays where new roofs abut existing walls and allow for weepholes at approx 900mm centres.

DPCs
Hyload or similar approved to new masonry walls at floor level and 150mm min. above ground level.

WINDOWS/DOORS:
New external Pvcu to be double glazed.(colour to match extg). New window/doors to comply with requirements of Parts K and L1b of the Building Regs with safety glazing to be used in critical locations to comply with Approved Doc and BS 6206. Emergency egress windows to be provided as required to new bedrooms. windows should have a minimum openable area equal to 0.33m² with a minimum dimension of 450mm (eg 735 x 450mm). The bottom of the openable window area should not be more than 1100mm above the finished floor level.

SPACE AND WATER HEATING:
Existing radiator system to be adapted as necessary to provide heating to new extension from the extg house. All pipework to be insulated. heating to be thermostatically controlled. Heating system to comply with part L1b of the building regulations.

ELECTRICAL WORK:
Modify extg electrical installation into new extension including new low wattage light fittings each with each lamp having a min luminaire efficacy rating of 75 light source lumens per circuit-watt, power sockets, and where specifically requested television outlets, telephone outlets, and security system as required. All switches and sockets to be installed in habitable rooms are to be between 450mm and 1200mm above floor level.All electrical work must be carried out to meet the requirements of Building Regulations Part P by a person competent to do so. Prior to completion either an electrical installation certificate issued under an Approved Competent Person Scheme, or an electrical installation certificate signed by a person competent to do so, should be provided to Building Control.

HEATING APPLIANCES:
Any work to heating appliances to be carried out by a registered Gas Safe engineer.

VENTILATION:
Windows to be min size of 1/10th floor area of room with opening lights to equal min 1/20th floor area.
VENTILATION: Mechanical ventilation system to be of an energy efficient type in compliance with Table 3.
" rooms with no windows or opening lights - fans to have 15min overun fitted/ Windowless rooms - fans to operate off main light switch." Replacement air to be provided to rooms with fans by 10mm undercut under door.Extract fans giving air flow of 6L/S to WC & 15L/S to bathroom.

CONSERVATION OF FUEL AND POWER:
Alterations to be designed in accordance with the latest edition of building regulations approved document L1B

ABOVE GROUND DRAINAGE:
- All traps to have min. 75mm deep seal. All wastes to connect to either Soil and Vent Pipe or Stub Stack, or discharge into trapped gully.- Provide new uPVC gutters (to match extg), mounted level and discharging to new rainwater pipe's, connected directly Into surface water trapped gullies.

BELOW GROUND DRAINAGE:
- Start of new drains to be either a gully or rest bend (from SVP). New drains to be clay pipes with flexible joints, and be nominally 100mmØ. Pipes to be bedded and backfilled with granular material to BS882, and generally laid to falls of 1:80. Drains passing under building to be encased all around with 100mm concrete if within 300mm of u/s of slab. For drains that pass through walls provide openings in wall with r.c. lintels to all leaves, to give 50mm clear space around pipe, to be filled with compressible fill to prevent gas entry.

NEW EXTENSION ROOF: new roof to comprise: interlocking conc tiles to match existing suitable for min. pitch 30° laid to manufacturer's recommendations on 25x38mm tsw, battens on glidevale vp400 protect underlay on 38x25mm tan s/w, battens on timber trussed rafters at 600mm ctrs fixed to manufacturers recommendations, 300mm quilt laid at right angles between and over over bottom cord of trussed rafter in layers with 12.5mm plasterboard fixed to underside. to achieve u value of 0.15w/m²/K. Proprietry mechanical fixed dry rifge and verge tiles to be used in accordance with BS 5534:2014 also providing ventilation to BS5250. Proprietry eaves vents to be provided

ELECTRICAL WORK:
Modify extg electrical installation into new extension including new low wattage light fittings, power sockets, and where specifically requested television outlets, telephone outlets, and security system as required. All switches and sockets to be installed in habitable rooms are to be between 450mm and 1200mm above floor level.All electrical work must be carried out to meet the requirements of Building Regulations Part P by a person competent to do so. Prior to completion either an electrical installation certificate issued under an Approved Competent Person Scheme, or an electrical installation certificate signed by a person competent to do so, should be provided to Building Control.

HEATING APPLIANCES:
Any work to gas heating appliances to be carried out by a registered Gas Safe engineer.

CONSERVATION OF FUEL AND POWER:
Alterations to be designed in accordance with the 2022 amendments of building regulations approved document L1B

ABOVE GROUND DRAINAGE:
- All traps to have min. 75mm deep seal. All wastes to connect to either Soil and Vent Pipe or Stub Stack, or discharge into trapped gully.- Provide new uPVC gutters (to match extg), mounted level and discharging to new rainwater pipe's, connected directly Into surface water trapped gullies.

Two storey rear extension to be in accordance with Guidelines & Standards for Residential Development SPD (Page 15 refers)

Structural calculations to be submitted and approved before commencement

Note It is the responsibility of the contractor to determine the location and direction of the existing drainage through excavation and provide new pipework to connect new to existing. Full drainage system on site is to be identified at time of excavation. If combined or separate systems are found that system is to be maintained during and after construction. All re-routing and any new drainage layouts are to be approved by BCO prior to laying of any drains.
RWP's into new trapped gullys and connected into extg drainage

Smoke/Fire Protection
Ceiling mounted self contained, interlinked smoke detectors to be fitted to Ground floor hallway and first floor landing and heat detector fitted within kitchen area. Detectors to be permanently hard wired to separate fused circuit on distribution board. Detectors to be fitted within 7 metres of doors to kitchen and lounge and within 3 metres of doors to bedrooms, and at least 300mm from any wall or light fitting. Detectors to have standby power and conform to BS 5466. Detection and alarm systems to be in accorance with BS 5839-6 2004 to Grade D Category LD3 Standard.

Construction Details
Continuity of insulation and limiting air leakage to be in accordance with DEFRA Robust Building Details. All materials to be fitted in accordance with manufacturers instrucctions. Roof insulation to be laid over top course of blockwork and wall insulation continued up to top of wall to meet roof insulation. Wall insulation batts to be tightly butted up to each other and to cavity closer. Service penetrations to be cored drilled to minimise damage to insulation and hole oversize kept to a minimum to provide snug fit. All penetrations to be sealed all round with a mastic sealant to junctions of plaster finishes, windows boards and frames.

REV	DESCRIPTION	CHECK	DATE

CLIENT
Mrs PF Faiz
350, Albert Royds Street, Rochdale. OL16 5AD

PROJECT
Construct new porch/extension and erect a single/ two storey rear extension & demolish extg outbldg and erect new outbuilding for gym / games room

DRAWING
Proposals

SCALE	DATE	DRAWN	CHECKED
1:50 @ A1	Sept 2024	rb	

DRAWING NO.	CAD REFERENCE NO.	REVISION
2427/PFF/02		