

Our Ref: 4847/TW.23

Pack Horse Public House, Birtle, BL9 7TU.

Tree Ref No.	Species	Work
G1	Sycamore and Ash	Fell. Stump management to be agreed.
1	Sycamore	Remove all dead wood.
2	Sycamore	Remove all dead wood.
3	Sycamore	Remove all dead wood.
4	Sycamore	Remove all dead wood.
5	Ash	Remove all dead wood.
6	Sycamore	Crown lift removing the epicormic growth up to the fork on the southern canopy.
7	Sycamore	Crown lift to give 8m clear stem height to the south over the roof. Remove all dead wood.
8	Sycamore	Remove epicormic growth to give 3m clear stem height.
9	Sycamore	Remove epicormic growth around the base of the stem.
10	Sycamore	Remove epicormic growth including that growing through the timber fence.
12	Sycamore	Remove all dead wood.
13	Sycamore	Fell. Stump management to be agreed.

Notes

Works in accordance with BS3998 – 2010

Not for planning control.

Any defects are to be reported to ACS Consulting – 01565 755422

No deviation from the specification without written consent.

General Risk Assessment and Method Statement to be supplied. Bat risk assessment to be supplied

Crown cleaning i.e. removal of any dead, diseased, broken or rubbing branches that were found.