


S106 Part 1 'Application to connect to a public sewer' Approval Notice



United Utilities Reference Number:		03725693				
Applicant details						
Applicant name	Paul Graveney					
Applicant address (including postcode)	Paul Graveney Consulting Ltd 108 Ack Lane West Cheadle Hulme Cheshire SK8 7ES					
Applicant email	paul@pgcl.co.uk					
Site details: The site / property which is proposed for connection to the public sewer						
Site address (including postcode)	Land off Noon Sun Street, Rochdale, OL12 0RP – BLOCK C					
APPROVED Your application for connection to the public sewer has been approved, to be made via a new connection:						
To a private drain	☐	You may appoint your contractor and advise your appointed building control body (who should inspect the work). United Utilities should be advised when this work is complete.				
Direct to the public sewer	☒	Further action required. You may now appoint an appropriately qualified contractor. Your appointed contractor is responsible for obtaining authorisation to work on a public sewer. (The S106 Part 2 application form 'Request for permission to work on a public sewer' is available on our website; Sewer connections - United Utilities).				
Mode of connection approved	Junction					
Sewer connection type	Foul	☐	Surface water	☐	Combined	☒
This approval is valid for 12 months from the date below. This approval does not grant access to third party land, permission should be sought if required between applicant and land owner. If the new connection renders access unsafe or is otherwise detrimental to the manhole or sewer, a new/upgraded manhole will be requested.						
Comments						
Approval granted for a 100mm combined connection via a preformed 'Y' type junction on the 225mm combined sewer located within Noon Sun Street. The preformed junction should be a 'Y' type laid in the direction of flow. 'T' type junctions are not acceptable. Please see details included in the Sewer Connection Pack. For low-lying sites, (where the ground level of the site or the level of a basement is below the ground level at the point where the drainage connects to the public sewer), care should be taken to ensure that the property is not at increased risk of flooding. If these circumstances exist it could affect the detailed design of your site and result in the need to incorporate appropriate mitigating measures in your drainage scheme. Please note, if you are proposing to connect to an existing, unchartered drain or sewer then it is the developer's responsibility to confirm that it communicates with the Public Sewer Connections may be made to private lateral drains or to existing neighbouring drain. A part 1 approval does not give permission to access third party land. The applicant must seek permission from the relevant landowner.						



Developer Services Inspector	Shelley McNamara
Contact number	07825 358095
Date	03/05/2024