

ELLUC Projects Ltd

- Consultancy
- Project Management
- Site Regeneration

Revision	Date	Purpose/Stat	Author	File Ref	Check	Review
F1	10/04/2024	Draft	Erin Thomas		Dave Wood	Dave Wood
F2	24/06/2025	Approval	James Carrino		Dave Wood	Dave Wood
F3	10/07/2025	Approval	James Carrino		Dave Wood	Dave Wood

This document has been prepared in accordance with the scope of ELLUC Projects appointment with its client and is subject to the terms of the appointment. It is addressed to and for the sole use and reliance of ELLUC Projects' client. ELLUC Projects accepts no liability for any use of this document other than by its client and only for the purposes, stated in the document, for which it was prepared and provided. No person other than the client may copy (in whole or in part) use or rely on the contents of this document, without the prior written permission of ELLUC Projects Limited. Any advice, opinions, or recommendations within this document should be read and relied upon only in the context of the document as a whole. The contents of this document are not to be construed as providing legal, business or tax advice or opinion.

© ELLUC Projects Limited 2020

Document Details

Last saved	10/04/2024
Path	ELLUC-MD-24018-FRA
Author	Erin Thomas
Project Number	24018
Project Name	Trubs Farm, Rochedale

Contents

Table of Contents

Abbreviations	3
1.0 Introduction	5
2.0 Planning Policy.....	6
3.0 Requirements of a Flood Risk Assessment.....	9
4.0 Sequential Test	11
5.0 Site Context	12
6.0 Proposed Development.....	14
8.0 Flood Hazards & Sources of Flooding	25
11.0 Climate Change	29
12.0 Conclusions & Recommendations.....	30

Appendices

APPENDIX A	Extract from NPPF – Flood Risk
APPENDIX B	Topographical Survey
APPENDIX C	Drainage Layout
APPENDIX D	SuDS Information

ABBREVIATIONS

Term	Meaning / Definition
------	----------------------

AEP	Annual Exceedance Probability
BGL	Below Ground Level
BGS	British Geological Society
CFMP	Catchment Flood Management Plan
CIRIA	Construction Industry Research and Information Association
CoP	Code of Practice
EA	Environment Agency
EFO	Extreme Flood Outline (Boundary of floodplain associated with a flood event with a probability of occurrence of 0.1%, 1 in 1000 years)
FDA	Flood Defence Agency (e.g. Environment Agency)
FERS	Flood Event Recording System
FFL	Finished Floor Level
FRA	Flood Risk Assessment
FW	Foul Water
GPZ	Groundwater Protection Zone
LDD	Local Development Document
LDF	Local Development Framework
LHA	Local Highway Authority
LPA	Local Planning Authority
m AOD	Metres above Ordnance Datum
MAF	Mean Annual Flood
NGR	National Grid Reference
OS	Ordnance Survey
PPG	Planning Policy Guidance
PPS	Planning Policy Statement
SFRA	Strategic Flood Risk Assessment
SSSI	Site of Special Scientific Interest
SuDS	Sustainable Drainage Systems
SW	Surface Water
WFD	Water Framework Directive

INTRODUCTION

PURPOSE OF THIS REPORT

MCI Developments are proposing a new residential development on Trubs Farm, Rochedale. Total area of the site is approximately 4.8ha.

The Local Planning Authority has requested that a Flood Risk Assessment (FRA) is undertaken to assess the risk of flooding to the site.

ELLUC Projects Limited has been commissioned by MCI Developments to prepare a formal Flood Risk Assessment to accompany the planning application.

REQUIREMENT FOR THIS REPORT

The application site is located in Flood Zone 1, (land assessed as having a less than 1 in 1,000 annual probability of river or sea flooding (<0.1% Annual Exceedance Probability (AEP)) in any one year.

Given that the site is greater than 1 Ha, in accordance with the National Planning Policy Framework

(NPPF) and the Planning Practice Guidance (Flood Risk & Coastal Change) (PPG), a Flood Risk Assessment (FRA) and Drainage Strategy is required to support the planning application.

PLANNING POLICY

NATIONAL PLANNING POLICY

The National Planning Policy Framework (NPPF)¹ clearly identifies flood risk as a specific material consideration in the Planning Process and in the allocation and release of sites for development or re-development.

NPPF builds on its predecessor (PPS 25) and seeks to further strengthen the co-ordination between land-use planning and development planning and the operational delivery of flood and coastal defence strategy. NPPF retains key elements of PPS 25 continuing to encourage Local Planning Authorities to use their existing powers to guide, regulate and control development in relation to flooding and flood risk. NPPF expects Local Authorities to adopt a risk-based approach at all levels of Planning, through the application of the Sequential Test detailed in Table 1 and 2, of the Technical Guidance to NPPF document, a copy of which is attached in Appendix A.

The aim of the sequential test is to steer new development to areas with the lowest probability of flooding. Development should not be allocated or permitted if there are reasonably available sites appropriate for the proposed development in areas with a lower probability of flooding. The Strategic Flood Risk Assessment will provide the basis for applying this test. A sequential approach should be used in areas known to be at risk from any form of flooding.

The Water Resources Act 1991 [Section 105] also requires the Environment Agency to exercise a general supervision over all flood defence matters, including flood plains and washlands which accommodate waters during periods of flood. In discharging their functions, the Agency from time to time carries out comprehensive surveys and flood studies, largely of 'main rivers' within its jurisdiction.

A Section 105 Study involves the Agency topographically surveying the subject watercourse (or parts of it) and obtaining details of the flow mechanics within the watercourse. This data then enables them to generate a comprehensive hydraulic computer model for the watercourse. From this hydraulic model, the EA are able to define the approximate extent of fluvial floodplain associated with the 1 in 100-year (1% annual probability) flooding event or the extent of tidal floodplain associated with the 1 in 200-year (0.5% annual probability) flooding event.

The extents of the modelled floodplain are then provided to Local Planning Authorities, to enable them to make more informed decisions when considering proposed development in flood-susceptible areas. If development is proposed in a flood-susceptible area, or in an area where there is a history of flooding, the EA, as a statutory consultee in the Planning Process, will generally recommend that the risk of flooding be formally assessed, in

¹ National Planning Policy Framework

accordance with NPPF, and that a Flood Risk Assessment report be produced to support the Planning Application. The broader modelled flood extents are also indicated on the EA's Flood Zone Maps, available through their website².

Local Planning Policy

Catchment Flood Management Plan (CFMP)

The site is located within the Wyre catchment area. The Environment Agency has produced the 'Wyre Catchment Flood Management Plan'³. A copy of the CFMP is available from the EA on request.

CFMP's are not specifically required by the Water Framework Directive⁴ and are prepared voluntarily by the EA (under Government sponsorship). A CFMP is a high-level strategic plan for an area which aims to develop policies to manage flood risk over the next 50 to 100 years. These policies take into account the likely impacts of climate change and the effects of land-use and land management and identify a range of benefits which contribute towards sustainable development. The CFMP's policies establish whether action should be taken to increase, decrease or maintain the current level of flood risk.

Strategic Flood Risk Assessment (SFRA)

Local Planning Authorities are required to produce Local Development Frameworks, which are a portfolio of Local Development Documents that collectively deliver the spatial planning strategy for the Authority area. The LDD's undergo a Sustainability Appraisal which assists Planning Authorities in ensuring their policies fulfill the principles of sustainability. Strategic Flood Risk Assessments are one of the documents to be used as the evidence base for planning decisions and are a component of the Sustainability Appraisal process. Therefore, SFRAs should be used in the review or production of LDD's.

To assist Local Planning Authorities in their strategic land-use planning, SFRA's should present sufficient information to enable Local Authorities to apply the Sequential Test to their proposed development sites: *"Decision-makers should use the SFRA to inform their knowledge of flooding, refine the information on the Flood Map and determine the variations in flood risk from all sources of flooding across and from their area. These should form the basis for preparing appropriate policies for flood risk management for these areas."*⁵

² www.environment-agency.gov.uk

⁴ www.defra.gov.uk/environment/water/wfd/index.htm

⁵ NPPF

FRA Level	Description / Scope
Level 1	Screening Study to identify whether there are any flooding or surface water management issues related to a development site that may warrant further consideration. This should be based on readily available existing information, including the SFRA, Environment Agency Flood Map and Standing Advice. The Screening Study will ascertain whether a FRA is required.
Level 2	Scoping Study to be undertaken if the Level 1 FRA indicates that the site may lie within an area that is at risk of flooding or that the site may increase flood risk due to increased run-off. This Study should confirm the sources of flooding which may affect the site and should include the following: • an appraisal of the availability and adequacy of existing information; • a qualitative appraisal of the flood risk posed to the site, and potential impact of the development on flood risk elsewhere; • an appraisal of the scope of possible measures to reduce the flood risk to acceptable levels. The Scoping Study may identify that sufficient quantitative information is already available to complete a FRA appropriate to the scale and nature of the development.
Level 3	Detailed Study to be undertaken if the Level 2 FRA concludes that further quantitative analysis is required to assess flood risk issues related to the development site. The Study should include: • quantitative appraisal of the potential flood risk to the development; • Quantitative appraisal of the potential impact of development site on flood risk elsewhere; • quantitative demonstration of the effectiveness of any proposed mitigation measures.

It is considered that a Level 2 Scoping Study is appropriate at this stage and to minimise pre-commencement conditions this report has therefore been based on the requirements of a Level 2 Study.

REQUIREMENTS OF A FLOOD RISK ASSESSMENT

The EA's Flood Zone Maps, available on the EA's website, indicate that the site is wholly within a Flood Zone 1. Flood Zone 1 is an area of high risk of flooding, with a risk of flooding lower than 1 in 1000 year event. Current EA guidance indicates that all proposed developments in this zone should be accompanied by an FRA for a development site with an area of over 1 hectare, or the Local Authority have requested one, as in this situation. An FRA should contain:

- Information about the surface water disposal measures already in place and their state of maintenance;
- An assessment of the volume of surface water run-off likely to be generated from the proposed development;
- Information on how that surface water run-off will be disposed of (from the new development);
- Estimates of how climate change could affect the probability and intensity of flooding events in the future;
- Information about any other potential sources of flooding to the site - streams, ditches, sewers, groundwater, overland surface water flow or any combination of these.

As set out in NPPF flood risk assessments should identify and assess the risks of all forms of flooding to and from the development and demonstrate how these flood risks will be managed so that the development remains safe throughout its lifetime, taking climate change into account.

The detail and complexity of a Flood Risk Assessment should reflect the level of risk to the proposed development and should:

- be proportionate to the risk and appropriate to the scale, nature and location of the development;
- consider the risk of flooding arising from the development in addition to the risk of flooding to the development;
- take the impacts of climate change into account;
- be undertaken by competent people, as early as possible in the particular planning process, to avoid misplaced effort and raising landowner expectations where land is unsuitable for development;
- consider both the potential adverse and beneficial effects of flood risk management infrastructure including raised defences, flow channels, flood storage areas and other artificial features together with the consequences of their failure;
- consider the vulnerability of those that could occupy and use the development, taking account of the Sequential and Exception Tests and the vulnerability classification (including arrangements for safe access;

- consider and quantify the different types of flooding (whether from natural and human sources and including joint and cumulative effects) and identify flood risk reduction measures, so that assessments are fit for the purpose of the decisions being made;
- consider the effects of a range of flooding events including extreme events on people, property, the natural and historic environment and river and coastal processes;
- include the assessment of the remaining (known as ‘residual’) risk after risk reduction measures have been taken into account and demonstrate that this is acceptable for the particular development or land use;
- consider how the ability of water to soak into the ground may change with development, along with how the proposed layout of development may affect drainage systems;
- be supported by appropriate data and information, including historical information on previous events.

SEQUENTIAL TEST

The sequential test is to ensure that a sequential approach is followed to steer new development to areas with the lowest probability of flooding. The aim is to steer new developments to Flood Zone 1 (areas with a low probability of river or sea flooding).

The proposed development is set within Flood Zone 1.

The proposed residential development will be categorised as ‘more vulnerable’ as classed within NPPF.

Table 4.5 Flood Risk Vulnerability Classification Chart (NPPF)

Flood Zones	Flood Risk Vulnerability Classification				
	Essential infrastructure	Highly vulnerable	More vulnerable	Less vulnerable	Water compatible
Zone 1	✓	✓	✓	✓	✓
Zone 2	✓	Exception Test required	✓	✓	✓
Zone 3a †	Exception Test required †	✗	Exception Test required	✓	✓
Zone 3b *	Exception Test required *	✗	✗	✗	✓*

Key:

✓ Development is appropriate

✗ Development should not be permitted.

Based upon the Flood risk Vulnerability classification the development site is classed as appropriate and therefore the sequential test is past.

1. SITE CONTEXT

1.1. SITE LOCATION

The closest address to the site is Trub, Castleton, Rochdale, Greater Manchester, England, OL11 2QH, United Kingdom.

The site is located on grass field. Situated to the north is Castleton Train Station. Rochdale Canal forms the western boundary of the site. Situated east of the site beyond Manchester Road consists of residential development properties. The total site area within the red line boundary is 4.96Ha.

According to the Topographical Survey (Appendix B) the site falls north to south. The levels north of the site range between 131.50m AOD to 136.16m AOD. The levels south of the site range between 130.00m AOD and 120.00m AOD

Figure (1-1) below shows the site location.




FIGURE 1-1 - SITE LOCATION PLAN

1.2. WATERCOURSES

The nearest 'Main River' (Regulated by the Environment Agency) to the site is the River Roch and is located approximately 2.00km north west of the site at its nearest point.

An Ordinary Watercourse 'Trub Brook' is located at the southern boundary of the site which flows East to west along the southern boundary of the site.

1.3. Ground Conditions

1.3.1. Geology

A review of the British Geological Survey (BGS) online geological mapping indicates that the bedrock of the site is Pennine Lower Coal Measures Formation - Mudstone, siltstone and sandstone. Superficial deposits of Glaciofluvial Deposits, Devensian - Sand and gravel.

Drift deposits were found within all ground testing locations and are variable across the site which consisted of layers such as clay, sand and peat. These ground conditions were discovered from 0.20 to a maximum proven depth of 15.00 m bgl.

Where encountered, cohesive deposits were encountered as brown soft to stiff, silty sandy CLAY. Granular deposits were encountered as light brown very loose to dense fine to medium SAND. From depths of 3.00 m bgl and below the sands were encountered as 'blowing sand' within window sample and cable percussive boreholes, likely associated with the high water table.

1.4. Soil

DEFRA's Magic Online Mapping tool indicates that the site is underlain mainly by 'Freely draining slightly acid sandy soils.

1.4.1. Hydrogeology

DEFRA's Magic Online Mapping tool indicates that the bedrock is classified as a Secondary A, these comprise permeable layers that can support local water supplies and may form an important source of base flow to rivers.

Based on the latest site investigation, the proposed development is in an area affected by river flooding due to its planned location, categorising it into 'Flood Risk Zone 1'. However, the Groundsure reports state that there is a potential for ground water flooding across majority of the site. This can be mitigated by implementing measures such as larger storage pipes and utilising near by ponds / attenuation basins.

1.5. Existing Services / Constraints

A formal drainage survey has not been completed, however, statutory utility plans for the site have been reviewed. A Cadent high pressure gas main has been identified along the southern boundary of the site (within the site boundary). A combined sewer is located in the centre of the site transecting north to south. In the south of the site this is diverted to the south western boundary. A further combined public sewer is located along the southern boundary. A surface water sewer is present in the centre of the site transecting south and then diverting west to the south western boundary. A further surface water sewer is present in the north of the site crossing east to west.

All existing utilities running through the proposed development is to be diverted under a S185 application.


2. FLOOD RISK

2.1. FLUVIAL FLOOD RISK

The Environment Agency Flood Map for Planning below in Figure 2-1 indicates that the site is located entirely within Flood Zone 1 and therefore a low risk from fluvial flooding. The land to the west adjacent to and beyond River don lies within Flood Zone 1.

There is a watercourse approximately 190m south of the site that connects to wine brook which has Flood Zone 3 and Flood Zone 2 along its course. However, these zones of influence do not encroach within the site boundary and so it is not considered to pose a risk to the site.

Trubs Brook runs along the southern boundary of the site from east to west and is culverted for a significant section of its run alongside the site. Therefore it can be considered to be a low risk of fluvial flooding.



© Environment Agency copyright and / or database rights 2022. All rights reserved. © Crown Copyright and database right 2022. Ordnance Survey licence number 100024198.

FIGURE 2-1 - FLOOD MAP FOR PLANNING

2.2. Surface water and overland flows Flood Risk

The Environment Agency's Surface Water Flood Map in Figure below in figure 2-2 indicates the extent of surface water flooding within the site. This demonstrates that the area can be considered to be at medium to high risk.

The highest risk of surface water flooding is indicated southwest of the site boundary. This is due to the lowest area of the site being located within this area. As stated in the site context section the site falls from north to south which explains the ponding of surface water flooding nearer south of the south.




FIGURE 2-2 - EXTENT OF FLOODING FROM SURFACE WATER

2.3. Groundwater Flooding

A Review of Rochdale's Borough Strategy for Flood Risk Management 2014-2024 highlighted below in figure 2-3 indicates that the site is within an area that is susceptible to groundwater.




FIGURE 2-3 - GROUNDWATER SUSCEPTIBILITY MAP

2.4 Canal Flooding

- 3 Flooding from a canal occurs when the canal is overtopped or breaches due to failure. Rochdale forms the eastern boundary of the site. From the topographical survey the levels around the canal are higher than that of the site. Therefore, if there were to be a leakage of the canal this could potential put thye site at risk. However, as canals have various features which allow for regulation of water flow their flood risk is generally low.

3.0 PLANNING POLICY AND GUIDANCE

The LLFA for the site is RBC (Rochdale Borough Council). The following national and local policies should be adhered to:

National Planning Policy Framework

2.1. In accordance with the NPPF a formal FRA is required in support of a planning application for development sites located within Flood Zone 1 that is more than 1 hectare (ha). The level of detail within an FRA should be appropriate to the scale and nature of the development.

2.2. Sequential & Exception Tests

2.3. One of the aims of NPPF is to steer development away from flood zones of high flood risk towards Flood Zone 1. The proposed development components are classified as 'more vulnerable'. In accordance with Table 2 of the Flood Risk Vulnerability and flood zone 'incompatibility'.

2.4. Give that the site is in Flood Zone 1 and the development is 'more vulnerable', the proposed development is considered appropriate on the flood risk terms and therefore the sequential test is considered passed.

2.5. Rochdale Borough Unitary Development Plan

2.6. The Development Plan (2006) includes objectives such as:

2.7. EM/7 DEVELOPMENT AND FLOOD RISK

- a) It will not increase the risk of flooding within the flood plain or in adjoining areas by reducing flood storage capacity, increasing flows within a flood plain or through the additional discharge of surface water;
- b) It will not itself be at risk from flooding;
- c) Appropriate sustainable drainage systems are used;
- d) Adequate access adjacent to the water course for maintenance is provided;
- e) Existing or proposed flood defences are protected;
- f) It would not result in extensive culverting; and
- g) Flood defence works required as a consequence of development are provided at the developer's expense

DEVELOPMENT PROPOSAL

PROPOSED DEVELOPMENT (CONCEPT DESIGN)

The proposed development is the following.

Erection of 179 units

- Apartment 1 – 24 Units
- Apartment 2 – 24 units
- Ashburn – 16 units
- Padbury – 37 units
- Seacort – 32 units
- Holgate – 15 units
- Farley – 13 units
- Selset – 6 units
- Winterborne – 8 units
- Thronton - 4 units



Proposed Site Layout (Produced by MCI Developments)

4.0 PROPOSED DRAINAGE

4.1 SURFACE WATER DRAINAGE OPTIONS

The BGS maps indicate that the geology of the site consists of Pennine Lower Coal Measures Formation – Mudstone. It is anticipated that larger storage pipes, attenuation basins and proposed ponds are to be used to mitigate any flooding risk from the development. For both a 30 year and 100 year storm.

To ensure that post-development run-off volumes and peak flow rates discharging from the site do not exceed current levels, it may be necessary to employ Sustainable Drainage Systems) methods and source control techniques, including flow control devices to restrict flows and to store attenuated water on site. The provision of such techniques will ensure that the maximum discharge from the site does not exceed the agreed rates with the statutory bodies. In addition, where practicable, opportunities for reducing flood risk through the management of surface water run-off from the site should be included.

Storage of attenuated flows within the site could be provided in a number of ways:

- underground – over-sized pipes / tanks or proprietary storage systems such as ‘Stormcell’;
- above ground – storage / balancing pond, designated surface areas (low risk areas such as car parks, open space);
- combination of underground and above ground.

Proposed SW drainage systems are generally designed in accordance with ‘Sewers for Adoption’⁶, which requires that any surface water drainage system, which is proposed to be Adopted after construction, should not surcharge during the 1 in 5-year storm event, and should not produce any surface flooding during a 1 in 30-year storm event (i.e. all run-off contained wholly within the sewerage system during the 1 in 30-year event).

It is generally accepted that a degree of surface flooding can be permitted during extreme storm events, subject to specific surface areas being designated as flood-susceptible and subject to flooding of these areas posing little or no risk to human life and/or damage to property. Examples of surface areas which might be permitted to flood during extreme events are:

- Agricultural land;
- Recreational land (playing fields etc.);
- Landscaped areas;
- Car parks;
- Other non-inhabited, designated areas.

⁶‘Sewers for Adoption’ 7th Edition, published by WRc Plc., March 2006

In all cases where surface flooding might be permitted or designed in to a scheme, due diligence needs to be given to NPPF and the need to make potential users of such areas aware of their functionality and purpose, and the requirement to maintain safe access and egress at all times.

The Building Regulations Approved Document H (2002) outlines a hierarchy of potential methods of disposing of surface water from a site:

- A soakaway; or where that is not practicable
- A watercourse or river; or where that is not practicable,
- A sewer.

The viability of this hierarchy has been assessed below:

4.2 SOAKAWAY

Due to shallow groundwater on site all soakaway tests failed, as such, soakaway drainage is not considered to be feasible for the proposed development.

4.3 WATERCOURSES / WATER BODIES

There is a watercourse running to the southern boundary of the site, however following onsite investigations watercourse is not suitable due to no outfall.

4.4 SEWERS

The foul water will drain to the diverted combined sewer running to along the eastern boundary at an unrestricted rate.

Below is a chart based on table 1.1 typical SuDS components within CIRIA Guidance 697 SuDS manual. This discusses the viable SuDS components and whether they are useable for this site.

Component	Description	Is it viable
Filter Strips	These are wide, gently sloping areas of grass or other dense vegetation that treat runoff from adjacent impermeable areas.	Infiltration is not likely to be successful therefore this type of SuDS system should not be viable on the site.
Swales	Swales are broad, shallow channels covered by grass or other suitable vegetation. They are designed to convey and/or store runoff, and can infiltrate the water into the ground (if ground conditions allow)	Infiltration is not likely to be successful therefore this type of SuDS system should not be viable on the site.
Infiltration Basins	Infiltration basins are depressions in the surface that are designed to store runoff and infiltrate the water to the ground. They may also be landscaped to provide aesthetic and amenity value	Infiltration is not likely to be successful therefore this type of SuDS system should not be viable on the site.
Wet Ponds	Wet ponds are basins that have a permanent pool of water for water quality	Wet pond could be used for this site if

	treatment. They provide temporary storage for additional storm runoff above the permanent water level. Wet ponds may provide amenity and wildlife benefits	needed.
Extended detention basins	Extended detention basins are normally dry, though they may have small permanent pools at the inlet and outlet. They are designed to detain a certain volume of runoff as well as providing water quality treatment.	Detention Basin to be used on this site.
Constructed Wetland	Constructed wetlands are ponds with shallow areas and wetland vegetation to improve pollutant removal and enhance wildlife habitat	Constructed wetland would not be possible Therefore this type of SuDS is unsuitable.
Filter drains and perforated pipes	Filter drains are trenches that are filled with permeable material. Surface water from the edge of paved areas flows into the trenches, is filtered and conveyed to other parts of the site. A slotted or perforated pipe may be built into the base of the trench to collect and convey the water.	Infiltration is not likely to be successful therefore this type of SuDS system should not be viable on the site.
Infiltration devices	Infiltration devices temporarily store runoff from a development and allow it to percolate into the ground.	Infiltration is not likely to be successful therefore this type of SuDS system should not be viable on the site.
Pervious surfaces	Pervious surfaces allow rainwater to infiltrate through the surface into an underlying storage layer, where water is stored before infiltration to the ground, reuse, or release to surface water	Pervious pavement could be implemented on residential driveways, in order to clean flows.
Green Roofs	Green roofs are system which cover a building's roof with vegetation. They are laid over a drainage layer, with other layers providing protection, waterproofing and insulation.	Green roofs are not viable on this site due to the heavy maintenance
Oversized Pipes / Tanks	Oversized pipes and cellular are pipes below ground that hold surface water.	Oversized pipes to be used in conjunction with detention basin,

4.5 SURFACE WATER DRAINAGE STRATEGY

The surface water will discharge to an infiltration basin at the southern boundary of the site hence all the drainage run off are dealt within the boundary of the development.

Drainage Layout can be seen in Appendix F.

The Qbar of the site is estimated to 28.5l/s.

The proposed surface water network has been designed using Microdrainage flow simulation software to ensure the following:

- No surcharging of drainage network for Design Storm of 1 in 2 years.
- No flooding for design flood frequency of 1 in 30 years.
- 1:100 year + 40% model should be duly reviewed and flood routing plans prepared as part of the detailed site designs.
- Maintenance of the drainage will be undertaken by MCI Developments until adopted and/or transferred to a management company.

4.6 Proposed SuDS Features

The proposed SuDS features at Trub Farm, as illustrated in Appendix G, include tree pits, permeable paving, an enlarged basin, and a series of rain gardens distributed throughout the site. The tree pits are positioned to support local infiltration and provide landscape benefits, while permeable paving areas help reduce surface runoff by allowing water to soak through. The basin, with its increased profile, is designed to accommodate larger volumes of surface water, aiding in attenuation during heavy rainfall. The rain gardens offer further infiltration capacity when required. Together, these features form a sustainable and integrated approach to surface water management.

5 Flood Hazards & Sources of Flooding

5.1 POTENTIAL FLOOD HAZARDS

Prior to undertaking an FRA, the different types of flooding mechanisms which may affect the site need to be identified and then assessed to determine whether the development site is located within an area which is at risk of flooding from one or more of the applicable mechanisms.

CIRIA Report C624 ⁷, Table A2.1, lists a number of key factors that should be considered during a Level 1 FRA. This table can be used to summarise the findings of a Level 1 FRA study and to identify those flood hazards which may be applicable to the site in question. The boxes shaded grey indicate those sources of flooding which are unlikely to be identified for each question. If sufficient information is not available to identify the specific source of flooding, then all possible sources should be ticked. If a tick is placed below any flood hazard then a Level 2 FRA will be required to assess flood risk issues relating to that hazard in more detail.

Table 8.1 below identifies the flood hazards applicable to this site.

⁷CIRIA publication 'C624 Development and Flood Risk – Guidance for the Construction Industry'

Table 5.1 Flood Hazard Identification

Question	Flood Hazard						
	Fluvial	Sea	Estuaries	Groundwater	Overland flow	Artificial drainage systems	Infrastructure failure
Is the development site next to the sea or any watercourse shown on Ordnance Survey maps?	x	x	x				
Is the development site, or part of the development site, identified as being at risk of flooding within available documentation?	x	x	x	x	x	x	x
If a strategic flood risk assessment is available, is the development site, or part of the development site, identified as being at risk of flooding?	x	x	x	x	x	x	x
If a flood zone map is available, is the development site, or part of the development site, within a High Risk zone?	x	x	x				
If a flood zone map is available, is the development site, or part of the development site, within a Low to Medium Risk zone?	✓	x	x				
If a flood zone map is not available, is the development site, or part of the development site, situated on alluvium based on consideration of geological maps of the area?	x	x	x				
If there is an existing property on, or next to the site at the same level, is the property within a flood warning area?	x	x	x	x			
Are the LPA / FDA aware of any existing, historical or potential flooding problems that may affect the site?	x	x	x	x	x	x	x
Do the physical characteristics of the site suggest that it may be prone to flooding?	x	x	x	x	x	x	x
If a flood zone map is not available, is the development site, or part of the development site below 10m AOD AND does the FDA consider the development to be at risk of tidal flooding?		x	x				
Is the development located within a natural or artificial hollow, or at the base of a valley or at the bottom of a hill slope?				x	x		
Does examination of historical maps indicate any likelihood of flood risk at the site?	x	x	x	x	x		
Do the names of surrounding roads, areas or houses suggest the possibility of seasonal or historical flooding?	x	x	x	x	x		
Is the site likely to involve excavation / construction below existing ground levels (excluding foundations)?	x	x	x	x	x		
Is the land use upslope of the site such that the generation of overland flow may be encouraged, and can water from this area flow onto the site?					x		
Are there any artificial drainage systems on or next to the site, at the same level, or upslope of, the site?						x	x
Is the development site protected by an existing flood defence?	x	x	x			x	x
Is the development site protected by a flood control structure (e.g. flap valve, sluice gate, tidal barrier etc)	x	x	x			x	x
Is the development site located upstream of a culvert which may be prone to	x		x	x	x	x	x

blockage?							
Are water levels in a watercourse located in or next to a development site controlled by a pumping station?	x	x	x	x	x	x	x
Is the development site next to or downstream / down slope of a canal?						x	x
Is the development site downstream/ down slope of a reservoir or other significant water body?						x	x
FURTHER COMMENT ON FLOOD RISK WITHIN THIS FRA?	✓	x	x	x	x	x	x

5.2 SOURCES OF FLOODING

It is considered that there are two potential sources of flooding to the site:

- Risk of flooding from watercourse located south of site boundary.
- Leakage of Canal due to site being positioned lower.

5.3 INFRASTRUCTURE FAILURE

The central CIRIA Report C624 defines ‘infrastructure failure’ as the structural, hydraulic, geotechnical, mechanical or operational failure of infrastructure which normally retains, transmits or controls the flow of water. This risk of flooding is usually associated with three main categories of infrastructure:

- failure of infrastructure designed to store or carry water (e.g. dam break, canal leak, water mains burst);
- failure of infrastructure designed to protect an area from flooding (e.g. flood defence breach, flap valve failure, penstock failure, pumping station failure);
- blockage of a pipe, bridge or culvert.

Failure of any water mains could result in leakage and consequently over-land flows within the site. There is therefore a risk of over-land flows being generated because of an infrastructure failure in any water mains, however, such failures occur very infrequently and there is little that can be done to anticipate them.

Water main failures are usually notified to the asset owner within a short period of time of the failure occurring and remedial Work is usually implemented soon thereafter to prevent subsequent property damage and inconvenience. Any failure of a water main is therefore likely to continue for a relatively short period of time.

Based on the above information, the risk of flooding as a result of infrastructure failure is considered to be low and on this basis any further assessment of flooding from infrastructure failure is not considered necessary.

5.4 RESIDUAL RISKS

Table 10.1 outlines the initial qualitative assessment of risk posed by each potential source of flooding, the mechanisms for flooding and the likely consequences. The table also includes a review of possible mitigation measures and what effect, if any, the mitigation measures are likely to have on the residual risk posed by each potential flood source.

Categories of risk have been qualitatively defined as:

‘High’ Risk: Flooding is likely to result in significant damage to property and pose a significant risk to life;
‘Medium’ Risk: Flooding is likely to result in possible minor damage to property but flood progress would allow adequate time for residents to be warned and safely evacuated to higher ground or appropriate places of safety;
‘Low’ Risk: Flooding is unlikely to result in any damage to property damage and pose little or no risk to life.

6 CLIMATE CHANGE

Below are the recommended rainfall intensity increases from the Flood Risk Assessment climate change allowances

Table 6.1 Peak rainfall intensity allowance in small and urban catchments (use 1961 to 1990 baseline)

Applies across all of England	Total potential change anticipated for 2020s	Total potential change anticipated for 2050s	Total potential change anticipated for 2080s
Upper End	24%	43%	75%
Central	12%	19%	24%

For practical reasons, it is difficult to define the lifetime of a development as each development has different characteristics. However, residential development is considered to have a minimum lifetime horizon of 100 years, unless there is specific justification for considering a shorter period (e.g. development controlled by a time-limited Planning Condition). This development lifetime is approximately 100-year design life.

Therefore, over the next 100 years, the recommendations contained in table 2 Flood Risk assessments: climate change allowance document in terms of increased rainfall, would equate to an increase of between 43% and 75% in peak rainfall intensity.

A rainfall intensity of 75% has been used for designing this development. The preliminary design of the proposed SW drainage system has taken account of this increase in peak rainfall intensity over the lifetime of the proposed development and has demonstrated that surface water run-off can be managed in a sustainable manner on the site, including the effects of climate change. It is therefore considered that the proposed development has taken account of climate change effects.

7 CONCLUSIONS

- MCI Developments are proposing a new residential development at the land of Trubs Farm, Thornton. Total area of the site is approximately 4.96ha.
- The development site is greenfield and currently consists of an existing field.
- The site lies within Flood Zone 1.
- Two existing United Utilities sewers running through proposed development, to be diverted through the S185.
- Levels are to be raised to move the SuDS from the water table.
- The site is overall at a low to medium risk from surface water flooding.

8 RECOMMENDATIONS

- The installation of an effective drainage strategy will mitigate the risk of surface water and groundwater flooding on the site.
- The Qbar rate is estimated to 28.5l/s.

APPENDIX A:

Introduction

1. This document provides additional guidance to local planning authorities to ensure the effective implementation of the planning policy set out in the National Planning Policy Framework on development in areas at risk of flooding and in relation to mineral extraction. This guidance retains key elements of Planning Policy Statement 25 and of the existing minerals policy statements and minerals planning guidance notes which are considered necessary and helpful in relation to these policy areas. The retention of this guidance is an interim measure pending a wider review of guidance to support planning policy.

Flood risk

2. As set out in the National Planning Policy Framework, inappropriate development in areas at risk of flooding should be avoided by directing development away from areas at highest risk, but where development is necessary, making it safe without increasing flood risk elsewhere. For these purposes:
 - “areas at risk of flooding” means land within Flood Zones 2 and 3; or land within Flood Zone 1 which has critical drainage problems and which has been notified to the local planning authority by the Environment Agency;
 - “flood risk” means risk from all sources of flooding - including from rivers and the sea, directly from rainfall on the ground surface and rising groundwater, overwhelmed sewers and drainage systems, and from reservoirs, canals and lakes and other artificial sources.

The Sequential and Exception Tests

3. As set out in the National Planning Policy Framework, the aim of the Sequential Test is to steer new development to areas with the lowest probability of flooding. The flood zones (see table 1) are the starting point for this sequential approach. Zones 2 and 3 are shown on the flood map¹ with Flood Zone 1 being all the land falling outside Zones 2 and 3. These flood zones refer to the probability of sea and river flooding only, ignoring the presence of existing defences.
4. Strategic Flood Risk Assessments (see paragraphs 7-8) refine information on the probability of flooding, taking other sources of flooding and the impacts of climate change (see paragraphs 11-15) into account. They provide the basis for applying the Sequential Test, on the basis of the flood zones in table 1. Where table 1

¹ To access the flood map, see the Environment Agency's website at:
<http://www.environment-agency.gov.uk/homeandleisure/floods/default.aspx>

indicates the need to apply the Exception Test (as set out in the National Planning Policy Framework), the scope of a Strategic Flood Risk Assessment will be widened to consider the impact of the flood risk management infrastructure on the frequency, impact, speed of onset, depth and velocity of flooding within the flood zones considering a range of flood risk management maintenance scenarios. Where a Strategic Flood Risk Assessment is not available, the Sequential Test will be based on the Environment Agency flood zones.

5. The overall aim should be to steer new development to Flood Zone 1. Where there are no reasonably available sites in Flood Zone 1, local planning authorities allocating land in local plans or determining planning applications for development at any particular location should take into account the flood risk vulnerability of land uses (see table 2) and consider reasonably available sites in Flood Zone 2, applying the Exception Test if required (see table 3). Only where there are no reasonably available sites in Flood Zones 1 or 2 should the suitability of sites in Flood Zone 3 be considered, taking into account the flood risk vulnerability of land uses and applying the Exception Test if required.

Table 1: Flood zones

(Note: These flood zones refer to the probability of river and sea flooding, ignoring the presence of defences)

Zone 1 - low probability Definition This zone comprises land assessed as having a less than 1 in 1,000 annual probability of river or sea flooding (<0.1%). Appropriate uses All uses of land are appropriate in this zone. Flood risk assessment requirements For development proposals on sites comprising one hectare or above the vulnerability to flooding from other sources as well as from river and sea flooding, and the potential to increase flood risk elsewhere through the addition of hard surfaces and the effect of the new development on surface water run-off, should be incorporated in a flood risk assessment. This need only be brief unless the factors above or other local considerations require particular attention. Policy aims In this zone, developers and local authorities should seek opportunities to reduce the overall level of flood risk in the area and beyond through the layout and form of the development, and the appropriate application of sustainable drainage systems².

² Sustainable drainage systems cover the whole range of sustainable approaches to surface drainage management. They are designed to control surface water run off close to where it falls and mimic natural drainage as closely as possible.

Zone 2 - medium probability

Definition

This zone comprises land assessed as having between a 1 in 100 and 1 in 1,000 annual probability of river flooding (1% – 0.1%), or between a 1 in 200 and 1 in 1,000 annual probability of sea flooding (0.5% – 0.1%) in any year.

Appropriate uses

Essential infrastructure and the water-compatible, less vulnerable and more vulnerable uses, as set out in table 2, are appropriate in this zone. The highly vulnerable uses are *only* appropriate in this zone if the Exception Test is passed.

Flood risk assessment requirements

All development proposals in this zone should be accompanied by a flood risk assessment.

Policy aims

In this zone, developers and local authorities should seek opportunities to reduce the overall level of flood risk in the area through the layout and form of the development, and the appropriate application of sustainable drainage systems.

Zone 3a - high probability

Definition

This zone comprises land assessed as having a 1 in 100 or greater annual probability of river flooding (>1%), or a 1 in 200 or greater annual probability of flooding from the sea (>0.5%) in any year.

Appropriate uses

The water-compatible and less vulnerable uses of land (table 2) are appropriate in this zone. The highly vulnerable uses should not be permitted in this zone.

The more vulnerable uses and essential infrastructure should only be permitted in this zone if the Exception Test is passed. Essential infrastructure permitted in this zone should be designed and constructed to remain operational and safe for users in times of flood.

Flood risk assessment requirements

All development proposals in this zone should be accompanied by a flood risk assessment.

Policy aims

In this zone, developers and local authorities should seek opportunities to:

- reduce the overall level of flood risk in the area through the layout and form of the development and the appropriate application of sustainable drainage systems;

- relocate existing development to land in zones with a lower probability of flooding; and
- create space for flooding to occur by restoring functional floodplain and flood flow pathways and by identifying, allocating and safeguarding open space for flood storage.

Zone 3b - the functional floodplain

Definition

This zone comprises land where water *has* to flow or be stored in times of flood.

Local planning authorities should identify in their Strategic Flood Risk Assessments areas of functional floodplain and its boundaries accordingly, in agreement with the Environment Agency. The identification of functional floodplain should take account of local circumstances and not be defined solely on rigid probability parameters. But land which would flood with an annual probability of 1 in 20 (5%) or greater in any year, or is designed to flood in an extreme (0.1%) flood, should provide a starting point for consideration and discussions to identify the functional floodplain.

Appropriate uses

Only the water-compatible uses and the essential infrastructure listed in table 2 that has to be there should be permitted in this zone. It should be designed and constructed to:

- remain operational and safe for users in times of flood;
- result in no net loss of floodplain storage;
- not impede water flows; and
- not increase flood risk elsewhere.

Essential infrastructure in this zone should pass the Exception Test.

Flood risk assessment requirements

All development proposals in this zone should be accompanied by a flood risk assessment.

Policy aims

In this zone, developers and local authorities should seek opportunities to:

- reduce the overall level of flood risk in the area through the layout and form of the development and the appropriate application of sustainable drainage systems;
- relocate existing development to land with a lower probability of flooding.

Table 2: Flood risk vulnerability classification

Essential infrastructure • Essential transport infrastructure (including mass evacuation routes) which has to cross the area at risk. • Essential utility infrastructure which has to be located in a flood risk area for operational reasons, including electricity generating power stations and grid and primary substations; and water treatment works that need to remain operational in times of flood. • Wind turbines.
Highly vulnerable • Police stations, ambulance stations and fire stations and command centres and telecommunications installations required to be operational during flooding. • Emergency dispersal points. • Basement dwellings. • Caravans, mobile homes and park homes intended for permanent residential use³. • Installations requiring hazardous substances consent⁴. (Where there is a demonstrable need to locate such installations for bulk storage of materials with port or other similar facilities, or such installations with energy infrastructure or carbon capture and storage installations, that require coastal or water-side locations, or need to be located in other high flood risk areas, in these instances the facilities should be classified as “essential infrastructure”)⁵.
More vulnerable • Hospitals. • Residential institutions such as residential care homes, children’s homes, social services homes, prisons and hostels. • Buildings used for dwelling houses, student halls of residence, drinking establishments, nightclubs and hotels. • Non-residential uses for health services, nurseries and educational establishments. • Landfill and sites used for waste management facilities for hazardous waste⁶. • Sites used for holiday or short-let caravans and camping, <i>subject to a specific warning and evacuation plan</i>.⁷
Less vulnerable • Police, ambulance and fire stations which are <i>not</i> required to be operational during flooding. • Buildings used for shops, financial, professional and other services,

³ For any proposal involving a change of use of land to a caravan, camping or chalet site, or to a mobile home site or park home site, the Sequential and Exception Tests should be applied.

⁴ See Circular 04/00: *Planning controls for hazardous substances* (paragraph 18) at: www.communities.gov.uk/publications/planningandbuilding/circularplanningcontrols

⁵ In considering any development proposal for such an installation, local planning authorities should have regard to planning policy on pollution in the National Planning Policy Framework.

⁶ For definition, see *Planning for Sustainable Waste Management: Companion Guide to Planning Policy Statement 10* at

www.communities.gov.uk/publications/planningandbuilding/planningsustainable

⁷ See footnote 3.

restaurants and cafes, hot food takeaways, offices, general industry, storage and distribution, non-residential institutions not included in “more vulnerable”, and assembly and leisure. • Land and buildings used for agriculture and forestry. • Waste treatment (except landfill and hazardous waste facilities). • Minerals working and processing (except for sand and gravel working). • Water treatment works which do <i>not</i> need to remain operational during times of flood. • Sewage treatment works (if adequate measures to control pollution and manage sewage during flooding events are in place).
Water-compatible development • Flood control infrastructure. • Water transmission infrastructure and pumping stations. • Sewage transmission infrastructure and pumping stations. • Sand and gravel working. • Docks, marinas and wharves. • Navigation facilities. • Ministry of Defence defence installations. • Ship building, repairing and dismantling, dockside fish processing and refrigeration and compatible activities requiring a waterside location. • Water-based recreation (excluding sleeping accommodation). • Lifeguard and coastguard stations. • Amenity open space, nature conservation and biodiversity, outdoor sports and recreation and essential facilities such as changing rooms. • Essential ancillary sleeping or residential accommodation for staff required by uses in this category, <i>subject to a specific warning and evacuation plan</i>.

Notes to table 2:

- This classification is based partly on Department for Environment, Food and Rural Affairs and Environment Agency research on *Flood Risks to People (FD2321/TR2)*⁸ and also on the need of some uses to keep functioning during flooding.
- Buildings that combine a mixture of uses should be placed into the higher of the relevant classes of flood risk sensitivity. Developments that allow uses to be distributed over the site may fall within several classes of flood risk sensitivity.
- The impact of a flood on the particular uses identified within this flood risk vulnerability classification will vary within each vulnerability class. Therefore, the flood risk management infrastructure and other risk mitigation measures needed to ensure the development is safe may differ between uses within a particular vulnerability classification.

⁸ See website for further details.

www.defra.gov.uk/science/Project_Data/DocumentLibrary/FD2320_3364_TRP.pdf

APPENDIX B:



REV	DATE	DRAWN	DESCRIPTION	ARCH. CHECK	ENG. CHECK
-----	------	-------	-------------	-------------	------------

TITLE
CONSTRAINTS AND HAZARD PLAN




PROJECT					
Trub Farm, Castleton Constraints Plan					
DRN BY	MM	SCALE	JOB REF	DRAWING NUMBER	REV
DATE	Dec '23	NTS @ A1	-	TRUB Constraints	-

APPENDIX C:

The details provided on this drawing are subject to comments by all the relevant approving authorities. Until such time as all comments have been received and incorporated onto the drawings, all the information provided and costings, are used at MCI Developments Ltd risk and no liability will be accepted by ALD Design. Scheme based on Site Layout MCI-000-DR-A-500 PL06

Prior to any construction, the contractor must confirm the precise invert level and pipe diameter of the receiving drainage system and must immediately advise ALD Design of any variation to that upon which the design has been based.



Infiltration has been discounted as a suitable means of surface water disposal due to the ground conditions.

Infiltration has been discounted as a suitable means of surface water disposal due to the ground conditions.

The design is based on current guidance however there may be changes in the future by statutory authorities which may have an impact on the current design and requirements.

Foundations to be designed to take into account any adjacent deep sewers

The highway and sewer designs are subject to technical approval by the Highway Authority and United Utilities, and may be amended in response to review comments.

S185 approval is critical to the design and therefore no works should be undertaken until approval is agreed

System designed not to flood in the 2yr, 30yr & 100yr+45%cc events

- GENERAL**
- All adoptable sewers and associated works are to comply fully with "Design and Construction Guidance" & Local Practices
 - All highway works to be to adoptable standards and to comply fully with the Local Authority specification.
 - All private drainage works are to comply fully with part H of the Building Regulations
 - All existing invert levels to be checked by the Contractor at the start of works and any discrepancies notified to ALD Design. All levels are based on topographical survey information provided by others.
 - All materials to bear the relevant B.S. Kitemark and comply fully with the specifications. All concrete & concrete products must use Sulphate resistant cement (unless the site investigation report proves that sulphate attack from soils and groundwater will not occur)
 - All opening notices etc. as required under highways acts etc. are to be obtained prior to commencement of works. All works are to be inspected by L.A., NHBC or Relevant Water Authority as applicable.
- C.D.M. REGULATIONS 2015**
- In line with the above regulations we are obliged to inform the Client of their responsibilities under section CDM 15/1, and residual risks that may be encountered in the construction of these works. All design work has been carried out with Health and Safety aspects given full consideration. Wherever possible risks have been eliminated from the design, however due to the very nature of this type of work it is not possible to remove all the risks from the design. We would also respectfully remind the Client of his obligations to take all reasonable steps in ensuring that only competent Contractors who have a valid safety policy are employed. They should also provide satisfactory responses at tender stage as to the manner in which they will deal with the elements of risk involved in this type of work and in particular those highlighted by ALD Design below:-
- Support / treatment for ALL excavation work.
 - Guarding to edges of excavations to prevent people, materials and vehicles falling into excavation.
 - Guarding of excavations outside working hours to prevent unauthorised access.
 - Undermining to adjacent roads or structures.
 - Confined space operations.
 - Dealing with existing services.
 - Traffic management on existing highways.
 - Procedure to be followed in event of accident or emergency.
 - Method of working where contaminated ground is present on site.
 - Confirmation will be required that all operatives are adequately trained, copies of relevant training certificates to be supplied.
- The above list is by no means exhaustive but it does highlight operations that present a risk to contractors and the general public. For clarification on any item please contact ALD Design.

Legend:

- Proposed foul water sewer and manhole
- Proposed surface water sewer and manhole
- Existing surface water sewer & manhole
- Existing combined water sewer & manhole
- Existing surface water sewer & manhole to be abandoned
- Existing combined water sewer & manhole to be abandoned
- Denotes proposed surface water attenuation basin
- Denotes finished floor levels
- Proposed Sewer Easement
- Proposed Tree pit locations
- Proposed Rain Garden locations

D	11.07.25	Suds feature locations added	AP		
C	23.06.25	Revised attenuation basin levels and sewers	AP		
B	12.06.25	Redesign to Accommodate Proposed Foul Water Levels	AP		
A	22.05.25	First Issue	AP		
Rev.	Date	Amendment	Drawn	Chkd.	Appd.



Client					
 MCI A KEEPMOAT HOMES COMPANY					
Project Title					
Trub Farm Rochdale					
Status					
Preliminary					
Drawing Title					
Adoptable Drainage Layout Sheet 1 of 2					
Drawn		Date		Checked	
AP		May 25		Date	
Scale		Orig Size		Dimensions	
1:500		A0			
Project No.			Drawing File		
25013					
Drawing No.				Rev.	
20-01-01				D	
0 5 10 15 20 25m Scale 1:500					

The details provided on this drawing are subject to comments by all the relevant approving authorities. Until such time as all comments have been received and incorporated onto the drawings, all the information provided and costings, are used at MCI Developments Ltd risk and no liability will be accepted by ALD Design. Scheme based on Site Layout MCI-000-DR-A-500 PL06

Prior to any construction, the contractor must confirm the precise invert level and pipe diameter of the receiving drainage system and must immediately advise ALD Design of any variation to that upon which the design has been based.

Infiltration has been discounted as a suitable means of surface water disposal due to the ground conditions.

Infiltration has been discounted as a suitable means of surface water disposal due to the ground conditions.




The design is based on current guidance however there may be changes in the future by statutory authorities which may have an impact on the current design and surface water storage values and requirements.

Foundations to be designed to take into account any adjacent deep sewers

The highway and sewer designs are subject to technical approval by the Highway Authority and United Utilities, and may be amended in response to review comments.

S185 approval is critical to the design and therefore no works should be undertaken until approval is agreed

System designed not to flood in the 2yr, 30yr & 100yr+45%cc events



The existing steep banking is to be assessed for slope stability, and any recommended safety measures are to be implemented following the findings of a road safety audit

Further survey information is required to confirm the highway drainage design to convey surface water runoff to the existing sewer network in Trub Road.

Ground to be regraded from the back of footpath to the existing headwall, with a maximum gradient of 1 in 2.5. A geotechnical engineer must be consulted prior to works. Crash barriers are to be installed subject to the recommendations of a road safety audit.

Attenuation Basin
Top of bank level - 129.620m
Basin bed level - 127.820m AOD
Permanent 300mm of water basin bed level 127.520m
Side slope - 1:4
Predicted Top water level in 100 year + 45% climate change return period storm event = 129.172m AOD

The attenuation basin level has been raised to minimise extensive remedial works associated with peat conditions and the high water table.

A 2 m high earth acoustic bund is to be constructed with a 2 m high acoustic fence installed on top. Final heights to be confirmed by the client.

Flow Control Manhole - H81
Hydro International HydroBrake Optimum
SHE-0210-2850-2500-2850
Design head = 2.50m
Discharge Rate = 28.50l/s
Flow control orifice size 210mm

The existing high-pressure gas main is to be accurately located, and guidance must be sought from the relevant gas authority.

The existing high-pressure gas main is to be accurately located, and guidance must be sought from the relevant gas authority.

- GENERAL**
- All adoptable sewers and associated works are to comply fully with "Design and Construction Guidance" & Local Practices
 - All highway works to be to adoptable standards and to comply fully with the Local Authority specification.
 - All private drainage works are to comply fully with part II of the Building Regulations
 - All existing invert levels to be checked by the Contractor at the start of works and any discrepancies notified to ALD Design. All levels are based on topographical survey information provided by others.
 - All materials to bear the relevant B.S.Kitemark and comply fully with the specifications.
All concrete & concrete products must use Sulphate resistant cement (unless the site investigation report proves that sulphate attack from soils and groundwater will not occur)
 - All opening notices etc. as required under highways acts etc. are to be obtained prior to commencement of works.
All works are to be inspected by L.A., NHBC or Relevant Water Authority as applicable.

C.D.M. REGULATIONS 2015
In line with the above regulations we are obliged to inform the Client of their responsibilities under section CDM 15/1, and residual risks that may be encountered in the construction of these works.
All design work has been carried out with Health and Safety aspects given full consideration.
Wherever possible risks have been eliminated from the design, however due to the very nature of this type of work it is not possible to remove all the risks from the design.
We would also respectfully remind the Client of his obligations to take all reasonable steps in ensuring that only competent Contractors who have a valid safety policy are employed.
They should also provide satisfactory responses at tender stage as to the manner in which they will deal with the elements of risk involved in this type of work and in particular those highlighted by ALD Design below:-

- Support / treatment for ALL excavation work.
- Guarding to edges of excavations to prevent people, materials and vehicles falling into excavation.
- Guarding of excavations outside working hours to prevent unauthorised access.
- Undermining to adjacent roads or structures.
- Confined space operations.
- Dealing with existing services.
- Traffic management on existing highways.
- Procedure to be followed in event of accident or emergency.
- Method of working where contaminated ground is present on site.
- Confirmation will be required that all operatives are adequately trained, copies of relevant training certificates to be supplied.

The above list is by no means exhaustive but it does highlight operations that present a risk to contractors and the general public.
For clarification on any item please contact ALD Design.

Legend:

- Proposed foul water sewer and manhole
- Proposed surface water sewer and manhole
- Existing surface water sewer & manhole
- Existing combined water sewer & manhole
- Existing surface water sewer & manhole to be abandoned
- Existing combined water sewer & manhole to be abandoned
- Denotes proposed surface water attenuation basin
- Denotes finished floor levels
- Proposed Sewer Easment
- Proposed Tree pit locations
- Proposed Rain Garden locations

Rev.	Date	Amendment	Drawn	Chkd.	Appd.
D	11.07.25	Suds feature locations added	AP		
C	23.06.25	Revised attenuation basin levels and sewers	AP		
B	12.06.25	Redesign to Accommodate Proposed Foul Water Levels	AP		
A	22.05.25	First Issue	AP		



3 Woodhurst Drive, Standish,
Wigan, WN4 0RN, United Kingdom
Tel: +44 (0) 1257 880003

Client					
Project Title	Trub Farm Rochdale				
Status	Preliminary				
Drawing Title	Adoptable Drainage Layout Sheet 2 of 2				
Drawn	Date	Checked	Date	Approved	Date
AP	May 25				
Scale	1:500	Orig Size	A0	Dimensions	
Project No.	25013		Drawing File		
Drawing No.	20-01-02			Rev.	D

Scale 1:500
0 5 10 15 20 25m

APPENDIX D:



D08.07.25PTTREE PIT CATCHMENT AREAS INDICATED

REV	DATE	DRAWN	DESCRIPTION	ARCH CHECK	ENG CHECK

TITLE

SuDS Features Sketch Plan



MCI

A KEEPMOAT HOMES COMPANY

M.C.I. Developments Ltd.

15 Beecham Court,

Smithy Brook Road,

Wigan, WN3 6PR

tel: 08448871467

fax: 08448871468

web: www.mcidevelopments.com

email: admin@mcidevelopments.com

PROJECT

TRUB FARM, ROCHDALE

DRN BY	SCALE	JOB REF	DRAWING NUMBER	REV
PT	1:500 @ A0	0102	MCI-TRUBSUDES-SK1	D
DATE	June 25			