

BS 5837 Tree Survey – 107 Marland Fold – Rochdale – OL11 4RF – 11th March 2024

Tree Number	Species	Height (m)	DBH (mm)	Crown Spread N,E,S,W (m)	Life Stage	General Observations	SULE (Years)	Retention category
T1	Beech	20	650	9-6-4-6	M	A good tree to be retained and protected throughout project. No work required.	50+	A
T2	Sycamore	15	500	9-6-7-6	M	A good tree to be retained and protected throughout project. Reduce 1 x limb by 2-3m from over property.	50+	B
T3	Sycamore	16	550	6-4-7-6	M	A good tree to be retained and protected throughout project. No work required.	50+	B
T4	Hawthorn	5	250 200	1-2-4-2	SM	A poor tree to be retained and protected throughout project. No work required.	10+	C
T5	Sycamore	16	16	5-5-6-3	M	A reasonable tree to be retained and protected throughout project. No work required.	50+	B
T6	Cherry	6	6	2-4-2-3	YM	A reasonable tree to be retained and protected throughout project. No work required.	30+	C
T7	Pine	8	8	4-4-4-4	YM	A good tree to be retained and protected throughout project. No work required.	50+	B
G1	Beech, Sycamore, Elder	3-5	100-150	-----	Y	A group of mixed species and mixed quality to be retained and protected throughout project. No work required.	30+	C

DBH – Diameter at Breast Height

SULE – Safe Useful Life Expectancy

Life Stage – OM = Over Mature – M = Mature – YM = Young Mature – SM = Semi Mature – Y = Young.