



adeptus
CONSULTING

COAL MINING RISK ASSESSMENT

LAND ADJACENT TO 27 BROOKDALE

ROCHDALE

OL12 0SS

On behalf of:

Shah Latif

Report No.: A230605-R02

Date: August 2023

Adeptus Consulting

14 Commercial Street

Manchester

M15 4PZ

T: +44 (0)161 667 1292

F: +44 (0)161 667 1292

E: contact@adeptus.co.uk

Document Control Record

Client: Shah Latif

Project Title: Land Adjacent To 27 Brookdale, Rochdale OL12 0SS

Report Title: Coal Mining Risk Assessment

Report No.: A230605-R02

Issue: B

Status: For issue

Comments -

Written by: D. Fisher

Checked by: N. Dixon

Control Date: August 2023

Confidentiality

This report was prepared by Adeptus for the use of the client, named on page 1. The report has been prepared specifically on the basis of the end use as defined by the client. Any change of end use would necessitate review of this report and its findings. Use of or reliance on this report by any third party is not permitted without our express written agreement, and where this is given, will be subject to our terms and conditions.

Table of Contents

LAND ADJACENT TO 27 BROOKDALE.....	1
1 INTRODUCTION.....	4
1.1 Background & Objectives.....	4
1.2 Scope of Coal Mining Risk Assessment	4
1.3 Previous Reports & Supporting Information	4
2 SITE DETAILS & PROPOSALS.....	5
2.1 Location and Description	5
2.2 Anticipated Geology	6
3 SITE-SPECIFIC COAL MINING HAZARDS.....	6
3.1 Coal Authority Data Review	6
4 RISK ASSESSMENT & MITIGATION	7
4.1 Risk Assessment.....	7
4.2 Mitigation Measures	7
4.0 Conclusions.....	7
APPENDIX A – SITE PLAN.....	8
APPENDIX B – INFORMATION SOURCES	9
APPENDIX C – COAL AUTHORITY REPORT	10
APPENDIX D – LIMITATIONS	11

1 INTRODUCTION

1.1 Background & Objectives

Adeptus was appointed by Shah Latif to undertake a Coal Mining Risk Assessment (CMRA) for a proposed residential development at the site known as Land adjacent to 27 Brookdale, in support of a planning application.

1.2 Scope of Coal Mining Risk Assessment

The objectives of the report are to:

- Present a desk-based review of all available information on the coal mining issues which are relevant to the application site;
- Use that information to identify and assess the risks to the proposed development from coal mining legacy, including the cumulative impact of issues;
- Set out appropriate mitigation measures to address the coal mining legacy issues affecting the site, including any necessary remedial works and/or demonstrate how coal mining issues have influenced the proposed development;
- Demonstrate to the Local Planning Authority that the application site is, or can be made, safe and stable to meet the requirements of national planning policy with regard to development on unstable land.

1.3 Previous Reports & Supporting Information

At the time of writing, no third-party reports have been made available to Adeptus.

A site plan is included as Appendix A.

Other sources of information utilised in producing this report are listed as Appendix B.

2 SITE DETAILS & PROPOSALS

This section provides a review of the land use on and in the vicinity of the Site, with reference to past, present and future mining activity.

2.1 Location and Description

Table 2-1: Site Summary

Location	The site is situated north of Brookdale in a predominantly residential area north of Rochdale.
Area & Coordinates	0.05ha. 389353 415369 (centred on, approx.)
Development Proposals	A pair of semi-detached dorma bungalows with gardens and driveways.



Figure 2-1: Site Location (based on the plan in Appendix A)

2.2 Anticipated Geology

According to BGS data, the following geological sequence prevails locally.

- Drift deposits comprising Glacial Till (diamict) of Devensian age
- Bedrock comprising Sandstone of the Helpet Edge Rock member of the Pennine Lower Coal Measures Formation

Drift deposits are known to be of around 5m thickness in this area.

3 SITE-SPECIFIC COAL MINING HAZARDS

3.1 Coal Authority Data Review

3.1.1 Past Mining Activity

The Coal Authority data indicate workings in the Lower Mountain Coal seam underlie the site, at a depth of 19m and with an extraction thickness of 0.5m. The last year of mining is said to be 1910.

3.1.2 Mine Entries/Adits

None recorded within 100 metres of the enquiry boundary.

3.1.3 Coal Mining Geology

No outcrops recorded.

No relevant faults, fissures or break lines recorded.

3.1.4 Site investigations

None recorded within 50 metres of the enquiry boundary.

3.1.5 Remediated sites

None recorded within 50 metres of the enquiry boundary.

3.1.6 Present Mining Activity

The site is not shown to within an area of current underground or surface opencast mining and none is recorded within 200m of the site boundary.

3.1.7 Future Mining Activity

The Coal Authority reports that the site is not in an area where it would be affected by planned future coal mining or surface workings.

3.1.8 Coal Mining Licensing

None recorded within 200 metres of the enquiry boundary.

3.1.9 Section 46 notices

No notices have been given, under section 46 of the Coal Mining Subsidence Act 1991, stating that the land is at risk of subsidence.

3.1.10 Intrusive Investigations

At the time of writing no existing intrusive investigation information has been supplied for this site.

4 RISK ASSESSMENT & MITIGATION

4.1 Risk Assessment

Based on a seam thickness of 0.5m, there is considered to be greater than ten times seam thickness of bedrock overlying the workings. Indeed, even given a depth to rockhead of 10m there would be around 18 times seam thickness overlying any workings in the Lower Mountain Coal at 19m depth.

In reality, rockhead is likely to be at circa 5m BGL, giving cover over any workings of circa 25 times seam thickness.

4.2 Mitigation Measures

Based on the recorded thickness and depth of working present as well as mapped geology, Adeptus considers that no specific mitigation measures are required.

4.0 CONCLUSIONS



Adeptus was appointed by Shah Latif in June 2021 to undertake a Coal Mining Risk Assessment (CMRA) for a proposed residential development at Land adjacent to 27 Brookdale, OL12 0SS.

According to the Coal Authority, the site is underlain by former mine workings in the Lower Mountain Coal seam at a depth of 19m and with a thickness of 0.5m. On this basis there is considered to be sufficient rock cover above the workings to mitigate any potential effects.

Adeptus considers that no specific mitigation measures are required.

However, it is stressed however that Coal Authority approval must be obtained before proceeding with any works.

APPENDIX A – SITE PLAN



FENCING DETAILS
SCALE 1:100



KEY

SITE BOUNDARY

Project:
Proposed Housing Scheme
Client:
Mr S Latif
Site:
**Land adjacent to 27 Brookdale,
Rochdale OL12 0SS**

Scale
1:100 @ A3

Date:
April 2023
Dwg No:
2004 02

PROPOSED SITE LAYOUT

APPENDIX B – INFORMATION SOURCES

The following information and data sources are utilised in compiling this report:

- Geological maps of the vicinity
- Coal Authority Consultants Coal Mining Report

This report is based on information available at the time of writing and is subject to the limitations set out in Appendix D.

APPENDIX C – COAL AUTHORITY REPORT




The Coal
Authority

Consultants Coal Mining Report

27, Brookdale, Rochdale, OL12 0ss
Greater Manchester

Date of enquiry:	12 June 2023
Date enquiry received:	12 June 2023
Issue date:	12 June 2023

Our reference:	51003360467001
Your reference:	GS-MTW-1G9-I2H-3BF



Consultants

Coal Mining Report

This report is based on and limited to the records held by the Coal Authority at the time the report was produced.

Client name

GROUNDSURE LIMITED

Enquiry address

27, Brookdale, Rochdale, OL12 0ss
Greater Manchester

How to contact us

0345 762 6848 (UK)
+44 (0)1623 637 000 (International)

200 Lichfield Lane
Mansfield
Nottinghamshire
NG18 4RG


www.groundstability.com

 @coalauthority

 /company/the-coal-authority

 /thecoalauthority

 /thecoalauthority



Approximate position of property



Reproduced by permission of
Ordnance Survey on behalf of
HMSO. © Crown copyright and
database right 2018. All rights
reserved.

Ordnance Survey Licence number: 100020315

Section 1 – Mining activity and geology

Past underground mining

Colliery	Seam	Mineral	Coal Authority reference	Depth (m)	Direction to working	Dipping rate of seam worked (degrees)	Dipped direction of seam worked	Extraction thickness (cm)	Year last mined
unnamed	LOWER MOUNTAIN	Coal	3W5M	19	Beneath Property	10.0	South-East	50	1910

Probable unrecorded shallow workings

None.

Spine roadways at shallow depth

No spine roadway recorded at shallow depth.

Mine entries

None recorded within 100 metres of the enquiry boundary.

Abandoned mine plan catalogue numbers

The following abandoned mine plan catalogue numbers intersect with some, or all, of the enquiry boundary:

NW163	16820	PO0
-------	-------	-----

Please contact us on 0345 762 6848 to determine the exact abandoned mine plans you require based on your needs.

Outcrops

No outcrops recorded.

Geological faults, fissures and breaklines

No faults, fissures or breaklines recorded.

Opencast mines

None recorded within 500 metres of the enquiry boundary.

Coal Authority managed tips

None recorded within 500 metres of the enquiry boundary.

Section 2 – Investigative or remedial activity

Please refer to the 'Summary of findings' map (on separate sheet) for details of any activity within the area of the site boundary.

Site investigations

None recorded within 50 metres of the enquiry boundary.

Remediated sites

None recorded within 50 metres of the enquiry boundary.

Coal mining subsidence

The Coal Authority has not received a damage notice or claim for the subject property, or any property within 50 metres of the enquiry boundary, since 31 October 1994.

There is no current Stop Notice delaying the start of remedial works or repairs to the property.

The Coal Authority is not aware of any request having been made to carry out preventive works before coal is worked under section 33 of the Coal Mining Subsidence Act 1991.

Mine gas

None recorded within 500 metres of the enquiry boundary.

Mine water treatment schemes

None recorded within 500 metres of the enquiry boundary.

Section 3 – Licensing and future mining activity

Future underground mining

None recorded.

Coal mining licensing

None recorded within 200 metres of the enquiry boundary.

Court orders

None recorded.

Section 46 notices

No notices have been given, under section 46 of the Coal Mining Subsidence Act 1991, stating that the land is at risk of subsidence.

Withdrawal of support notices

The property is not in an area where a notice to withdraw support has been given.

The property is not in an area where a notice has been given under section 41 of the Coal Industry Act 1994, cancelling the entitlement to withdraw support.

Payments to owners of former copyhold land

The property is not in an area where a relevant notice has been published under the Coal Industry Act 1975/Coal Industry Act 1994.

Section 4 – Further information

The following potential risks have been identified and as part of your risk assessment should be investigated further.

Future development

If development proposals are being considered, technical advice relating to both the investigation of coal and former coal mines and their treatment should be obtained before beginning work on site. All proposals should apply specialist engineering practice required for former mining areas. No development should be undertaken that intersects, disturbs or interferes with any coal or coal mines without first obtaining the permission of the Coal Authority.

MINE GAS: Please note, if there are no recorded instances of mine gas within 500m of the enquiry boundary, this does not mean that mine gas is not present within the vicinity. The Coal Authority Mine Gas data is limited to only those sites where a Mine Gas incident has been recorded. Developers should be aware that the investigation of coal seams, mine workings or mine entries may have the potential to generate and/or displace underground gases. Associated risks both to the development site and any neighbouring land or properties should be fully considered when undertaking any ground works. The need for effective measures to prevent gases migrating onto any land or into any properties, either during investigation or remediation work, or after development must also be assessed and properly addressed. In these instances, the Coal Authority recommends that a more detailed Gas Risk Assessment is undertaken by a competent assessor.

Development advice

The site is within an area of historical coal mining activity. Should you require advice and/or support on understanding the mining legacy, its risks to your development or what next steps you need to take, please contact us.

For further information on specific site or ground investigations in relation to any issues raised in Section 4, please call us on 0345 762 6848 or email us at groundstability@coal.gov.uk.

Section 5 – Data definitions

The datasets used in this report have limitations and assumptions within their results. For more guidance on the data and the results specific to the enquiry boundary, please **call us on 0345 762 6848** or **email us at groundstability@coal.gov.uk**.

Past underground coal mining

Details of all recorded underground mining relative to the enquiry boundary. Only past underground workings where the enquiry boundary is within 0.7 times the depth of the workings (zone of likely physical influence) allowing for seam inclination, will be included.

Probable unrecorded shallow workings

Areas where the Coal Authority believes there to be unrecorded coal workings that exist at or close to the surface (less than 30 metres deep).

Spine roadways at shallow depth

Connecting roadways either, working to working, or, surface to working, both in-seam and cross measures that exist at or close to the surface (less than 30 metres deep), either within or within 10 metres of the enquiry boundary.

Mine entries

Details of any shaft or adit either within, or within 100 metres of the enquiry boundary including approximate location, brief treatment details where known, the mineral worked from the mine entry and conveyance details where the mine entry has previously been sold by the Authority or its predecessors British Coal or the National Coal Board.

Abandoned mine plan catalogue numbers

Plan numbers extracted from the abandoned mines catalogue containing details of coal and other mineral abandonment plans deposited via the Mines Inspectorate in accordance with the Coal Mines Regulation Act and Metalliferous Mines Regulation Act 1872. A maximum of 9 plan extents that intersect with the enquiry boundary will be included. This does not infer that the workings and/or mine entries shown on the abandonment plan will be relevant to the site/property boundary.

Outcrops

Details of seam outcrops will be included where the enquiry boundary intersects with a conjectured or actual seam outcrop location (derived by either the British Geological Survey or the Coal Authority) or intersects with a defined 50 metres buffer on the coal (dip) side of the outcrop. An indication of whether the Coal Authority believes the seam to be of sufficient thickness and/or quality to have been worked will also be included.

Geological faults, fissures and breaklines

Geological disturbances or fractures in the bedrock. Surface fault lines (British Geological Survey derived data) and fissures and breaklines (Coal Authority derived data) intersecting with the enquiry boundary will be included. In some circumstances faults, fissures or breaklines have been known to contribute to surface subsidence damage as a consequence of underground coal mining.

Opencast mines

Opencast coal sites from which coal has been removed in the past by opencast (surface) methods and where the enquiry boundary is within 500 metres of either the licence area, site boundary, excavation area (high wall) or coaling area.

Coal Authority managed tips

Locations of disused colliery tip sites owned and managed by the Coal Authority, located within 500 metres of the enquiry boundary.

Site investigations

Details of site investigations within 50 metres of the enquiry boundary where the Coal Authority has received information relating to coal mining risk investigation and/or remediation by third parties.

Remediated sites

Sites where the Coal Authority has undertaken remedial works either within or within 50 metres of the enquiry boundary following report of a hazard relating to coal mining under the Coal Authority's Emergency Surface Hazard Call Out procedures.

Coal mining subsidence

Details of alleged coal mining subsidence claims made since 31 October 1994 either within or within 50 metres of the enquiry boundary. Where the claim relates to the enquiry boundary confirmation of whether the claim was accepted, rejected or whether liability is still being determined will be given. Where the claim has been discharged, whether this was by repair, payment of compensation or a combination of both, the value of the claim, where known, will also be given.

Details of any current 'Stop Notice' deferring remedial works or repairs affecting the property/site, and if so the date of the notice.

Details of any request made to execute preventative works before coal is worked under section 33 of the Coal Mining Subsidence Act 1991. If yes, whether any person withheld consent or failed to comply with any request to execute preventative works.

Mine gas

Reports of alleged mine gas emissions received by the Coal Authority, either within or within 500 metres of the enquiry boundary that subsequently required investigation and action by the Coal Authority to mitigate the effects of the mine gas emission. Please note, if there are no recorded instances of mine gas reported, this does not mean that mine gas is not present within the vicinity. The Coal Authority Mine Gas data is limited to only those sites where a Mine Gas incident has been recorded.

Mine water treatment schemes

Locations where the Coal Authority has constructed or operates assets that remove pollutants from mine water prior to the treated mine water being discharged into the receiving water body.

These schemes are part of the UK's strategy to meet the requirements of the Water Framework Directive. Schemes fall into 2 basic categories: Remedial – mitigating the impact of existing pollution or Preventative – preventing a future pollution incident.

Mine water treatment schemes generally consist of one or more primary settlement lagoons and one or more reed beds for secondary treatment. A small number are more specialised process treatment plants.

Future underground mining

Details of all planned underground mining relative to the enquiry boundary. Only those future workings where the enquiry boundary is within 0.7 times the depth of the workings (zone of likely physical influence) allowing for seam inclination will be included.

Coal mining licensing

Details of all licenses issued by the Coal Authority either within or within 200 metres of the enquiry boundary in relation to the under taking of surface coal mining, underground coal mining or underground coal gasification.

Court orders

Orders in respect of the working of coal under the Mines (Working Facilities and Support) Acts of 1923 and 1966 or any statutory modification or amendment thereof.

Section 46 notices

Notice of proposals relating to underground coal mining operations that have been given under section 46 of the Coal Mining Subsidence Act 1991.

Withdrawal of support notices

Published notices of entitlement to withdraw support and the date of the notice. Details of any revocation notice withdrawing the entitlement to withdraw support given under Section 41 of the Coal Industry Act 1994.

Payment to owners of former copyhold land

Relevant notices which may affect the property and any subsequent notice of retained interests in coal and coal mines, acceptance or rejection notices and whether any compensation has been paid to a claimant.


The map highlights any specific surface or subsurface features within or near to the boundary of the site.

Key

Approximate position of the enquiry boundary shown 

How to contact us

0345 762 6848 (UK)
+44 (0)1623 637 000 (International)
www.groundstability.com



APPENDIX D – LIMITATIONS

This report was prepared by Adeptus (registered in England: 05908395) for the use of the client, named on page 1. The report has been prepared specifically on the basis of the end use as defined by the client. Any change of end use would necessitate review of this report and its findings. Use of or reliance on this report by any third party is not permitted without our express written agreement, and where this is given, will be subject to our terms and conditions.

We have prepared this report in our professional capacity using reasonable skill, care and diligence. The assessments, conclusions and recommendations within this report pertain to the study site (the extents of which are in Figure 1, below) and the immediate area in continuity with the Site. They are based on the established historical uses, information available at the time of writing and the proposed use of the Site. Where any information supplied by the client or other sources have been utilised, it has been assumed that the information is correct. No responsibility can be accepted by Adeptus for inaccuracies in data supplied by any other party.

Any plans, diagrams, cross sections or images are for illustrative purposes only and should be checked for accuracy on-site. In the event of changes to the proposed end use of the Site, the report may require updating to reflect such changes. Although reference may be made to archaeological, ecological or geotechnical issues, invasive species, flood risk and the presence of asbestos containing materials (ACMs), this report does not constitute an archaeological assessment, ecological assessment, geotechnical assessment, invasive species survey, flood risk assessment or asbestos survey and liability for any claim caused by arising out of or in any way involving asbestos is excluded.

New information relating to environmental matters can come to light after the report has been prepared and changes in conditions and regulatory requirements may occur in future. Either of those factors may change the conclusions presented in our report. If development does not take place within the expected timescales, consideration should be given to reviewing this assessment to confirm that no changes to the site or relevant legislation have taken place. No part of this report is intended to provide legal advice or opinion of any nature.
