

PEAK acoustics



Noise Impact Assessment

Client: Newell John

Site: 237 Milnrow Road, Rochdale, OL16 5AS

Reference No. 2701251

Revision: 0

Date of Issue: 13/03/2025

Project Consultant

T. Brown BSc (Hons) MIOA
Acoustic Consultant
tom@acousticsurveys.co.uk

Email: office@acousticsurveys.co.uk | **Office** 0330 043 1764

Web: www.acousticsurveys.co.uk

Executive Summary

A noise assessment has been undertaken at 237 Milnrow Road, Rochdale in relation to the proposed change of use of the site to an HMO.

Environmental noise monitoring has been undertaken at the site from 28th February to 3rd March 2025. Noise affecting the development was determined to be primarily from road traffic on Milnrow Road.

A glazing and ventilation scheme has been given to ensure conditions in habitable rooms remain within the desired design criteria of BS8233:2014. The derived scheme is summarised below.

Glazing & Ventilation Scheme

Internal Space	Glazing		Ventilation	
	Minimum Performance $R_w (+C_{tr})$	Example Specification	Minimum Performance $D_{ne,W,+C_{tr} (Open)}$	Example Specification
Front Bedrooms	42 (35)	8/16/8.8SC	52	Powered Attenuated Vent: Titon Sonair F+
Rear Bedrooms	30 (26)	4/16/4	32	Hit & Miss Trickle Vent (Open)
Kitchen / Dining Room	30 (26)	4/16/4	32	Hit & Miss Trickle Vent (Open)

Internal noise levels are anticipated to be within the guidelines of BS8233 with comments from ProPG.

Contents

Executive Summary	2
1. Introduction	4
1.1. Proposal	4
1.2. Reason for Assessment.....	4
1.3. Planning Conditions	4
1.4. Assessment Guidance Documentation.....	4
2. Environmental Noise Survey	4
2.1. Survey Measurement	4
2.2. Measurement Location	4
2.3. Site Descriptions	5
2.4. Noise Affecting the Development	5
2.5. Environmental Noise Survey Results	6
2.6. Weather Conditions.....	6
2.7. Measurement Equipment	6
3. Internal Noise Level Assessment	6
3.1. Design Criteria	6
3.2. Assessment Noise Levels	7
3.3. Internal Noise Calculations.....	7
4. Sound Insulation Scheme.....	8
4.1. External Building Envelope	8
4.2. Glazing and Ventilation	8
5. Internal Noise Levels	9
6. External Amenity Areas.....	9
7. Conclusions	9
APPENDIX A – Measurement Details	11
APPENDIX B - Equipment Details	11
APPENDIX C - Meteorology Details	11
APPENDIX D - Calibration Details	11
APPENDIX E – Noise Survey Time History	12
APPENDIX F – BS8233 Rigorous Design Calculations	14
APPENDIX G – Site Plans	19
APPENDIX H – Legislation, Policy and Guidance	20
APPENDIX I – Acoustic Terminology	22
APPENDIX J – Recommended Example Roof Specification.....	23

1. Introduction

1.1. Proposal

It is proposed to convert the existing dwelling at 237 Milnrow Road to an 8-bed HMO including ground, 1st and 2nd floor rooms.

1.2. Reason for Assessment

A noise assessment is to be submitted as part of the planning application to ensure desirable noise levels are met within the habitable rooms of the proposed development and external amenity areas. The assessment aims to provide a sound insulation scheme for the development.

1.3. Planning Conditions

No planning conditions have yet been set for the development however pre-application guidance from the local authority requests that a noise impact assessment be submitted for the proposals.

1.4. Assessment Guidance Documentation

Guidance on the assessment and design criteria will be drawn from BS8233:2014 - *Guidance on sound insulation and noise reduction for buildings*. Table 4 in Section 7.7.2 of this standard suggests indoor ambient noise levels for dwellings.

Additional guidance will be drawn from 'ProPG: Planning & Noise' which was published *"to provide practitioners with guidance on a recommended approach to the management of noise within the planning system in England."*

Where necessary, mitigation recommendations will be given to comply with the requirements of the National Planning Policy Framework (2024) and the Noise Policy Statement for England (2010). Further information on all guidance documentation can be found in **Appendix H**.

2. Environmental Noise Survey

2.1. Survey Measurement

To assess the environmental noise levels affecting the proposed development, an unattended noise survey has been undertaken at the site from 28th February – 3rd March 2025. This period was selected to capture events and noise levels on across typical weekday and weekend periods from Milnrow Road (A640) as well as noise from other nearby residential and commercial sources.

Measurements of $L_{Aeq,T}$ and L_{AFmax} were logged in 5- minute intervals in accordance with the provisions of BS7445 - 'Description and Measurement of Environmental Noise'.

2.2. Measurement Location

Monitoring positions M1 and M2 were located to the front and rear of the site respectively. The microphones were positioned approximately 4.5 metres above ground level via 1st floor windows.

The site and monitoring locations are shown below in **Figure 1**:




Figure 1: Site & Measurement Locations – [google.com/maps](https://www.google.com/maps)

● Monitoring Location (M1)

— Site Boundary (Approx.)

● Monitoring Location (M2)

2.3. Site Descriptions

The site is located mid terrace on Milnrow Road in Rochdale. To the front of the site is the A640 (Milnrow Road) which links Rochdale centre to the M62. Opposite the site is the junction with Bertha Road. There is a hairdresser adjacent to the site at ground floor level while other properties in the terrace are residential. To the rear of the site is a small yard area and rear access for adjacent properties.

2.4. Noise Affecting the Development

The primary noise source affecting the development was identified as road traffic on Milnrow Road. Secondary sources were noted as intermittent noise from the trainline to the west and vehicles visiting the tyre shop to the north of the site.

2.5. Environmental Noise Survey Results

The results from the noise monitoring locations M1 and M2 are summarised below.

The full-time history of the noise monitoring data is given in **Appendix E**.

Measurement	Date(s)	Period	L _{Aeq} (dB)	Typical* L _{AFmax} (dB)
M1	28 th Feb 2025	Day (13:30 – 23:00)	68	-
	28 th Feb – 1 st Mar 2025	Night (8hr)	63	84
	1 st Mar 2025	Day (16hr)	68	-
	1 st – 2 nd Mar 2025	Night (8hr)	62	84
	2 nd Mar 2025	Day (16hr)	67	-
	2 nd – 3 rd Mar 2025	Night (8hr)	62	81
	3 rd Mar 2025	Day (07:00 – 09:30)	70	-
M2	28 th Feb 2025	Day (13:40 – 23:00)	51	-
	28 th Feb – 1 st Mar 2025	Night (23:00 – 01:10)	47	64

Table 1: Environmental Measurement Summary

* The given 'Typical' L_{AFmax} levels are an average of the spectra of the noisiest 10 events of the night-time period.

2.6. Weather Conditions

Daytime temperatures of between 4 - 7°C were noted during the survey with winds of 1 – 3m/s. Detailed weather conditions are given in **Appendix C**.

2.7. Measurement Equipment

Measurement equipment complies with accuracy requirements for common environmental noise measurement standards. Equipment was calibrated before and after use and no significant drift occurred during measurements. Up-to-date calibration certification can be provided upon request. A detailed equipment list is given in **Appendix B** with calibration information in **Appendix D**.

3. Internal Noise Level Assessment

3.1. Design Criteria

BS8233:2014 - *Guidance on sound insulation and noise reduction for buildings* suggests indoor ambient noise levels for dwellings in Table 4, Section 7.7.2. These are summarised below.

Activity	Location	07:00 to 23:00	23:00 to 07:00
Resting	Living Room	35 dB L _{Aeq,16hour}	-
Dining	Dining room/area	40 dB L _{Aeq,16hour}	-
Sleeping	Bedroom	35 dB L _{Aeq,16hour}	30 dB L _{Aeq,8hour}

Table 2: Indoor Ambient Noise Levels for Dwellings

BS8233 states that the guideline values given above are for 'noise without character', further stating:

“Noise has a specific character if it contains features such as a distinguishable, discrete and continuous tone, is irregular enough to attract attention, or has strong low-frequency content, in which case lower noise limits might be appropriate.”

Table 4 of BS8233 also has accompanying notes that were subject to additions in ProPG. The relevant notes with the additions of ProPG are given below.

“In most circumstances in noise sensitive rooms at night (e.g. bedrooms) good acoustic design can be used so that individual noise events do not normally exceed 45dB LA_{max,F} more than 10 times a night.”

In considering the noise climate affecting the proposed development, as discussed in Section 2.4, it is deemed appropriate to use guidelines set out in BS8233 and ProPG to ensure the internal criteria set out by the WHO for internal noise maxima L_{Amax} and internal L_{Aeq}.

3.2. Assessment Noise Levels

In the interest of a robust assessment, the loudest of the measurement intervals, subject to irregular events, are to be considered in the assessment of internal noise levels and determining the sound insulation scheme.

The resultant external noise levels for the assessment of internal ambient noise levels are summarised in the table below.

Facade	Period	L _{Aeq,T} (dB)	L _{Amax} (dB)
Front	Daytime (1hr)	70	-
	Night (1hr)	67	84
Rear	Daytime (1hr)	53	-
	Night (1hr)	48	64

Table 3: Assessment Noise Levels

3.3. Internal Noise Calculations

Internal noise levels have been calculated to demonstrate that the proposed dwellings can achieve the desired design criteria when appropriate glazing and ventilation systems are utilised.

Internal arrangements of the dwellings have been submitted by the client, proposed drawings by ‘Mark Gordon Design Associates’ have been used to scale room and glazing dimensions and can be found in **Appendix G**.

Assessment is not required for each individual room therefore a worst-case situation will be used in which the worst affected rooms/floors will be used.

Calculations of internal ambient noise levels have been undertaken using the ‘rigorous calculation’ method given in Annex G2 of BS8233:2014. Full details of the calculations are provided in **Appendix F**.

4. Sound Insulation Scheme

4.1. External Building Envelope

Material build-up of the façade will significantly dictate the noise levels within the proposed dwelling. For the purposes of this report, the heavyweight construction of the façade is assumed to provide a minimum sound reduction of 49 dB R_w .

The proposed HMO has rooms within the roof space, a recommended minimum performance of 59dB R_w is utilised within the calculations for the roof element. An example specification is provided within **Appendix J**.

4.2. Glazing and Ventilation

The following glazing and ventilation scheme for the development has been derived with a view of achieving the internal noise level criteria given in Table 2.

Internal Space	Glazing		Ventilation	
	Minimum Performance $R_w (+C_{tr})$ ^[1]	Example Specification ^[2]	Minimum Performance $D_{ne,W,+C_{tr}}$ (Open)	Example Specification ^[3]
Front Bedrooms	42 (35)	8/16/8.8SC	52	Powered Attenuated Vent: Titon Sonair F+
Rear Bedrooms	30 (26)	4/16/4	32	Hit & Miss Trickle Vent (Open)
Kitchen / Dining Room	30 (26)	4/16/4	32	Hit & Miss Trickle Vent (Open)

Table 4: Glazing & Ventilation Scheme

N.B. Note that other glazing configurations and ventilators can achieve the given minimum performance requirements.

[1] The sound insulation value of the glazing should take into account the glass as well as the frame and perimeter seal.

[2] Example glazing specification format given as 'XXmm Float / 16mm Air gap / XXmm Float'

[3] It is noted that BS8233 section 7.2.2 states 'If relying on closed windows to meet the guide values, there needs to be an appropriate alternative ventilation that does not compromise the façade insulation or the resulting noise level'. This statement implies that the use of closed windows and an alternative means of ventilation is acceptable.

5. Internal Noise Levels

It is determined that by using mitigation as specified in **Table 4** for the building façades, the outcome summarised in the following table is achieved.

Internal Space	Noise Parameter	Internal Noise Level (dB)	Within Design Criteria?
Bedrooms – Front	Daytime $L_{Aeq, 16hr}$	30	Yes
	Night-time $L_{Aeq, 8hr}$	27	Yes
	Night-time $L_{Amax, F}$	45	Yes
Bedrooms - Rear	Daytime $L_{Aeq, 16hr}$	27	Yes
	Night-time $L_{Aeq, 8hr}$	22	Yes
	Night-time $L_{Amax, F}$	38	Yes
Kitchen / Dining Room	Daytime $L_{Aeq, 16hr}$	27	Yes

Table 5: Internal Noise Levels

For the daytime assessment for living areas, the desirable limit of BS8233:2014 suggests a guideline of 35 dB $L_{Aeq, 16hr}$ for resting conditions, and up to 40 dB is considered acceptable for necessary developments.

All results, with the implementation of the derived sound insulation scheme given in **Table 4**, would place the internal daytime noise levels below 35 dB, therefore within the desired limit.

For the night-time assessment for bedrooms, BS8233:2014 suggests a desirable guideline of 30 dB $L_{Aeq, 8hr}$ for sleeping conditions, with an acceptable limit of 35 dB $L_{Aeq, 8hr}$.

Implementation of the derived sound insulation scheme given in **Table 4** would place the internal continuous night-time noise levels below 30 dB, therefore within the desirable category.

For the night-time assessment for bedrooms, ProPG suggests that individual noise events do not normally exceed 45dB $L_{Amax, F}$ more than 10 times a night.

Implementation of the derived sound insulation scheme given in **Table 4** would place the internal $L_{Amax, F}$ night-time events below 45 dB, therefore within the criteria.

6. External Amenity Areas

BS8233:2014 provides a desirable guideline of 50 dB $L_{Aeq, 16hr}$ for external amenity spaces and an acceptable guideline of 55 dB $L_{Aeq, 16hr}$ for noisier environments.

External daytime noise levels were measured on-site at position M2 to be 51dB at the rear of the site. This is within the 'acceptable' criteria of BS8233. It is expected that for receivers within amenity areas at the ground floor, noise levels will also be within the 'desirable' guidelines for much of the daytime period once the development is completed.

7. Conclusions

A noise assessment has been undertaken at 237 Milnrow Road, Rochdale in relation to the proposed change of use of the site to an HMO.

Environmental noise monitoring has been undertaken at the site from 28th February to 3rd March 2025. Noise affecting the development was determined to be primarily from road traffic on Milnrow Road.

A glazing and ventilation scheme has been given to ensure conditions in habitable rooms remain within the design criteria.

Internal noise levels are anticipated to be within the guidelines of BS8233 with comments from ProPG.

APPENDIX A – Measurement Details

Measurement(s)	Kit	Start Date	Start Time	End Date	End Time
M1	3	28/02/2025	13:30	03/03/2025	09:30
M2	2	28/02/2025	13:40	01/03/2025	01:10

APPENDIX B - Equipment Details

Kit	Equipment	Make	Model	Class	Serial Number
3	Sound Meter	Svantek	977	1	45494
	Pre-Amp	Svantek	SV12L	1	49995
	Microphone	ACO	7052E	1	72673
2	Sound Meter	Svantek	977A	1	69273
	Pre-Amp	Svantek	SV12L	1	71601
	Microphone	ACO	7052E	1	68217
C2	Calibrator	Svantek	SV33	1	83715


APPENDIX C - Meteorology Details

Date	Temp C°	Wind Speed m/s	Wind Direction	Humidity %	Precipitation mm	Cloud Cover (Oktas)
28/02/2025	7	3	SW	69	0	2/8
03/03/2025	4	1	SE	80	0	7/8


APPENDIX D - Calibration Details

Kit	Calibrator Ref Level (dB)	Deviation Before (dB)	Deviation After (dB)
2	113.80	0.71	0.58
3		0.21	0.23

APPENDIX E – Noise Survey Time History



Environmental Noise Measurement M1 Time History



Environmental Noise Measurement M2 Time History: 28th Feb – 1st Mar 2025

2. 1F - Rear - Bedroom

BS8233:2014 Façade Noise Break In Calculator				
Daytime External Noise Level - LAeq - 1 hour				
Night-time External Noise Level - LAeq - 1 hour				
Night-time Lmax Noise Levels - 10 times per night				
Room Properties				
Width (m)	Height (m)	Depth (m)	Glazing	Reverb Time
4.5	2.4	3	3	0.6
Façade Construction				
Wall Construction	Brick and block, 75mm cavity, 60mm Fibreglass			
Roof Construction	Not Within Roof Space			
Glazing Spec	4 / 16 / 4			
Ventilation Spec	Hit & Miss Trickle Vent (Open)			
Calculation Results				
Daytime Internal Noise Level - LAeq		Target Value <	35	
Night-time Internal Noise Level - LAeq		Target Value <	30	
Internal LAmaz Noise Levels		Target Value <	45	

125	250	500	1k	2k	dBA
52.4	50.9	48.3	49.6	45.9	53
48.9	45.6	40.9	45.1	40.5	48
64.0	60.6	56.7	61.6	57.6	64

Room Coefficient					
8	8	8	9	9	A
0.7	0.7	0.6	0.6	0.6	RT

SRI (Sound Reduction Index)					Rw
31	46	43	49	56	49(44)
0	0	0	0	0	N/A
24	18	26	40	45	30(26)
38.4	36.8	33.8	29.7	33.8	32

125	250	500	1k	2k	dBA
12.5	23.3	19.2	22.1	15.5	27.1
9.1	17.9	11.8	17.5	10.1	21.8
24.2	32.9	27.5	34.0	27.2	37.7

Sound Insulation Requirement

Minimum Sound Insulation Requirement			Suitable Systems
Glazing	30(26)	dB R _{W(+Ctr)}	Double Glazing 4 / 16 / 4
Ventilation	32	D _{n,e,w+Ctr}	Hit & Miss Trickle Vent (Open) Titon Trimvent XS13 4400EA

Suitable systems given as reference only. Other products that achieve the required sound insulation values are available.

Calculations conducted in accordance with BS8233:2014 rigorous calculation method

$$L_{eq,2} = L_{eq,1} + 10 \log_{10} \left(\frac{A_0}{S} 10^{\frac{-D_{st}}{10}} + \frac{S_{wi}}{S} 10^{\frac{-R_{w1}}{10}} + \frac{S_{ew}}{S} 10^{\frac{-R_{w2}}{10}} + \frac{S_{r1}}{S} 10^{\frac{-R_{r1}}{10}} \right) + 10 \log_{10} \left(\frac{S}{A} \right) + 3$$

3. 2F - Front - Bedroom

BS8233:2014 Façade Noise Break In Calculator					
Daytime External Noise Level - LAeq - 1 hour					
Night-time External Noise Level - LAeq - 1 hour					
Night-time Lmax Noise Levels - 10 times per night					
Room Properties					
Width (m)	Height (m)	Depth (m)	Glazing	Reverb Time	
4.7	2.4	2.4	1.5	0.6	
Façade Construction					
Wall Construction	Brick and block, 75mm cavity, 60mm Fibreglass				
Roof Construction	Insul Up rated Tiled Roof				
Glazing Spec	8 / 16 / 8.8SC				
Ventilation Spec	Powered Attenuated Vent				
Calculation Results					
Daytime Internal Noise Level - LAeq			Target Value <	35	
Night-time Internal Noise Level - LAeq			Target Value <	30	
Internal Lmax Noise Levels			Target Value <	45	

125	250	500	1k	2k	dBA
65.5	67.5	65.0	67.1	62.5	70
64.7	63.8	61.8	63.8	59.7	67
82.1	81.4	80.6	78.2	77.4	83

Room Coefficient					
6	7	7	8	8	A
0.7	0.6	0.6	0.5	0.6	RT

SRI (Sound Reduction Index)					Rw
31	46	43	49	56	49(44)
41	50	56	61	60	59(54)
24	31	40	49	51	42(35)
42	48	52	58	65	52

125	250	500	1k	2k	dBA
24.5	25.4	22.5	20.7	13.3	29.8
23.7	21.6	19.3	17.3	10.5	27.2
41.1	39.2	38.1	31.7	28.2	44.8

Sound Insulation Requirement

Minimum Sound Insulation Requirement			Suitable Systems
Glazing	42(35)	dB R _{W(+Ctr)}	Laminated Double Glazing 8 / 16 / 8.8SC
Ventilation	52	D _{n,e,w+Ctr}	Powered Attenuated Vent Titon Sonair F+

Suitable systems given as reference only. Other products that achieve the required sound insulation values are available.

Calculations conducted in accordance with BS8233:2014 rigorous calculation method

$$L_{eq,2} = L_{eq,1} + 10 \log_{10} \left(\frac{A_0}{S} 10^{\frac{-D_{st}}{10}} + \frac{S_{wi}}{S} 10^{\frac{-R_{w1}}{10}} + \frac{S_{ew}}{S} 10^{\frac{-R_{w2}}{10}} + \frac{S_{r}}{S} 10^{\frac{-R_{r}}{10}} \right) + 10 \log_{10} \left(\frac{S}{A} \right) + 3$$

4. 2F - Rear - Bedroom

BS8233:2014 Façade Noise Break In Calculator				
Daytime External Noise Level - LAeq - 1 hour				
Night-time External Noise Level - LAeq - 1 hour				
Night-time Lmax Noise Levels - 10 times per night				
Room Properties				
Width (m)	Height (m)	Depth (m)	Glazing	Reverb Time
3	2.4	3.5	1	0.6
Façade Construction				
Wall Construction	Brick and block, 75mm cavity, 60mm Fibreglass			
Roof Construction	Flat Timber Joist Roof			
Glazing Spec	4 / 16 / 4			
Ventilation Spec	Hit & Miss Trickle Vent (Open)			
Calculation Results				
Daytime Internal Noise Level - LAeq		Target Value <	35	
Night-time Internal Noise Level - LAeq		Target Value <	30	
Internal Lmax Noise Levels		Target Value <	45	

125	250	500	1k	2k	dBA
52.4	50.9	48.3	49.6	45.9	53
48.9	45.6	40.9	45.1	40.5	48
64.0	60.6	56.7	61.6	57.6	64

Room Coefficient					
6	6	7	7	7	A
0.7	0.6	0.6	0.5	0.5	RT

SRI (Sound Reduction Index)					Rw
31	46	43	49	56	49(44)
22	37	43	49	57	0
24	18	26	40	45	30(26)
38.4	36.8	33.8	29.7	33.8	32

125	250	500	1k	2k	dBA
20.3	20.3	18.2	23.6	17.0	27.5
16.9	14.9	10.8	19.0	11.5	22.7
32.0	29.9	26.5	35.5	28.6	38.7

Sound Insulation Requirement

Minimum Sound Insulation Requirement			Suitable Systems
Glazing	30(26)	dB R _{W(+Ctr)}	Double Glazing 4 / 16 / 4
Ventilation	32	D _{n,e,w+Ctr}	Hit & Miss Trickle Vent (Open) Titon Trimvent XS13 4400EA

Suitable systems given as reference only. Other products that achieve the required sound insulation values are available.

Calculations conducted in accordance with BS8233:2014 rigorous calculation method

$$L_{eq,2} = L_{eq,1} + 10 \log_{10} \left(\frac{A_0}{S} 10^{\frac{-D_{st}}{10}} + \frac{S_{wi}}{S} 10^{\frac{-R_{w1}}{10}} + \frac{S_{ew}}{S} 10^{\frac{-R_{w2}}{10}} + \frac{S_{r}}{S} 10^{\frac{-R_{r}}{10}} \right) + 10 \log_{10} \left(\frac{S}{A} \right) + 3$$

5. GF - Rear - Kitchen / Diner

BS8233:2014 Façade Noise Break In Calculator				
Daytime External Noise Level - LAeq - 1 hour				
Night-time External Noise Level - LAeq - 1 hour				
Night-time Lmax Noise Levels - 10 times per night				
Room Properties				
Width (m)	Height (m)	Depth (m)	Glazing	Reverb Time
3	2.4	8	3	0.7
Façade Construction				
Wall Construction	Brick and block, 75mm cavity, 60mm Fibreglass			
Roof Construction	Not Within Roof Space			
Glazing Spec	4 / 16 / 4			
Ventilation Spec	Hit & Miss Trickle Vent (Open)			
Calculation Results				
Daytime Internal Noise Level - LAeq		Target Value <	40	
Night-time Internal Noise Level - LAeq		Target Value <		
Internal LMax Noise Levels		Target Value <		

125	250	500	1k	2k	dBA
52.4	50.9	48.3	49.6	45.9	53

Room Coefficient					
13	13	14	15	14	A
0.7	0.7	0.7	0.6	0.7	RT

SRI (Sound Reduction Index)					Rw
31	46	43	49	56	49(44)
0	0	0	0	0	N/A
24	18	26	40	45	30(26)
38.4	36.8	33.8	29.7	33.8	32

125	250	500	1k	2k	dBA
12.7	21.3	18.9	24.2	17.7	27.4


Sound Insulation Requirement

Minimum Sound Insulation Requirement			Suitable Systems
Glazing	30(26)	dB R _{W(+Ctr)}	Double Glazing 4 / 16 / 4
Ventilation	32	D _{n,e,w+Ctr}	Hit & Miss Trickle Vent (Open) Titon Trimvent XS13 4400EA
Suitable systems given as reference only. Other products that achieve the required sound insulation values are available.			

Calculations conducted in accordance with BS8233:2014 rigorous calculation method

$$L_{eq,2} = L_{eq,1} + 10 \log_{10} \left(\frac{A_0}{S} 10^{\frac{-D_{st}}{10}} + \frac{S_{wi}}{S} 10^{\frac{-R_{w1}}{10}} + \frac{S_{ew}}{S} 10^{\frac{-R_{w2}}{10}} + \frac{S_{r1}}{S} 10^{\frac{-R_{r1}}{10}} \right) + 10 \log_{10} \left(\frac{S}{A} \right) + 3$$

GENERAL NOTES
 All materials and construction works are to comply with current ISI standards and Codes of Practice, Building Regulations and NBSG Standards.
 All materials and construction goods shall be suitable for their purposes and shall be stored, mixed and fixed in accordance with the manufacturers instructions.
 The Contractor shall ascertain and include for all works and necessary materials to complete the works to the complete satisfaction of the Building Inspector and Client whether indicated on this drawing or not.
 Existing elements of structure to be retained on site and to be thermally upgraded, if required to satisfy A CoC 1.
 Sound, healthy and free from the Parts 1/10a



The energy performance of new/replacement windows/doorlight and door fittings to an extension/existing dwelling should comply with the following requirements of L1 Table 4.2 Approved Doc L, Vol 1 (2021 edition):
 Windows/Doorlights should achieve either U-value of 1.40W/m²K OR a WER (Window Energy Rating) Band B
 Doorlights should achieve either U-value of 2.2 W/m²K
 Door Fittings with +80% of internal face glazing should achieve either U-value of 1.40W/m²K OR a WER (Window Energy Rating) Band C
 All other door fittings should achieve U-value of 1.40W/m²K OR a WER (Window Energy Rating) Band B

PARTEAL
All conventional entrance doors and entrance doors into bedrooms are to adequately resist unauthorised access into the dwelling and are to be in accordance with the guidance given in Approved Document Q, 2015 edition.
All easily accessible windows (including easily accessible rooflights) and all external doors are to adequately resist unauthorised access into the dwelling and are to be in accordance with the guidance given in Approved Document Q, 2015 edition. Ensure that 'double lock mechanisms providing background ventilation also provides the appropriate level of security

LIGHTING:
New interior lighting to be in accordance with doc. 3.17, item 3.54 and table 4.

PAINT GRADE TRIMMER DOGS (INTERIOR)
strength class - medium duty
door frame to have a solid construction facing either side with 4mm plywood and provided with blocking for fixing of door assembly as required by the schedule.
All door frames to be finished with a smooth, even and the front and back external doors to have a fluted turning back to the inside vertical edges of doors are to be fixed with minimum 6mm hardwood.
Door leaf is to be primed with 1 coat of thinned lacquer and finished with 2 full coat polyurethane lacquer coats.
New internal timber door frames are to be formed from 6050x125mm hardwood to be 18mm, class 1, dimensions of finished frames to comply with BS/ET/FP/1995. The stops are to be formed integral to the frame. The frames are to be related as follows:
a) The door frame to be fitted to the door leaf is to be formed integral to the door leaf.

ARCHITRAVES
all doors are to be fitted with 25x75mm architraves, where there is no return on the jamb the architrave is to be scribed to create a hand profile.
architraves are to be formed from polyurethane and are to be painted, as the door frames.

PART P:
All work required to meet the requirement of Part P (electrical safety) will be designed, installed, inspected and tested by a person competent to do so.
Prior to completion the local authority must be satisfied that either >
An electrical installation certificate issued under a Competent Person Scheme has been issued or
Appropriate certificates and forms defined in BS 7671 (as amended) have been submitted that confirm that the work has been inspected and tested by a competent person. A competent person will have a sound knowledge and experience, relevant to the nature of the work undertaken and to the technical standards set down in BS 7671, be fully versed in the inspection and testing procedures contained in the regulations and capable of issuing valid certificates.

PART E:
Walls and ceilings that separate all bedrooms from bedrooms and bedrooms from communal areas are to achieve a 42 Db Airborne Sound Reduction Value.
Pre-completion testing of sound insulation between bedrooms and communal areas/buildings, is to be carried out in accordance with the testing procedure formally approved by the secretary of state and is described in Approved Doc E, Annex B, Division 1 of the Building Regulations. Compliance is to be demonstrated by the following:

FIRE AND SMOKE DOORS
 Doorsets within firewalls, as indicated on plans are to be 30 min fire/smoke rated are to have intumescent/seals related into the door or frame as required to comply with the certification procedures of the following British standards:-

FIXING
painted hardwood door frames are to be supplied to also pre-drilled for steel counter-sunk frame anchors, at fixing points in accordance with ba4787/part1:1980.
counter-sunk screw holes are to be filled and sanded prior to receipt of finishes.
door frames are to be packed and wedged at fixing positions to ensure a rigid and secure fit.
construction tolerance between the frame and structural opening, of the noted doors are to be sealed with a proprietary intumescent sealant on a backing rod.

SEALANT
all external windows are to be sealed all round externally with a proprietary silicone sealant, as recommended by the sealant manufacturer, on a polyethylene backing rod to control joint depth.
All sealants are to be worked in accordance with the recommendations of the manufacturer, on suitable primers.

FIRE EXTINGUISHERS
1 no. fire extinguisher placed at Ground Floor within Hallway and 1 placed at first & second floor to landing areas. Where extinguishers are installed they should comply with BS EN 3-7 and be maintained in accordance with BS 5306-3. Suitable instructions should be given to tenants on their correct use at the start of the tenancy.

ESCAPE WINDOWS :
Must have an unobstructed operable area of 0.33sqm and be at least either 450mm high x 750mm wide, or 750mm high x 450mm wide. The bottom of the operable area should not be more than 1150mm above the floor level.

SERVICES.
All work & installations to comply with Regulations & recommendations of the relevant State or Authority, to the satisfaction of the Insurance Company.
Water main to be 750 below ground level & deep to able to be fitted with an insulation sleeve. Gas main to have m6, 375 ground cover. Electricity main to have 400 ground cover & electrical installation to comply with I.E.E. Regulations. Any power running outside insulated shell of building to be insulated. All hot water pipes in roof space & hot water cylinder should be adequately insulated if central heating system is to be provided. Room thermostats or radiator thermostatic valves to be fitted.

Use safe conditions required for any gas appliances. Energy Performance Certificate required for the property.


Part G. Ensure any new combustion appliances (appliances is installed by a competent person. Ensure any new or repositioned flue outlets are at an appropriate distance horizontally from window and/or door openings.

Part G. The potential consumption of wholesome water by persons occupying the flats must not exceed 125 litres per person per year, BDL, to be notified that the calculated consumption rate of wholesome water does not exceed this rate as determined in accordance with the methodology outlined in the water "Water Efficiency calculator for new dwellings."


Ensure new baths are fitted with an appropriate temp. control device which will not allow hot water supply to exceed 48 degrees C in unvented solids.

COMPARTMENTATION
All walls and floors that vertically and horizontally separate each habitable room from other parts of the building should be constructed to achieve 30 minute fire resistance. This will require walls between each floor level and between live and the roof level to be constructed of masonry or concrete. The ceiling and floor surfaces, linings of walls and ceilings on access routes and other circulation areas will have to have a class 0 surface spread of flame rating. All ceilings and roof joints will have to have joints having been tested in accordance with approved European BS.


SMOKE & HEAT DETECTION:
Self-contained smoke alarms are to remain operational with a secondary battery power supply and to be wired to a separate fuse circuit to RLC wiring requirements all in accordance with IIS 5446. Smoke Detectors to be located in all rooms, and within 7500cms of each door to a habitable room. Detectors should not be situated within 300cms of a wall or light fitting. All in accordance with Approved Document B.
Kitchens to receive a heat Detector Grade D, L602 system.
Interlinked mains wired smoke detectors throughout the escape routes to be provided.
Interlinked alarm sounded in each bed room.



PROPOSED GROUND FLOOR PLAN
1:100 @ A3



PROPOSED FIRST FLOOR PLAN
1:100 @ A3



DOMER CREEK WITHIN 10' OF A
FIRE RESISTING AND TO BE FORM
HINDING TILT, ON UNPAVED OR
ON SIMILAR TYPE BREATHABLE OR
CONCRETE/STONE SCREENED TO 2
MM TACK TAPE MOUNTED ON
RESISTING BOARD. THIS IS SUPPLY
STUDIES AT 400 C/S INFILTRATING
KINGDOMS BODILY/HEAVY AT THAT
END. (400-720-0000) (400-720-0000)

KEY

-  ELECTRICAL SOCKET
-  2 GANG WITH USB CHARGING POINT BUILT IN
-  TV
-  32" TV WITH 150mm HIGH SOCKETS BEHIND WITH AERIAL POINT INCLUDED WITH SINGLE SOCKET
-  RADIATOR
-  FD.30 30 MINUTE FIRE DOOR
-  30 MINUTE FIRE RESISTANT PARTITION WALL
-  SMOKE ALARM
-  HEAT DETECTOR
-  EMERGENCY LIGHTING
-  BREAK GLASS POINT
-  TR 100mm THICK WALL
-  WALLS TO BE DEMOLISHED

Mark Gordon
sign + Associates

Project

237 MILNROW ROAD,
ROCHDALE. OL16 5AS

Drawing Title
PROPOSED PLAN LAYOUTS

Drawn MG	Checked ..
Date MAY 2024	Scale 1 : 100
Drawing No. 237MR/204/BR	

APPENDIX H – Legislation, Policy and Guidance

Guidance for the assessment of noise affecting new residential development is given in the National Planning Policy Framework (NPPF). Section 15 of the NPPF states:

“174. Planning policies and decisions should contribute to and enhance the natural and local environment by:

e) preventing new and existing development from contributing to, being put at unacceptable risk from, or being adversely affected by, unacceptable levels of...noise pollution.”

Section 185 further states:

“Planning policies and decisions should also ensure that new development is appropriate for its location taking into account the likely effects (including cumulative effects) of pollution on health, living conditions and the natural environment, as well as the potential sensitivity of the site or the wider area to impacts that could arise from the development. In doing so they should:

A. Mitigate and reduce to a minimum potential adverse impact resulting from noise from new development – and avoid noise giving rise to significant adverse impacts on health and the quality of life;

B. Identify and protect tranquil areas which have remained relatively undisturbed by noise and are prized for their recreational and amenity value for this reason.”

Section 187 states:

“Planning policies and decisions should ensure that new development can be integrated effectively with existing businesses and community facilities (such as places of worship, pubs, music venues and sports clubs). Existing businesses and facilities should not have unreasonable restrictions placed on them as a result of development permitted after they were established. Where the operation of an existing business or community facility could have a significant adverse effect on new development (including changes of use) in its vicinity, the applicant (or ‘agent of change’) should be required to provide suitable mitigation before the development has been completed.”

To avoid and mitigate adverse noise effects on health arising from and impacting on new development, the NPPF makes reference to NPSE. The Noise Policy Statement for England (NPSE) was published in March 2010 and covers all forms of noise other than occupational noise.

The Noise Policy Statement for England (NPSE) states the following aims in paragraph 2.2.

NOEL – No Observed Effect Level.

This is the level below which no effect can be detected. In simple terms, below this level, there is no detectable effect on health and quality of life due to the noise.

LOAEL – Lowest Observed Adverse Effect Level.

This is the level above which adverse effects on health and quality of life can be detected.

SOAEL – Significant Observed Adverse Effect Level.

This is the level above which significant adverse effects on health and quality of life occur.

The NPSE does not define the SOAEL numerically, stating in paragraph 2.22:

"It is not possible to have a single objective noise-based measure that defines SOAEL that is applicable to all sources of noise in all situations. Consequently, the SOAEL is likely to be different for different noise sources, for different receptors and at different times. It is acknowledged that further research is required to increase our understanding of what may constitute a significant adverse impact on health and quality of life from noise. However, not having specific SOAEL values in the "NPSE provides the necessary policy flexibility until further evidence and suitable guidance is available."

There is no local or national guidance on how the three terms should be defined numerically, it is for the assessor to collate and interpret appropriate guidance on noise, such as may be found in British Standards, and correlate the guidance with the concepts of NOEL, LOAEL and SOAEL.

BS8233:2014 - *Guidance on sound insulation and noise reduction for buildings* suggests indoor ambient noise levels for dwellings in Table 4, Section 7.7.2. These are summarised below.

Activity	Location	07:00 to 23:00	23:00 to 07:00
Resting	Living Room	35 dB $L_{Aeq,16hour}$	-
Dining	Dining room/area	40 dB $L_{Aeq,16hour}$	-
Sleeping	Bedroom	35 dB $L_{Aeq,16hour}$	30 dB $L_{Aeq,8hour}$

BS8233 states that the guideline values given above are for 'noise without character', further stating:

"Noise has a specific character if it contains features such as a distinguishable, discrete and continuous tone, is irregular enough to attract attention, or has strong low-frequency content, in which case lower noise limits might be appropriate."

Table 4 of BS8233 also has accompanying notes that were subject to additions in ProPG. The relevant notes with the additions of ProPG are given below.

"NOTE 4 Regular individual noise events (for example, scheduled aircraft or passing trains) can cause sleep disturbance. A guideline value may be set in terms of SEL or $L_{Amax,F}$, depending on the character and number of events per night. Sporadic noise events could require separate values. In most circumstances in noise sensitive rooms at night (e.g. bedrooms) good acoustic design can be used so that individual noise events do not normally exceed 45dB $L_{Amax,F}$ more than 10 times a night. However, where it is not reasonably practicable to achieve this guideline then the judgement of acceptability will depend not only on the maximum noise levels but also on factors such as the source, number, distribution, predictability and regularity of noise events."

"NOTE 7 Where development is considered necessary or desirable, despite external noise levels above WHO guidelines, the internal L_{Aeq} target levels may be relaxed by up to 5 dB and reasonable internal conditions still achieved."

APPENDIX I – Acoustic Terminology

To aid the understanding of acoustic terminology and the relative difference between noise levels the following background information is provided.

We perceive sound when the ear detects fluctuations in air pressure (sound waves), which are then processed by the brain and perceived as sound. Humans can hear an incredibly wide range of sound intensities ranging from jet engines to fingertips lightly brushing against each other. This range is quantified using a logarithmic scale called the decibel scale (dB). The comfortable range of the decibel scale typically ranges from 0dB (the threshold of hearing) to around 140dB. Here are some examples of common environments and their typical noise levels.

Noise Level	Environment
0 dB(A)	Threshold of hearing
20 to 30 dB(A)	Quiet bedroom at night
30 to 40 dB(A)	Living room during the day
40 to 50 dB(A)	Typical office
50 to 60 dB(A)	Inside a moving car
60 to 70 dB(A)	Typical high street
100 to 110 dB(A)	Fire alarm at 1 meter away
140 dB(A)	Threshold of pain

Terminology

dB (decibel) – A unit used to quantify the pressure level of sound. Defined as 20 times the logarithm of the ratio between the root-mean-square pressure of a given sound field and a reference pressure level (2×10^{-5} Pa – threshold of hearing).

$L_{Aeq, T}$ – The equivalent continuous sound pressure level over a stated period. It quantifies a fluctuating sound level over a given period as the equivalent continuous sound level over which the same amount of acoustic energy is contained over. This is A-weighted in order to assess human perception.

L_{Amax} – the maximum RMS A-weighted sound pressure level occurring within a specified time period; the time weighting is typically either Fast or Slow.

A-Weighting – A standard weighting of the audible frequencies designed to reflect the response of the human ear to noise.

R_w – The Weighted Sound Reduction Index (R_w) is a number used to rate the effectiveness of a soundproofing system or material.

$D_{n,e,w}$ – The Weighted Sound Reduction Index specifically for ventilators.

C_{tr} – C_{tr} is a spectrum adaptation term which method is defined in BS EN ISO 717. The standard uses a reference curve to determine the weighted value of airborne sound insulation. The spectrum adaptation terms C and C_{tr} may be used to take into account different source spectra. ' C_{tr} ' is the A-weighted urban traffic noise spectrum.

APPENDIX J – Recommended Example Roof Specification



Rw	59 dB
C	-2 dB
Ctr	-6 dB

Mass-air-mass resonant frequency = 36 Hz

Panel Size = 2.7 m x 4.0 m

Partition surface mass = 52 kg/m²

System description

Panel 1 : 1 x 7 mm Roofing Slates

+ 1 x 17.5 mm Plywood

Frame: Solid Joist with resilient rail (1.5E2 mm x 45 mm), Stud spacing: 400 mm; Cavity Width 168 mm; 1 x Fibreglass (10kg/m³) 60mm Thickness 60 mm

Panel 2 : 2 x 12.5 mm Gyproc SoundBloc 12.5mm

...

freq.(Hz)	R(dB)	R(dB)
50	21	
63	28	25
80	34	
100	38	
125	42	41
160	45	
200	48	
250	51	50
315	53	
400	55	56
500	57	
630	58	
800	60	
1000	61	61
1250	61	
1600	59	
2000	64	60
2500	59	
3150	60	
4000	64	63
5000	68	

