

PLANNING PERMISSION REF 23/01162/FUL

LAND OFF GREENHILL ROAD / SMETHURST STREE MIDDLETON M24 2BB

PLANING CONDITION 13 SOLAR PHOTO-VOLTAIC PANELS

We are proposing to install Solar Photo-Voltaic Panels to meet SAP derived kWp targets indicated Anderson Goddards Report with Veridian panels. The installation will be "in roof," comprising Veridian Clearline Fusion Panels and incorporate an appropriate inverter installed to designated area. The panels will be installed in accordance with the Veridian specification with flashings to all sides.

The products and services comply with current and relevant regulations, manufacturer's installation recommendations and requirements.

- . Solar panels carry a minimum of 5 years' manufacturer's defect warranty.
- . Solar panels have a 25-year minimum performance output warranty.
- . Inverters are covered by a 5-year manufacturer's warranty.
- . Our installation carries a full 2-year labour & parts warranty.