



**Land at St Mary's Gate Retail Park,
Whitworth Road,
Rochdale,
OL12 0TY**

Proposed Commercial Development

Phase 1 Site Investigation Report

For: Glenbrook Investments

Integra Consulting
Suite 4
14-32 Hewitt Street
Manchester
M15 4GB

Ref: 3361-SI
Job: 3361
Rev: -
By: NS
Date: Jan 23

Environmental

Geotechnical

Highways

Structural

Civil

TABLE OF CONTENTS

1.0	INTRODUCTION.....	1
2.0	PURPOSE & AIMS OF THE STUDY	1
3.0	SITE DATA	1
3.1	Site Location	1
3.2	Site Description & Walkover Observations	1
4.0	SITE HISTORY	2
5.0	ENVIRONMENTAL SETTING.....	3
5.1	Documented Geology	3
5.2	Historical Coal Mining	4
5.3	Hydrology and Hydrogeology.....	4
6.0	FURTHER ENVIRONMENTAL DATA.....	5
7.0	PREVIOUS SITE INVESTIGATIONS / REPORTS	7
8.0	PRELIMINARY QUALITATIVE RISK ASSESSMENT (TIER 1).....	7
8.1	Introduction	7
8.2	Preliminary Conceptual Model	8
8.3	Summary of Risks.....	8
9.0	AIMS AND PROPOSED SCOPE OF PHASE II INTRUSIVE INVESTIGATION	9

APPENDIX A: DRAWINGS

APPENDIX B: NOTES ON LIMITATIONS

APPENDIX C: CURRENT CONTAMINATED LAND GUIDANCE / LEGISLATION & RISK ASSESSMENT METHODOLOGIES

APPENDIX D: COMMERCIAL ENVIRONMENTAL DATA

APPENDIX E: SITE PHOTOGRAPHS

1.0 INTRODUCTION

Integra Consulting is providing consultancy services to **GLENBROOK INVESTMENTS** (the *Client*) in connection with the proposed re-development of a parcel of land fronting on to Queen Street and Whitehall Street, St Mary's Gate, Rochdale, OL12 0TY.

It is understood that the site is to be re-developed for commercial / retail use by the construction of a 'Drive-Thru' facility, with associated hard paved car parking and areas of soft landscaping / cultivation.

The existing and proposed site layouts are illustrated on **RADCLIFFE GROVE PARTNERSHIP** architectural drawings contained herein.

The proposed development falls within the administrative jurisdiction of **ROCHDALE BOROUGH COUNCIL**.

This Phase I Desk Study was required as a preliminary to planning an intrusive phase of investigation. The report was devised to generally comply with the relevant principles and requirements of a as a wide range of guidance including BS5930:1999 as amended 2007: "*Code of Practice for Site Investigations*", BS10175: 2011 "*Investigation of Potentially Contaminated Sites - Code of Practice*", and the DEFRA/Environment Agency Report CLR11 "*Model Procedures for the Management of Land Contamination*".

This report should be read in conjunction with the Notes on Limitations, given in Appendix B.

2.0 PURPOSE & AIMS OF THE STUDY

The primary aim of the Phase I Desk Study was to assess whether the site is likely to be affected by contamination to an extent that it may pose a risk to human health and/or the built environment and/or the wider natural environment or is affected by any other natural or man-made features which may impact on the proposed redevelopment.

Specific tasks undertaken to achieve these objectives were as follows:

- Undertaking of a review of available historical mapping, environmental databases, and Environment Agency data
- Undertaking of a site walkover inspection
- Development of Preliminary Conceptual Model
- Development of a Phase 2 intrusive investigation strategy

3.0 SITE DATA

3.1 Site Location

The site comprises a rectangular shaped parcel of land located immediately to the south of Queen Street, and east of Whitehall Street, St Mary's Gate, Rochdale, OL12 0TY as illustrated in Appendix A.

The **ORDNANCE SURVEY** coordinates for the approximate site centre are 389786 413897. It stands at an approximate elevation of c. 140m AOD.

3.2 Site Description & Walkover Observations

The site was visited during January 2023 on completion of a review of all relevant historical and environmental mapping data (provided in Appendix D).

The site is located within a mixed commercial context. It comprises a rectangular shaped parcel of land (currently utilised as for car parking), which extends to the approximate dimensions of c. 64m x 40m; its long axis being on a northeast – southwest alignment.

It is bound to the north and west by public pavements extending along Queen Street and Whitehall Street respectively. Its eastern boundary is delineated by pavements extending along Duke Street whilst its southern boundary is adjoined by a public car park associated with nearby retail units.

The surface topography across the site was seen to be generally flat with surface cover comprising well-maintained bituminous paving, and with areas of soft landscaping / cultivation extending along its western, northern, and eastern boundaries.

2 No street / security lighting towers are set within the hard paved cover.

Given that the site has previously been developed, there is a potential for the presence of buried services to exist beneath the site.

There was no visual evidence of the presence of native and/or non-native plant species within, or adjoining, the site boundary.

Vehicle and pedestrian access can be made via Duke Street to the east.

The information obtained from the visit is summarised in Table 1 hereunder.

Table 1: Summary of Walkover Observations

FEATURE		OBSERVATION
Current Use of Land		Car parking facility
Context		Commercial context
Topography / Surfaces		The surface topography across the site was seen to be sensibly flat with surface cover comprising well-maintained bituminous paving with areas of soft landscaping / cultivation extending along its western, northern, and eastern boundaries. 2nr tall street / security lights are set within the hard paved cover.
Dimensions		c. 64m x 40m; its long axis being on a northeast – southwest alignment
Access		Vehicle and pedestrian access can be made via Duke Street to the east.
Buildings Adjacent to the Site		Commercial
Services		Given that the site has previously been developed, the presence of 2nr tall streetlights within the site, and taking into account the adjoining commercial properties, there is a potential for the presence of buried services to exist beneath the site.
Boundary	NW	Public pavements extending along Queen Street
	West	Public pavements extending along Whitehall Street
	South	Car parking associated with nearby retail units
	East	Public pavements extending along Duke Street
Material storage		None observed
Waste disposal		None observed
Other potential contamination		Hydrocarbons associated with on site car parking
Ecology*		None observed

**These comments on the ecology are for initial preliminary assessment only and are based on observations undertaken by a person who is a trained ecologist but who has not undertaken a comprehensive Phase I Habitat Survey or similar.*

4.0 SITE HISTORY

The history of the site and its immediate surrounds was investigated by consultation with a range of archive resources. Geographical information, historical mapping and environmental data were primarily based on a GroundSure Environmental Report (Reference No. CMAPS-AAG-1078975-4165-030123, dated January 2023), presented in Appendix D.

A summary of the historical mapping data is given hereunder:

Table 2: Historical Map Review

YEAR	SCALE	ON SITE	ADJACENT TO SITE	<250M
1851 1851 1890 1890-1891 1891 1892	1:1,056 1:10,560 1:10,560 1:10,560 1:2,500 1:500	Site developed for commercial / light industrial land uses. Boiler Works located within NE section of the site. Duke Street crossing the site on a NE-SW alignment	Adjacent land fully developed for mixed commercial / light industrial land uses. Phoenix Foundry to the S.	Surrounding area fully developed for mixed commercial / light industrial land uses. Wardleworth Workhouse c.30m SW. Public house c. 30m E Public house c.20m NW Coal & timber yard c. 80m S. Boiler Works c.100m N. Cotton Mill c. 30m N. Town Head Mills c. 50m SE. 2nr Reservoirs c. 50m E. Victoria Foundry c. 200m NE Corporation Highway Depot & associated grounds c. 180m NE Silk Mill C. 130m W. Tannery c. 80m SE
1908-1909 1910	1:10,560 1:2,500	No significant change	Land to the S renamed Phoenix Machine Works	Atlas Iron Works – Textile Works c. 130m N Timber yard c. 150m N Burial grounds c. 120m SW
1928	1:10,560	No significant change	No significant change	No significant change
1930 1938	1:2,500 1:10,560	Site renamed warehouse	No significant change	No significant change
1949-1954	1:10,560	No significant change	No significant change	No significant change
1956 1957-1959 1958-1959	1:10,560 1:1,250 1:1,250	Site redeveloped as a warehouse with Castle Street extending along its S boundary	Land to the S redeveloped for continued commercial land use, renamed Works	Significant redevelopments undertaken within the surrounding area with associated infrastructure Former corporation depot fully redeveloped for mixed

				commercial residential land uses. Reservoirs no longer shown Factory c.130m N Expensive parcel of amenity land c. 150m NW
1967-1968	1:10,560	No significant change	No significant change	No significant change
1973-1974 1975-1979 1976-1977 1975-1978	1:1,250 1:10,000 1:1,250 1:1,250	Site shown to be clear of former structures	Land to the S redeveloped / extended as an engineering works	Significant redevelopments undertaken within the surrounding area with associated infrastructure
1983-1987 1985-1989 1987-1989 1988-1992 1989-1993	1:1,250 1:1,250 1:10,000 1:1,250 1:1,250	No significant change	No significant change	Former Cotton Mill to the E no longer shown Engineering works to the S no longer shown Site of former cotton mill redeveloped for commercial land uses
1992-1993 1992 1995 1995	1:1,250 1:10,000 1:1,250 1:1,250	No significant change	No significant change	No significant change
2001 2003 2010 2023	1:10,000 1:1,250 1:10,000 1:10,000	Site utilised as a car parking facility	Land to the SE utilised as a car parking facility associated with the adjoining retail units	Significant redevelopment works undertaken within the surrounding area

5.0 ENVIRONMENTAL SETTING

5.1 Documented Geology

The geology of the site was researched by reference to the 1:50000 scale **BRITISH GEOLOGICAL SURVEY** (BGS) Sheet 076 Rochdale (2008) 1: 50,000 Scale Solid and Drift Editions and Crofts. R.D. *et.al* (2010) 'Geology of the Rochdale district — a brief explanation of the geological map. Sheet explanation of the British Geological Survey. 1:50 000 sheet 76 Rochdale (England and Wales)'. Keyworth, Nottingham. British Geological Survey.

The **BGS** 1:10, 000 Scale Drift Geological map indicate that the overall site is underlain with natural drift deposits comprising impermeable diamicton (*boulder clay*) comprising gravel sand silt and clay deposits of glacial origin (*Pleistocene Epoch - Late Quaternary - Devensian Sub Age*).

The solid geology is documented to comprise the Old Lawrence Rock overlying dark grey, fissile, argillaceous mudstone and siltstone. Both geological units associated with the Pennine Lower Coal Measure Formation (*Westphalian A: Langsettian Substage*).

There are no documented geological lines of weakness within 500m of the study site.

The 'Indicative Atlas of Radon in England and Wales' (Miles. J.C.H *et.al*, 2007) Map 13 'Northern Welsh Marches and Liverpool', shows the site to be situated within an area where it is believed that less than 1% of the properties within the area are affected by Radon and therefore Radon Protection Measures will not be required for new structures in contact with the ground.

Geological Information obtained from the GroundSure Environmental Report is presented in Appendix D, and summarised hereunder:

Table 3: Summary of Geological Data from GroundSure Report

GEOLOGY		
Data	Distance	Comments
Artificial Ground	N/A	If present, artificial ground and/or reworked ground deposits associated with the development of the site & its immediate surroundings
Superficial Deposits / Drift Geology	On Site	Diamicton of glacial origin
Permeability of Diamicton	Maximum Permeability	Diamicton = High
	Minimum Permeability	Diamicton = Low
Bedrock and Solid Geology	On Site	Old Lawrence Rock – Sandstone of the Pennine Lower Coal Measure Formation
Permeability of Bedrock: On Site	Minimum Permeability	Moderate
	Maximum Permeability	High
Geological Lines of Weakness	On Site	No records
	<250m	No records
Radon Affected Area	On Site	The site is not in a Radon Affected Area, as less than 1% of properties are above the Action Level
Radon Protection	On Site	No radon protective measures are necessary
MINING, GROUNDWORKINGS AND NATURAL CAVITIES		
Data	Distance	Comments

Natural cavities	<500m	No records
BritPits	<500m	171m N. Green Hayes Clay Pit – Ceased 474m E. Rock House Sand Pit - Ceased
Surface ground workings	<250m	32m E. Pond – 1851 60m E. Reservoir – 1949 65m E. Reservoir – 1968 66m E. Reservoir – 1908 - 1928 141m N. Pond – 1851 155m N. Clay Pit - 1851
Underground workings	<1000m	638m N. Unspecified Old Shaft – 1928 649m N. Unspecified Disused Shaft – 1968 662m N. Unspecified Old Shaft - 1890
Historical Mineral Planning Areas	<500m	No records
Non-coal mining	<1000m	No records
Mining cavities	<1000m	No records
Coal mining	On Site	The site is located within a coal mining area as defined by the Coal Authority. A Consultants Coal Mining Report is recommended to further assess coal mining issues at the site.
Brine areas	On Site	No records
Gypsum areas	On Site	No records
Tin mining	On Site	No records
Clay mining	On Site	No records
HAZARDS		
Data	Distance	Comments
Maximum shrink swell clays	On site	Very Low
Maximum running sands	On site	Very Low
Maximum compressible deposits	On site	Negligible
Maximum collapsible deposits	On site	Very Low
Maximum landslides	On site	Very Low
Maximum ground dissolution of soluble rocks	On site	Negligible

5.2 Historical Coal Mining

The appended environmental data, **BGS** mapping data and **COAL AUTHORITY** Gazetteer confirm that the site is located within an area which is believed to be underlain by productive coal measures which may have been worked in the past and therefore the Client is advised to commission a Coal Mining Risk Assessment.

5.3 Hydrology and Hydrogeology

Information on hydrology and hydrogeology obtained from a GroundSure Environmental Report is presented in Appendix D, and summarised hereunder:

Table 5: Summary of Hydrology and Hydrogeological Data from GroundSure Environmental Report

HYDROGEOLOGY AND HYDROLOGY		
Aquifer within Superficial Drift Deposits (Boulder Clay)	On site	Diamicton: Secondary Undifferentiated: Assigned where it is not possible to attribute either category A or B to a soil type. In general, these layers have previously been designated as both minor and non-aquifer in different locations due to the variable characteristics of the soil type
Aquifer within Bedrock Deposits	On site	Old Lawrence Sandstone- Secondary A: Permeable layers capable of supporting water supplies at a local rather than strategic scale, and in some cases forming an important source of base flow to rivers. These are generally aquifers formerly classified as minor aquifers
Groundwater Abstraction Licenses	<500m	No records
Surface Water Abstraction Licenses	<500m	No records
Potable Water Abstraction Licences	<500m	No records
Source Protection Zones	<500m	No records
Source Protection Zones (confined aquifer)	<500m	No records
Water Network (OS Mastermap)	<200m	No records
Surface water features	<250m	No records
WFD Surface water body catchments	On Site	On Site: River. Roch (Source to Spodden) GB112069064720 Roch Irk Medlock Irwell
WFD Surface water bodies	<250m	No records
WFD Groundwater bodies	<250m	On Site: Northern Manchester Carboniferous Aquifers
FLOODING		
Risk of Flooding from Rivers and Sea (RoFRaS)	<50m	No records
Historical Flood Events	<250m	No records
Flood Defences	<250m	No records
Areas Benefitting from Flood Defences	<100m	No records
Flood Storage Areas	<250m	No records
Flood Zone II	<50m	No records

Flood Zone III	<50m	No records
Surface water flooding: Highest risk	On Site	Negligible
	<50m	1 in 30 years, 0.3m – 1.0m
Groundwater flooding: Highest risk	On Site	Low
	<50m	Low

For simplified interpretation, the geological succession underlying the site may be regarded as a series of discrete units in terms of their hydrogeological significance, as illustrated hereunder:

Table 6: Hydrogeological Interpretation

UNIT	PROPERTIES	HYDROGEOLOGICAL DESIGNATION
Made / Reworked Ground	If present, likely to be generally granular and permeable and will permit vertical and lateral transmission of groundwater.	Unproductive Aquifer
Diamicton	Assigned where it is not possible to attribute either category A or B to a soil type. In general, these layers have previously been designated as both minor and non-aquifer in different locations due to the variable characteristics of the soil type	Secondary Undifferentiated
Old Lawrence Sandstone	Permeable layers capable of supporting water supplies at a local rather than strategic scale, and in some cases forming an important source of base flow to rivers. These are generally aquifers formerly classified as minor aquifers	Secondary A Aquifer

5.4 Potential for Soakaway Drainage

The documented geology strongly indicates that soakaway drainage will not function effectively on this site.

6.0 FURTHER ENVIRONMENTAL DATA

Environmental data was researched using several sources including Environment Agency Maps and GroundSure Envirosight Report presented in Appendix D and is summarised hereunder in Table 6. This environmental data has been used to carry out a Preliminary Qualitative Risk Assessment (Tier 1) and formulate the preliminary conceptual model as discussed in Section 8.0 of this report.

Table 7: Summary of Environmental Data

POTENTIALLY CONTAMINATIVE USES IDENTIFIED FROM 1:10,000 SCALE MAPPING		
Data	Distance	Comments
Historical industrial land uses	<250m	There are 94 records pertaining to historical industrial land uses within the surrounding area, those shown to be within 100m of the study site are listed hereunder: On site> Unspecified Works 23m E. Unspecified Mills 24m E. Unspecified Commercial/Industrial 24m E. Unspecified Mills 25m E. Unspecified Mills 26m E. Unspecified Commercial/Industrial 27m E. Cotton Mills 28m E. Unspecified Mills 31m S. Unspecified works 50m E. Unspecified Commercial/Industrial 75m E. Chimney
Historical tanks	<250m	149m SW. Unspecified Tank 248m SW. Unspecified Tank 249m SW. Unspecified Tank
Historical energy features	<250m	32m NW. Electricity Substation 47m S. Electricity Substation 57m NW. Electricity Substation 174m NW. Electricity Substation
Historical petrol stations	<250m	No records
Historical garages	<250m	There are 94 records pertaining to historical garages within the surrounding area, those shown to be within 100m of the study site are listed hereunder: 56m NE. Garage 83m N. Garage 87m N. Garage
Historical military land	<250m	No records
Records of Current Industrial Land Use		
Data	Distance	Comments
Recent industrial land uses	<250m	16m NE. Frank Key 31m N. Boltons Textiles 35m N. Tri-Cast Composite Tubes Ltd 40m NW. Electricity Substation 48m S. Electricity Substation

		64m NW. Electricity Substation 78m NW. H Rothwell & Co 99m NW. Works 102m NW. Ringtag International 103m N. Discount Clearance centre 105m NW. Duke St' Auto Point 105m NW. Wren Prestige 123m N. Spring Court Auto Centre 125m NE. Electricity Substation 126m N. MOT Test Centre 134m NE. NRG Telecoms Ltd 142m E. Electricity Substation 157m N. Kwik Fit 170m S. TJ Booth 180m NE. Works 184m N. Sawmills 191m NE. Works 192m NW. Rochdale Ambulance Station 200m NE. Rochdale Re Tool Ltd 201m E. Works 206m NE Burns Motor Works 210m NE. Isaac Butterworth Ltd 216m SE. Rochdale Mobility 216m S. Mobile Planit 227m NE. Motaquip 227m NE. Motaquip Autocentre 234m N. Answer & Co 242m NE. Works 248m SW. EVM Sports & Prestige
Current or recent petrol stations	<250m	210m N. Gulf - Open
Electricity cables	<250m	No records
Gas pipelines	<250m	No records
Sites determined as Contaminated Land	<250m	No records
Control of Major Accident Hazards (COMAH)	<250m	No records
Regulated explosive sites	<250m	No records
Hazardous substance storage/usage	<250m	No records
Historical licensed industrial activities (IPC)	<250m	No records
Licensed industrial activities (Part A(1))	<250m	No records
Licensed pollutant release (Part A(2)/B)	<250m	28m N. Anwar and Co Ltd, - Status: Current Permit / Permit Type: Part B 206m N. Manson Timber, Whitworth Road, Status: Historical Permit / Permit Type: Part B
Radioactive Substance Authorisations	<250m	No records
Licensed Discharges to controlled waters	<250m	139m S. Permit Number: 01ROC0055 / Permit Version: 1 139m S. Permit Number: 01ROC0055 / Permit Version: 2 186m S. Permit Number: EPRQB3591EA / Permit Version: 1
Pollutant release to surface waters (Red list)	<250m	No records
Pollutant release to public sewer	<250m	No records
List 1 Dangerous Substances	<250m	No records
List 2 Dangerous Substances	<250m	No records
Pollution Incidents (EA/NRW)	<250m	No records
Pollution inventory substances	<250m	No records
Pollution inventory waste transfers	<250m	No records
Pollution inventory radioactive waste	<250m	No records
WASTE AND LANDFILL		
Data	Distance	Comments
Active or recent landfill	<250m	No records
Historical landfill (BGS records)	<250m	No records
Historical landfill (LA/mapping records)	<250m	No records
Historical landfill (EA/NRW records)	<250m	No records
Historical waste sites	<250m	No records
Licensed waste sites	<250m	No records
Waste exemptions	<250m	98m N. Whitworth Rd; WEX227128 210m NE. Balfour Beatty Living Places Ltd, WEX159308 210m NE. Balfour Beatty Living Places Ltd, WEX159308 222m NE. BBLP Princess Street Depot. EPR/XF0006V N/A001 243m S. 79 Yorkshire St', WEX156666 248m S. 79 Yorkshire St', EPR/PF0300H H/A001 249m S. Rochdale Pharmacy, WEX074442
ENVIRONMENTAL DESIGNATIONS		
Data	Distance	Comments
Sites of Special Scientific Interest (SSSI)	<500m	None
Conserved wetland sites (Ramsar sites)	<500m	None

Special Areas of Conservation (SAC)	<500m	None
Special Protection Areas (SPA)	<500m	None
National Nature Reserves (NNR)	<500m	None
Local Nature Reserves (LNR)	<500m	None
Designated Ancient Woodland	<500m	None
Biosphere Reserves	<500m	None
Forest Parks	<500m	None
Marine Conservation Zones	<500m	None
Green Belt	<500m	None
Proposed Ramsar sites	<500m	None
Possible Special Areas of Conservation (PSAC)	<500m	None
Potential Special Protection Areas (pSPA)	<500m	None
Nitrate Sensitive Areas	<500m	None
Nitrate Vulnerable Zones	<500m	None

7.0 PREVIOUS SITE INVESTIGATIONS / REPORTS

Searches and consultations have not established any evidence that ground investigation works have previously been undertaken on this site.

8.0 PRELIMINARY QUALITATIVE RISK ASSESSMENT (TIER 1)

8.1 Introduction

Based on the foregoing study, there is a 'Low - Moderate' potential for the presence of contamination associated with the historic land uses on the site and/or immediately adjoining the study site of the site, and previous land uses and hence a preliminary risk assessment was undertaken.

The risk assessment methodologies adopted by **Integra Consulting** are based on current available guidance from several sources and are included in Appendix D.

The Tier 1 Risk Assessment and Preliminary Conceptual Model (PCM) were formulated using the information discussed above and based on the following assumptions:

- It is understood that the site is to be redeveloped for commercial use by the construction of a 'Drive-Thru' facility with associated hard paved car parking and areas of soft landscaping / cultivation.

The existing and proposed layout are as illustrated on **RADCLIFFE GROVE PARTNERSHIP** architectural drawings contained herein.

- Drinking water will be from a mains supply.

In constructing the Preliminary Conceptual Model (PCM), **Integra Consulting** applied the guidance contained in CIRIA C552: 2001. This recommends use of a Risk Matrix which classifies risk based on the product of Probability of a source being present, and the Consequence of receptors being exposed to the source. Guidance tables setting out the classifications of probability and consequence together with a risk matrix are given in Tables 8 - 9 hereunder. In using this approach **Integra Consulting** recommends actual intrusive investigation of any Risk Classification of "Moderate" or over.

Table 8: Matrix of consequences against probability to gain a risk classification [CIRIA C552, 2001]

		CONSEQUENCE			
		SEVERE	MEDIUM	MILD	MINOR
Probability	High Likelihood	Very High Risk	High Risk	Moderate Risk	Moderate / Low Risk
	Likely	High Risk	Moderate Risk	Moderate / Low Risk	Low Risk
	Low Likelihood	Moderate Risk	Moderate / Low Risk	Low Risk	Very Low Risk
	Unlikely	Moderate / Low Risk	Low Risk	Very Low Risk	Very Low Risk

Table 9: Classification Definitions (C552 CIRIA, 2001)

CLASSIFICATION	DEFINITION
Very High	There is a high probability that severe harm could arise to a designated receptor from an identified hazard. Or there is evidence that severe harm to a designated receptor is currently happening. This risk, if realised, is likely to result in a substantial liability. Urgent investigation (if not undertaken already) and remediation are likely to be required.

High	Harm is likely to arise to a designated receptor from an identified hazard. Realisation of the risk is likely to present a substantial liability. Urgent investigation (if not undertaken already) is required and remedial works may be necessary in the short term and are likely over the longer term.
Moderate	It is possible that harm could arise to a designated receptor from an identified hazard. However, it is either relatively unlikely that such harm would be server, or if any harm were to occur it is more likely that harm would be relatively mild. Investigation (if not undertaken already) is normally required to clarify the risk and to determine to potential liability. Some remedial works may be required in the longer term.
Moderate / Low	
Low	It is possible that harm could arise to a designated receptor from an identified hazard, but it is likely that this harm, if realised, would at worst normally be mild
Very Low	There is a low possibility that harm could arise to a receptor. In the event of such harm being realised it is not likely to be server.

8.2 Preliminary Conceptual Model

By application of the risk assessment methodology outlined above, the following PCM was constructed.

Table 10: Preliminary Conceptual Model (PCM)

POLLUTANT LINKAGE	SOURCE	PATHWAY	RECEPTOR	PROBABILITY	CONSEQUENCE	RISK RATING
1	Boiler Works and other light industrial uses giving rise to risk of broad spectrum of heavy metals, aggressive pH, hydrocarbons, PAH's, asbestos in Made Ground associated with development of the site and the demolition of former structures et	Soil and / or soil dust ingestion	Construction workers Future worker Offsite receptors	Likely	Medium	Moderate
2	Asbestos containing materials (ACM) in made ground soils associated with Boiler Works and construction / demolition of former structures etc	Fibre Inhalation	Construction workers Future worker Offsite receptors	Likely	Severe (ACM)	High
3	Inhalation of vapours associated with potential on-site made ground deposits, associated with development of the site and the demolition of former structures etc	Inhalation	Future residents	Unlikely	Medium	Low
4	Inhalation of ground gases from onsite or offsite sources i.e., made ground deposits associated with infilling of former reservoirs, demolition and infilling of basements of former structures etc	Inhalation	Future residents	Unlikely	Medium	Moderate
5	pH & Sulphate attack on concrete	Future building	Future building	Likely	Mild	Moderate / Low
6	Organic contamination associated with on site car parking facilities	Direct contact with water mains	Potable water supply	Unlikely	Medium	Low

The contaminants of concern associated with those risks which require intrusive investigation were researched by reference to published industry profiles, and are summarised hereunder:

Table 11: Summary of Contaminants of Concern based on PCM

LINKAGE NO.	METALS	NON-METALS	ORGANICS	GASES	OTHERS
PL1, PL2 PL5, PL6	Cd, Cr (total & hexavalent), Ni, Cu, Zn, Pb, Hg, Se, Mo, Sb	As, sulphates, sulphides, boron, free cyanide	TPHCWG, PAH's, BTEX, Volatiles (by PID), VOC's & SVOC's, SOM	-	pH Asbestos
PL3 & PL4	-	-	-	CH ₄ , CO ₂ , CO, H ₂ S	-
PL1, PL6	-	-	TPHCWG, PAH's, BTEX, Volatiles (by PID)	-	-
PL1-PL6	Cd, Cr (total), Ni, Cu, Zn, Pb, Hg, Se, Mo, Sb	As, sulphates, sulphides, boron, free cyanide	TPHCWG, BTEX PAH's, Volatiles (by PID), SOM	CH ₄ , CO ₂ , CO, H ₂ S	pH Asbestos

8.3 Summary of Risks

The foregoing analysis has identified a significant number of potential risks, and if present, these could adversely impact on human or environmental receptors, and since no previous site investigation has been undertaken, an intrusive phase of investigation is recommended to determine whether the postulated pollutant linkages are present on site.

9.0 AIMS AND PROPOSED SCOPE OF PHASE II INTRUSIVE INVESTIGATION

Based on the findings above, it is recommended that an intrusive investigation be undertaken. The Phase II Intrusive Investigation should include for exploratory holes to be sunk through made ground into the underlying natural strata.

The primary objectives of a ground investigations are to obtain enough data to reliably ascertain ground conditions on site, and to aid confirmation of the potential pollution linkages identified within the Preliminary Conceptual Model above. Sufficient soil and groundwater/soil leachate contamination data should be obtained to reliably allow the Preliminary Conceptual Model to be tested and refined by the performance of a quantitative risk assessment.

Using the guidance contained in BS10175: 2011 and R&D Technical Report P5-0066/TR: 2000, it is proposed that 5 No boreholes be sunk using light dynamic sampling methods to a notional depth of c.5m below ground level, or to refusal in rock head, whichever is the lesser.

Given the potential for the presence of underlying made ground deposits of an unknown thickness - composition, and given the nature of the development, it is recommended that 3 No light dynamic sampling boreholes be utilised for the installation of standpipes, thus enabling a programme of ground gas monitoring to be undertaken. To comply with CIRIA C665 for a “*Moderate*” risk site, it is proposed that gas monitoring is undertaken as a minimum on 4 No occasions, distributed over a period of 1 month.

The prime objective of any intrusive ground investigation is to provide reliable soil / groundwater, or soil leachate, contamination data and to assess the potential risk to human health and sensitive environmental receptors.

The proposed scope of works is summarised in Table 12 hereunder:

Table 12: Proposed Scope of Works

RISK	METHOD OF ASSESSMENT
Is the superficial ground impacted by contamination to the extent it may present a risk to human health?	Using the guidance contained in BS10175: 2011 and R&D Technical Report P5-0066/TR: 2000 it is proposed that 5 No boreholes be sunk using light dynamic sampling methods to a notional depth of c.5m bgl, or to refusal in rock head, whichever is the lesser. Broad spectrum contamination analyses will be performed on selective subsamples of recovered made ground (5 No analyses) to suite in Table 11
What are the geotechnical properties of the ground?	Standard Penetration Test's (SPT's) to be carried out at regular depth increments throughout the boreholes, with HSV tests to be carried out in cohesive strata on recovered soils. A programme of soil engineering laboratory testing will be carried out. The <i>in-situ</i> tests and soil engineering test data will be used in formulating suitable foundation solutions.
Is the site affected by migrating gas from made ground deposits?	The evidence of the desk study is that there is a low – moderate risk of the site being contaminated by ground gases and therefore 3nr boreholes will be utilised for the installation of gas / groundwater monitoring standpipes. CIRIA C665 recommends monitoring on 4 No occasions distributed over a period of 1-month.
Does the site pose a risk to the underlying aquifer	Soil water samples will be recovered from the standpipes and will be analysed to the suite proposed in Table 11. In the event that water does not accumulate in the standpipes, soil leachate analyses will be undertaken to the suite in Table 7. The results will be assessed against Drinking Water Standards and Environmental Quality Standards.

The layout of the proposed intrusive investigation is as annotated in Appendix A of this report.

Given that the site is to be re-developed for commercial use with associated soft landscaping, contamination data obtained as part of the above recommended Phase II intrusive investigation will be based on criteria contained in publication LQM/CIEH S4UL's for Human Health Risk Assessment (2015), applicable to the “*Commercial*” land use scenario. Given this document does not provide criteria for Lead contaminants, it is proposed that Lead results are compared to the C4SL published by DEFRA SP1010 Development of Category 4 Screening Levels for ‘*Commercial Land*’ use.


APPENDIX A: DRAWINGS:

SITE LOCATION PLAN

AERIAL PLATE

ARCHITECTURAL DRAWINGS

OS MasterMap site plan



Site Area: 0.23ha



Recent aerial photograph





Capture Date: 23/05/2019

Site Area: 0.23ha



SITE SPECIFIC HAZARDS

IN ACCORDANCE WITH THE REQUIREMENTS OF THE CDM REGULATIONS 2015 THE FOLLOWING SIGNIFICANT RESIDUAL HAZARDS HAVE NOT BEEN DESIGNED OUT OF THIS PROJECT AND MUST BE TAKEN INTO CONSIDERATION BY CONTRACTORS PLANNING TO UNDERTAKE THE WORKS SHOWN ON THIS DRAWING:



NOTES

SITE PLAN BASED ON TOPOGRAPHIC SURVEY BY SURVEY OPERATIONS. REFER TO DRAWING A0 21G200/001 FOR FULL DETAILS

[illegible]

REV.	DATE	NOTES	INIT.
------	------	-------	-------



CLIENT / PRO

GLENBROOK
ST. MARYS GATE
ROCHDALE

DRAWING TITLE
ENLARGED SITE PLAN
SCHEME FIVE

FOR INFORMATION

DATE	DRAWN	SCALE @ A3
21.09.22	AJP	1:250

PROJECT NUMBER	UNIT / BLOCK	CI / SFB CODE	TYPE & NUMBER	REVISION LETTER
-------------------	-----------------	------------------	------------------	--------------------

DRAWING NO.	
11390	SC05 L02


Site Location Plans	L	GA Plans	P	Elevations	E
Sections	S	Details	D	Prefix: Colour	C

THE RATCLIFFE GROVES PARTNERSHIP

MANCHESTER
105 MANCHESTER ROAD
BURY LANCASHIRE BL9 0TD
T. 0161 797 6000 E. manchester@rgp.uk.com
www.rgp.uk.com

LONDON
19 BEDFORD ROW
LONDON WC1R 4EB
T. 020 7600 6666 E. london@rgp.architects





APPENDIX B: NOTES ON LIMITATIONS

General

Integra Consulting has prepared this report solely for the use of the Client and those parties with whom a warranty agreement has been executed, or with whom an assignment has been agreed. Should any third party wish to use or rely upon the contents of the report, written approval must be sought from **Integra Consulting**, and a charge may be levied against such approval.

Integra Consulting accepts no responsibility or liability for:

- The consequences of this document being used for any purpose or project other than for which it was commissioned and/or
- The consequences of use of this document by any party with whom an agreement has not been executed.

Phase I Environmental Audits / Desk Studies

The work undertaken to provide the basis of a Phase 1 Desk Study report comprises a study of available documented information from a variety of sources (including the client), together with (where appropriate) a walk over inspection of the site and meetings and discussions with relevant authorities and other interested parties. The opinions given in a Desk Study report have been dictated by finite data on which they are based and are relevant only to the purpose for which the report was commissioned. The information reviewed should not be considered exhaustive and has been accepted in good faith as providing true and representative data pertaining to site conditions. Should additional information become available which may affect the opinions expressed in the report, **Integra Consulting** reserves the right to review such information and to modify the opinions accordingly.

It should be noted that any risks identified in this report are perceived risks based on the information reviewed; actual risks can only be assessed following a physical investigation of the site.

Phase II Environmental Audits

The investigation of the site has been carried out with the intention of providing enough information concerning the type and degree of contamination, and ground and groundwater conditions to allow a reasonable risk assessment to be made. The objectives of the investigation have been limited to establishing the risks associated to potential human targets, building materials, the environment (including adjacent land), and surface and groundwater.

The amount of exploratory work and chemical testing undertaken may have been restricted by the timescale available, and the locations of the exploratory holes may have been restricted to areas unoccupied by the building(s) on the site, and further restricted by the existence of buried services. A more comprehensive investigation may be required if the site is to be redeveloped as, in addition to risk assessment, several important engineering and environmental issues may need to be resolved.

For those reasons, if costs have been included in relation to site remediation these must be considered as tentative only and must, in any event, be confirmed by a qualified quantity surveyor.

The exploratory holes undertaken, investigate only a small volume of the ground in relation to the size of the site, and can only provide a general indication of site conditions. The number of sampling points and the methods of sampling and testing do not preclude the existence of localised “hotspots” of contamination where concentrations may be significantly higher than those encountered.

Geoenvironmental Ground Investigations

The investigation of the site has been carried out to provide sufficient information within the agreed scope of the investigation, under the general headings of type and degree of contamination, geotechnical characteristics, and ground and groundwater conditions, to provide a reasonable assessment of the environmental risks together with engineering and development implications.

If costs have been included in relation to the site remediation, these must be confirmed by a qualified quantity surveyor.

The exploratory holes undertaken, investigate only a small volume of the ground in relation to the size of the site, and can only provide a general indication of the site conditions. The opinions provided and recommendations given in this report are based on the ground conditions apparent at the site of each of the exploratory holes. There may be ground conditions present on the sites which have not been disclosed by this investigation, and which have therefore not been considered in this report.

The comments made on groundwater conditions are based on observations made at the time that site work was carried out. It should be noted that groundwater levels will vary owing to seasonal, tidal, weather, or other effects.

The risk assessment and opinions provided, inter alia, take into consideration currently available guidance relating to acceptable contamination concentrations; no liability can be accepted for the retrospective effects of any future changes or amendments to these values.

**APPENDIX C: CURRENT CONTAMINATED LAND GUIDANCE / LEGISLATION & RISK ASSESSMENT
METHODOLOGIES**

CURRENT CONTAMINATED LAND LEGISLATION / GUIDANCE & ENVIRONMENTAL RISK ASSESSMENT METHODOLOGY

LEGISLATION OVERVIEW

This report includes hazard identification and risk assessment in line with the risk-based methods referred to in relevant UK legislation and guidance. Government environmental policy is based upon a "suitable for use approach". When considering the current use of land, Part IIA of the Environment Protection Act 1990 (EPA 1990) provides the regulatory regime, which was introduced by Section 57 of the Environment Act 1995, which came into force in England on 1 April 2000. The main objective of introducing the Part IIA regime is to provide an improved system for the identification and remediation of land where contamination is causing unacceptable risks to human health, or the wider environment given the current use and circumstances of the land.

Part IIA provides a statutory definition of contaminated land under Section 78A(2) as:

"any land which appears to the Local Authority in whose area it is situated to be in such a condition, by reason of substances in, on, or under the land, that:

Significant harm is being caused or there is a significant possibility of such harm being caused;

or

Pollution of controlled waters is being, or is likely to be, caused."

Part IIA provides a statutory definition of the pollution of controlled waters under Section 78A(9) as:

"the entry into controlled waters of **any** poisonous, noxious or polluting matter or **any** solid waste matter".

To assist in establishing if there is a "significant possibility of significant harm" there must be a "significant pollutant linkage" for potential harm to exist. That means there must be a source(s) of contamination, sensitive receptors present and a connection or pathway between the two. This combination of source-pathway-receptor is termed a "pollutant linkage or SPR linkage."

Part IIA of The Environmental Protection Act 1990 is supported by a substantial quantity of guidance and other Regulations, especially DEFRA Circular 01/2006 Contaminated Land (this replaces DETR Circular 02/2000). Part IIA defines the duties of Local Authorities in dealing with it. Except for situations of very high pollution risk, Part IIA places contaminated land responsibility on the planning and redevelopment process. In situations where there is very high pollution risk direct action from the Local Authority is usually necessary. Planning Policy Statement 23 (PPS23) provides guidance on the planning process and requires that sites which have been developed shall not be capable of being determined "contaminated land" under Part IIA.

The criteria for assessing levels of pollutants and hence determining whether a site represents a hazard are based on a range of techniques, models, and guidance. Within this context it is relevant to note that Government objectives are:

- (a) to identify and remove unacceptable risks to human health and the environment;
- (b) to seek to bring damaged land back into beneficial use;
- (c) to seek to ensure that the cost burdens faced by individuals, companies and society are proportionate, manageable, and economically sustainable.

These three objectives underlie the "suitable for use" approach to remediation of contaminated land. The "suitable for use" approach focuses on the risks caused by land contamination. The approach recognises that the risks presented by any given level of contamination will vary greatly according to the use of the land and a wide range of other factors, such as the underlying geology of the site. Risks therefore should be assessed on a site-by-site basis.

The "suitable for use" approach then consists of three elements:

- (a) ensuring that land is suitable for its current use - in other words, identifying any land where contamination is causing unacceptable risks to human health and the environment, assessed on the basis of the current use and circumstances of the land, and returning such land to a condition where such risks no longer arise; the contaminated land regime provides the regulatory mechanisms to achieve this;
- (b) ensuring that land is made suitable for any new use, as planning permission is given for that new use - in other words, assessing the potential risks from contamination, on the basis of the proposed future use and circumstances, before official permission is given for the development and, where necessary to avoid unacceptable risks to human health and the environment, remediating the land before the new use commences; this is the role of the town and country planning and building control regimes; and
- (c) limiting requirements for remediation to the work necessary to prevent unacceptable risks to human health or the environment in relation to the current use or future use of the land for which planning permission is being sought - in other words, recognising that the risks from contaminated land can be satisfactorily assessed only in the context of specific uses of the land (whether current or proposed), and that any attempt to guess what might be needed at some time in the future for other uses is likely to result either in premature work (thereby running the risk of distorting social, economic and environmental priorities) or in unnecessary work (thereby wasting resources).

The mere presence of pollutants does not therefore necessarily warrant action, and consideration must be given to the scale of risk involved for the current and proposed end use of the site.

RISK ASSESSMENT METHODOLOGY

Current practice recommends that the determination of potential liabilities that could arise from land contamination be carried out using the process of risk assessment, whereby "risk" is defined as:

- "(a) The probability, or frequency, or occurrence of a defined hazard; and

- (b) The magnitude (including the seriousness) of the consequences.”

The UK’s approach to the assessment of environmental risk is set out in by the Department of the Environment (2000) publication “A Guide to Risk Assessment and Risk Management for Environmental Protection.” This established an iterative, systematic staged process which comprises:

- (a) Hazard identification
- (b) Hazard assessment
- (c) Risk estimation
- (d) Risk evaluation
- (e) Risk Assessment

At each stage during the investigation process the above steps are repeated as more detailed information becomes available for the site.

CLR11- ‘Model Procedures for the Management of Land Contamination’, a document published by the Department for Environment, Food and Rural Affairs (DEFRA) and the Environment Agency (EA) outlines a tiered approach to the assessment of risks posed by contaminated land, as summarised hereunder:

Tier 1: Preliminary Risk Assessment

A Preliminary Risk Assessment is usually undertaken as part of a desk study, outlines potential risks posed by potential contamination to all receptors by defining plausible “pollution linkages” and developing a preliminary conceptual model (PCM). The purpose of this model is to define all possible complete pollution linkages, where the requisite source – pathway – target elements are present, and these elements being defined as:

- a contaminant (source) is a hazardous substance or agent, present at levels that have the potential to cause harm or damage a receptor
- a pathway is the means by or through which a contaminant meets, or otherwise affects, the receptor
- a receptor (target) is an entity (human being, aquatic environment, flora, and fauna etc) that is vulnerable to the adverse effects of the contaminant

This relationship is termed a “pollution linkage”. It should be recognised that for a health or environmental risk to exist, all three elements of the relationship or linkage must be present, i.e.

- if there is no contaminant, or contaminant present at levels below those considered to be harmful or damaging to a receptor, then there can be no adverse effect on a receptor
- if there is no receptor present that can be adversely affected by a contaminant, no harm or damage can arise
- even where both a contaminant and a receptor are present, no harm or damage will occur if there is no pathway by or through which a linkage between the two can be established

The absence of one or more of each component (source, pathway, receptor) would prevent a pollutant linkage being established and there would be no significant environmental risk.

The PCM is subject to continual refinement as additional data becomes available. As part of a Phase I Investigation (Desk Study and site walk over) a PCM is formed. Based on the PCM, potential pollutant linkages can be assessed. If the PCM and hazard assessment indicate that a pollution linkage is not of significance, then no further assessment or action is required due to this linkage. For each significant and possible linkage, a risk assessment is carried out. The linkages which potentially pose significant risks may require a variety of responses ranging from immediate remedial action or risk management or, more commonly, further investigation and risk assessment. This next stage is usually termed a Phase II Main Site Investigation and should provide additional data to allow refinement of the PCM and assess the level of risk from each pollutant linkage. Risk assessment will usually include Tier 2 Generic Quantitative Risk Assessment and / or, if necessary, a Tier 3 Detailed Quantitative Risk Assessment.

Tier 2: Generic Quantitative Risk Assessment (GQRA)

GQRA requires an intrusive investigation to characterise the site assisting in the re-assessment of the source-pathway receptor linkage. The conceptual model should be refined accordingly.

Upon completion of an intrusive investigation, it must be decided whether Generic Assessment Criteria (GAC) are suitable for assessing the risk posed by potential contamination at the site. If GAC are deemed unacceptable for risk assessment purposes or cannot be developed a Tier 3 Detailed Quantitative Risk Assessment (DQRA) is required.

If GQRA reveals that unacceptable risks are not present, then no further action is required. If GQRA identifies a possibility of risk, a decision must be made whether further work is required or necessary for the purposes of risk assessment. If further risk assessment is deemed not suitable not required, an Options Appraisal should be undertaken. If further risk assessment is required, the scope nature of further risk assessment must be decided – it is possible that a Tier 3 DQRA will be undertaken in this scenario.

Tier 3: Detailed Quantitative Risk Assessment (DQRA)

DQRA is used when pollutant linkages require further assessment. DQRA is often undertaken for pollutant linkages where GAC are unavailable or inappropriate for or more conservative than the actual circumstances of the site. Site specific data is used to create Site Specific Assessment Criteria (SSAC) and enable a more accurate assessment of the risks. Further investigation may or may not be required to formulate SSAC depending on the site-specific conditions and information already obtained.

If DQRA reveals that unacceptable risks are not present, then no further action is required. If DQRA identifies a possibility of risk, a decision must be made whether further work is required or necessary for the purposes of risk assessment. If further risk assessment is deemed not suitable not required, an Options Appraisal should be undertaken. If further risk assessment is required, the scope and nature of further risk assessment must be decided at this point.

NOTE: A Tier 1 Preliminary Risk Assessment is undertaken as part of a Desk Study Report and a Preliminary Conceptual Model is developed for all pollutant linkages. However, the methodologies for assessing the risks to human health, risks to controlled waters and risk posed by ground gas using quantitative techniques vary considerably, therefore GQRA and DQRA for human health, controlled waters and ground gas must be undertaken separately. The risk assessment methodologies where quantitative assessment is used for risks to human health, risks to controlled waters and risks posed by ground gas, if relevant, are described hereunder.

BACKGROUND INFORMATION, CURRENT GUIDANCE AND RISK ASSESSMENT METHODOLOGY FOR RISKS POSED TO HUMAN HEALTH

Background

In March 2002, the Department for Environment, Food and Rural Affairs (DEFRA) and the EA published the Contaminated Land Exposure Assessment (CLEA) Model and a series of related reports. These were designed to provide a scientifically based framework for the assessment of chronic risks to human health from contaminated land. These reports (CLR7-10) together with associated “SGV” documents have since been withdrawn (August 2008) and the following documents have been published as revised guidance to the CLEA assessment:

Environment Agency : 2008: Updated Technical Background to the CLEA model Science Report SC050021/SR3

Environment Agency : 2008: Human Health Toxicological Assessment of Contaminants in Soil SC050021/SR2

Additional guidance on statistical assessment replacing CLR 7 is provided in:

CL:AIRE :2008 Guidance on Comparing Data with a Critical Concentration

Other guidance/software used in spatial / statistical assessment is provided in:


USEPA 2006: Data Quality Assessment: Statistical Methods for Practitioners

Spatial Analysis and Decision Assistance (SADA) – The University of Tennessee

A different approach to the statistical appraisal of data is required depending on whether the assessment of risk is to assess whether land is Contaminated Land in accordance with regulations, or whether the assessment is to determine whether the site is suitable for new development in according with Planning guidance. This is discussed further in CL:AIRE :2008 “Guidance on Comparing Data with a Critical Concentration”.

A program for the derivation of GAC’s based on the above guidance is provided by the Environment Agency and is entitled “CLEA Software Version 1.04”.

The CLEA model has been developed to calculate an estimated tolerable daily soil intake (TDSI) for site users given a set ‘default’ exposure pathway. Ten human exposure pathways are covered in the CLEA model as presented below:



Ingestion

ingestion of outdoor soil

ingestion of indoor dust

ingestion of home grown produce

ingestion of soil attached to home grown produce

Dermal Contact

dermal contact with outdoor soil

dermal contact with indoor dust

Inhalation
inhalation of outdoor dust
inhalation of indoor dust
inhalation of outdoor soil vapour
inhalation of indoor soil vapour

It should be noted that there are other potential exposure pathways on some sites not included in the CLEA model e.g., certain organic compounds can pass through plastic water pipes into drinking water supply.

Where contaminated water is present at a depth less than 2.00mbgl and there is a potential risk of inhalation of vapours (only when volatile compounds are present) the risk from inhalation of vapours from soil water will be assessed using a UK compliant version of BP Risc v4.02.

The presence and/or significance of each of the above exposure pathways are dependent on the type of land use being considered and the nature of the contaminant under scrutiny. Accordingly, the CLEA model considers for principal 'default' land use types and makes a series of 'default' assumptions about human exposure frequency, duration and critical human target groups for each land use considered:

residential
allotments
commercial / industrial land use

The above land use categories defined in the CLEA are detailed below:

Residential: This generic scenario assumes a typical residential property consisting of a two-storey house built on a ground-bearing slab with a private garden consisting of lawn, flowerbeds, and a small fruit and vegetable patch. The occupants are assumed to be parents with young children, who make regular use of the garden area.

Allotments: This generic scenario assumes a plot of open space (about 250 m²), commonly made available by the local authority to tenants to grow fruit and vegetables for their own consumption. There are usually several plots to a site and the overall site area may cover more than a hectare. The tenants are assumed to be parents or grandparents and that young children make occasional accompanied visits to the plot.

Commercial/Industrial: There are many kinds of workplace and work-related activities. This generic scenario assumes a typical commercial or light industrial property consisting of a three-storey building at which employees spend most time indoors and are involved in office based or relatively light physical work.

Human Health Risk Assessment Methodology

Assessment of risk for the protection of human health is undertaken using the methodology as outlined previously, and summarised hereunder:

Tier 1 Preliminary Risk Assessment
Tier 2 Generic Quantitative Risk Assessment
Tier 3 Detailed Quantitative Risk Assessment

The Tier 1 Preliminary Risk Assessment is undertaken as part of the desk study report and includes the development of a Preliminary Conceptual Model. Tier 2 and Tier 3 Quantitative Risk Assessments are undertaken to develop and refine the Preliminary Conceptual Model aiding a more detailed assessment of the risk posed by contaminants revealed by site investigation and soil / soil water chemical analyses.

The methods used by Integra Consulting to derive assessment criteria, to statistically analyse chemical data and to compare chemical data to the derived assessment criteria are discussed hereunder.

Derivation of Generic Assessment Criteria (GAC) and Site-Specific Assessment Criteria (SSAC)

GAC's are derived based on the proposed land use and the associated applicable exposure pathways. It should be noted that there are difficulties in establishing soil concentrations of contaminants beyond which risks from exposure to these contaminants would be 'unacceptable' and the GAC value does not necessarily equate to the level for "significant possibility of significant harm" as defined in Part IIA of The Environmental Protection Act (1990) to determine whether land is "contaminated." This ultimately requires detailed 'toxicological' information of the health effects of individual contaminants and a scientific judgement on what constitutes an 'unacceptable' risk. The primary purpose of the CLEA derived GAC's are as 'minimal risk thresholds' for the assessment of human health risks in relation to land use.

Minimal risk thresholds calculated using generic input parameters for each of the above land uses are termed Generic Assessment Criteria (GAC) and are used for Generic Quantitative Risk Assessment (GQRA). However, further assessment may be required taking into consideration site specific factors such as the way the land is used, the soil type, the building characteristics, and the exact nature of the receptor, to determine whether there is a significant possibility of risk to human health to site users. Such an assessment is known as a Detailed Quantitative Risk Assessment (DQRA) and the resultant threshold concentrations are known as Site Specific Assessment Criteria (SSAC). Such assessments should be conducted with the agreement of the local authority (or the Environment Agency) since it is the authority that determines whether land is Contaminated Land or whether Planning Permission for a new development may be granted.

For the purposes of this report, assessment criteria have been derived in accordance with current guidance based on the conceptual model for the proposed land use using the CLEA v1.04 software. These criteria are not intended to indicate whether the site may be contaminated land, nor do they replace any published soil guideline values. However, the values are intended to provide guidance for the local authority on whether the site may be considered uncontaminated. If, based on the site's proposed future use, the site would be considered by the local authority to be uncontaminated and therefore, on the basis of soil concentrations, fit for purpose, then no further risk assessment based on soil concentrations and the risk to human health would be necessary. However, should these criteria be exceeded, or the conceptual site model vary from the model used in the risk assessment to derive these values then the risk assessment should be updated accordingly.

For contaminants routinely analysed where inhalation is a significant pathway (naphthalene, phenanthrene, Aromatic EC5-EC7, Aromatic EC7-EC8, Aromatic EC8-EC10, Aromatic EC10-EC12, Aromatic EC12-EC16, Aliphatic EC5-EC6, Aliphatic EC8-EC10, Aliphatic EC10-EC12, Aliphatic EC12-EC16), plots of the GAC as a function of Soil Organic Matter (SOM) are used to determine if they pose a potential risk to human health, which are presented hereunder. Where there is an exceedance further assessment may be undertaken.

Statistical Assessment of Soil Contamination Data & Comparison of Contamination Data to Threshold Values

In any site investigation only a small fraction of the soil on the site is analysed. Therefore, the mean derived from the contamination data for a contaminant may not be the same as the true mean for the contaminant distribution on the site. To improve the reliability of any assessment a statistical analysis is undertaken in line with the CL:AIRE document "Guidance on Comparing Soil Contamination Data with a Critical Concentration".

Statistical assessment of soil data is undertaken using programs based on the guidance in the CL:AIRE document or the USEPA software ProUCL v4.0.

Where the number of results in a dataset is less than four, a statistical assessment is not undertaken, and the assessment is performed by comparison of the maximum value(s) with a Health Criteria Value (HCV), such as Generic Assessment Criteria value(s).

For the Planning situation, the regulator needs to check whether the concentration of contaminants is low compared to the HCV. This decision is based on whether there is at least a 95% confidence level that the true mean of the dataset is lower than the HCV.

For the Part IIA scenario the regulator needs to determine whether the concentration of contaminants is greater than the HCV. This decision is based on whether there is at least a 95% confidence level that the true mean of the dataset is higher than the HCV. However, the regulator may proceed with determination if there is just a 51% probability, "on the balance of probabilities".

The Outlier Test used in the statistical assessment may not be able identify separate populations if numerous populations are present. To ensure that this is not the case a spatial assessment of the data will be undertaken using SADA.

If the screening levels are exceeded, then more sophisticated quantitative risk assessment or remedial action may be undertaken. The benefits of undertaking a quantitative risk assessment must be weighed against the likelihood that it will bring about cost savings in the proposed remediation.

BACKGROUND INFORMATION, CURRENT GUIDANCE AND RISK ASSESSMENT METHODOLOGY FOR RISKS POSED TO CONTROLLED WATER

Definition of Controlled Waters

The term 'controlled waters' is defined in Section 104 of the Water Resources Act 1991 as:

"Territorial Waters...which extend seawards for three miles..., coastal waters..., inland freshwaters, waters in any relevant lake or pond or of so much of any relevant river or watercourse as is above the freshwater limit, and ground waters, that is to say, any waters contained in underground strata."


Note that the definition of groundwater under the Water Resources Act 1991 includes all water within underground strata (including soil / pore water in the unsaturated zone). The definition of groundwater under the Groundwater Directive however is limited to water in the saturated zone. For the purposes of Part IIA of the Environmental Protection Act 1990, the Environment Agency recommends that the groundwater within the saturated zone only is considered as the receptor (rather than soil / pore water).

Environment Agency Guidance

Legislation and guidance surrounding the protection of controlled waters in the UK is abundant and can be complex. The Environment Agency's overall position on groundwater is "To protect and manage groundwater resources for present and future generation in ways that are appropriate for the risks that we identify" (Groundwater Protection : Policy and Practice GP3, 2006). In brief, the core objectives of the existing legislation serve to enforce this position.

In 1992, the National Rivers Authority published their Policy and Practice for the Protection of Groundwater (PPPG), this document was influential as it provided a focus for key developments such as Source Protection Zones (SPZs) and Groundwater Vulnerability Maps. The Policy was then revised in 1998, since which there have been substantial changes in legislation, driven by Europe. Key European Directives relating to groundwater include the Groundwater Directive (80/68/EEC) and the Water Framework Directive (2000/60/EC). Aspects of these directives are controlled by primary UK legislation such as the Water Resources Act 1991. Further to legislative changes, gaps identified in the 1998 PPPG required addressing. These changes are reflected in the forthcoming Environment Agency Policy document entitled Groundwater Protection : Policy and Practice (GP3), a draft version of which was available for public consultation (Parts 1 to 3) ending July 2006 with Part 4 issued in March 2008. Part 4 includes a section on key groundwater legislation and the Environment Agency's interpretation of it.

The following gives a breakdown of the structure of the document (taken from the Environment Agency GP3 draft consultation document, 2006)



Controlled Water Risk Assessment Methodology

The risk posed to controlled water is assessed by Integra Consulting in accordance with current guidance as outlined hereunder.

In order for a developer of a potentially contaminated site to fulfil their obligations under the legislation, a site assessment would be required to be undertaken in order to identify any potential risks to controlled waters and to derive suitable clean-up criteria if necessary to ensure the protection of controlled waters. The general approach for Groundwater Protection is detailed further in Part 3 of GP3.

When assessing groundwater impact the Environment Agency advocate the application of their framework methodology "Remedial Targets Methodology – Hydrogeological Risk Assessment for Land Contamination" Environment Agency (2006). The methodology has four levels of assessment as described below:

Level 1 considers whether contaminant concentrations in "pore water" in contaminated soil are enough to impact on the receptor, ignoring dilution, dispersion, and attenuation along the pathway. The "pore water" concentration is determined from:

measured "pore water" concentrations or perched water quality

ii) soil leaching tests


iii) theoretical calculations based on soil/water partitioning equations

Level 2 considers dilution by the receiving groundwater or surface water body and whether this is enough to reduce contaminant concentrations to acceptable levels. The remedial target is defined as the target concentration multiplied by a dilution factor (DF).

Levels 3 and 4 consider whether natural attenuation (including dispersion, retardation, and degradation) of the contaminant as it moves through the unsaturated and saturated zones to the receptor are enough to reduce contaminant concentrations to acceptable levels. The remedial target is defined as target concentration multiplied by a dilution factor (DF) and attenuation factor (AF). In Level 3 simple analytical models are used to calculate the significance of attenuation. The Environment Agency has released a "Remedial targets worksheet v3.1" to carry out basic calculations using a conservative approach up to Level 3 using basic principles assuming a simple migration of contaminants from the source zone into the aquifer receptor. Level 4 assessment uses more sophisticated numerical models and allows for the introduction of additional geological horizons and is used mainly to determine whether soil contaminants will reach their target within a specified timeframe. Use of such software should only be used once agreement has been obtained from the Environment Agency.

Three main stages apply to any risk assessment of controlled waters, these are:

1. Risk Screening (Tier 1 Preliminary Risk Assessment): The understanding of the Conceptual Site Model (CSM) is the key to assessing any site. Using a robust CSM, potential pathways or receptors may be screened out from any further assessment at an early stage. For example, if the pathway through the unsaturated zone is blocked by the presence of a significant thickness of low permeability clay. A greater understanding of the CSM is achieved with each tier of risk assessment. An example of a basic CSM is given below (taken from the Environment Agency GP3 draft consultation document, 2006):



2. Generic Hydrogeological Risk Assessment (EA Remedial Targets Methodology Level 1): When undertaking the Generic Hydrogeological Risk Assessment (EA Remedial Targets Methodology Tier 1), comparison of chemical analytical results is made with screening criteria. Published values of screening criteria with which chemical test results can be compared are published in the following guidance:

Water Supply (Water Quality) Regulations 2000

The Private Water Supplies Regulations 1991

Environmental Quality Standards for surface waters based on The EC Dangerous Substances Directive (76/464/EEC and Daughter Directives)

The Surface Waters (Abstraction for Drinking Water Classification) Regulations 1996

World Health Organisation Drinking Water Standards 2004

Should the Level 1 assessment indicate threshold levels to be exceeded, then there are three alternative ways in which to proceed:

To devise suitable remedial solutions

To carry out more investigation, sampling, and analysis

To conduct a site specific Detailed Quantitative Risk Assessment (DQRA) to determine if the materials are suitable for their proposed use, or devise site specific clean-up level

3. Detailed Quantitative Risk Assessment (EA Remedial Targets Methodology Levels 2 to 4): The decision to carry out a DQRA will be dependant on the extent and implications of the initial qualitative and generic assessment. The scope of any such assessment will be accurately defined by the outcomes of the previous levels of assessment. The conceptual model will be sufficiently refined by this stage that only certain contaminants of concern, certain pathways and certain receptors will require further assessment, the remainder having been screened out.

Additional site-specific data is normally required for this stage of assessment, as explained above, more processes that are capable of affecting contaminant concentrations are considered (such as dilution and attenuation).

Remediation criteria, if derived, will therefore be specific to each site and will be based on a detailed assessment of the potential impact at the identified receptor or compliance point. A greater level of confidence can be placed on the predicted impact on the compliance point following a DQRA.

BACKGROUND INFORMATION, CURRENT GUIDANCE AND RISK ASSESSMENT METHODOLOGY FOR RISKS POSED BY GROUND GAS

Origin of Ground and Landfill Gases

When carrying out a ground gas risk assessment, the origin or source of the gases is important as potential risks will vary depending on the source. This Appendix relates to the risk of the two main ground gases of concern; methane and carbon dioxide and does not apply to other ground gases (e.g., radon or vapours from hydrocarbon spills). Methane and carbon dioxide are major constituents of landfill gas but can also occur from a variety of anthropogenic and natural sources, as summarised in Table 5 below:

Gas	Source	Comments
Landfill Gas	Anaerobic decomposition of degradable waste within landfill sites. Typically, 60% methane and 40% carbon dioxide during methanogenic phase.	Composition varies over time, particularly in early stages. Contains a range of minor constituents (particularly carbon monoxide and hydrogen sulphide).
Landfill Associated Gases	- Anaerobic degradation of leachate external to the site; - Degassing of dissolved gases in groundwater; - Evolution of gases following interaction between leachate and groundwater	Can result in secondary (external) production of methane or carbon dioxide.
Made Ground	Anaerobic degradation of organic components	Very variable depending on source
Sewer Gas, Cess Pits	Anaerobic degradation of organic components of sewage producing methane and carbon dioxide.	Often characterised by hydrogen sulphide odour.
Mains Gas	Leakage from underground pipework or storage tanks. Mainly methane but often contains higher alkanes.	An odourise is added to permit detection of leaks. Typically, 90% CH ₄ , but 1 to 27% C ₂ -C ₄ alkanes, May also contain other trace gases e.g., CO, helium, and CO ₂ (from degradation of CH ₄ in the ground).

Gas	Source	Comments
Other Anthropogenic Sources	- Degradation of leaked or spilled hydrocarbons or other industrial chemicals; - Anaerobic degradation of organic contaminants in groundwaters (e.g., silage liquor); - Reactions between monitoring well construction components and environment; - Burial grounds/cemeteries.	Hydrocarbon spillages often have an 'oily' odour. Fuel spillages common – Petrol or Diesel and can contain a wide range of VOC's. Can degrade to produce methane / carbon dioxide.
Alluvium / Marsh / Peat Gas	Anaerobic microbial degradation of organic material (usually waterlogged vegetation / peat). Often associated with the presence of alluvial deposits or dredging's.	
Geogenic Gas	Natural seepages of carbon dioxide and hydrocarbon gases derived from geologic sources such as coal seams and deep oil / gas source formations. Can be present in solution in groundwaters.	Methane most common but can contain carbon dioxide and higher alkanes.
Mine Gases	Various types. Most common is "fire damp" with high methane, produced by the desorption of gas trapped in coal. "Black damp" (Scythe gas) with high carbon dioxide and denser than air. "White damp" is high in carbon monoxide.	Methane most common. Can contain higher alkanes, carbon dioxide and carbon monoxide. Often low in oxygen.
Natural Shallow Ground Gas	Various types - high carbon dioxide formed by subsurface aerobic activity leading to depleted oxygen and elevated carbon dioxide; - chemical degradation of rocks (e.g., carbonates) producing carbon dioxide; - carbon dioxide production in root zone of soils by plants.	Gases can be emitted from ground under falling barometric pressure conditions.

Table 5. Potential Sources of Ground Gases

This Appendix does not provide guidance for the assessment of risk when other gases are present due to 'Other Sources' from the above table (particularly organic compounds such as BTEX and VOC's or for the risk from radon or hydrogen sulphide).

To determine the origin of the gas a range of factors must be considered together, including;

1. Proximity of likely sources
2. Ground conditions (geology, hydrogeology, anthropogenic pathways etc)
3. Properties of gases present including:
 - Chemical composition
 - Physical properties
 - Ratios of components e.g., methane : carbon dioxide
4. Timeframe of activities such as infilling periods, capping works, installation of gas control systems etc

Identification of the originating source may be problematic given that there may be more than one source present and trace gas analysis may be required. Identification of the sources of the gases encountered during monitoring is usually carried out through a process of eliminating the most unlikely potential sources (given the site setting) and selecting those which are most likely.

Hazards Associated with Presence of Methane


Methane gas is combustible and potentially explosive. When the concentration of methane in air is between the limits of 5.0%v/v and 15.0%v/v an explosive mixture is formed. The Lower Explosive Limit (LEL) of methane is 5.0%v/v, which is equivalent to 100% LEL. The 15.0%v/v limit is known as the Upper Explosive Limit (UEL), but concentrations above this level cannot be assumed to represent safe concentrations. Further, the LEL and UEL will vary (up and down) depending upon the proportion of other gases (including oxygen). However, the fact that methane is a colourless, odourless gas means that there is no simple indicator of the presence of the gas until such a time as explosive limits are reached, and an incident occurs. Methane is lighter than air and has a low toxicity. However, at high concentrations it can result in asphyxiation due to oxygen displacement.

Hazards Associated with Presence of Carbon Dioxide

Carbon dioxide is a colourless, odourless gas, which, although non-flammable, is both toxic and an asphyxiant. As carbon dioxide is denser than air, it will collect in low points and depressions. The UK Health & Safety Executive (HSE) has published information relating to concentrations of carbon dioxide that humans may be exposed to, which uses concentrations contained in the Control of Substances Hazardous to Health Regulations 2002 (as amended). These are the Long-Term Occupational Exposure Limit (LTOEL, 8-hour period) and the Short-Term Occupational Exposure Limit (STOEL, 15-minute period), which are 0.5% and 1.5% carbon dioxide, respectively.

Parameters Influencing the Rate of Ground Gas Production

The figure below is taken from EA guidance document LFTGN 03 illustrates typical ground gas generation curves from biodegradable materials:



The production of methane and carbon dioxide at a landfill site may be expected to be considerable and ongoing. Concentrations of methane will eventually decrease, followed by concentrations of carbon dioxide, but the duration and rate of gas production can vary markedly between sites. Five distinct phases of gas production occur during the process which are, in order of event as marked above, as follows:

1. An aerobic phase involving oxygen depletion and temperature increase through aerobic respiration;
2. The establishment of anaerobic conditions and the evolution of carbon dioxide and hydrogen through acidogenic activity;
3. Commencement of methanogenic activity; the establishment of populations of methanogenic bacteria;
4. A phase of stable methanogenic activity, which may go on for many tens of years;
5. A phase of decreasing methanogenic activity, representing depletion of the organic material and a return to aerobic conditions.

The time scale for the return to the normal ground gas concentrations will be highly variable, depending upon the types and quantities of materials present. In addition, the optimum parameters influencing the rate of decomposition and ground gas production within the ground at a site are as follows:

High water content with adequate rainfall and water infiltration to provide moisture content between approximately 20 to 26%;
 Conditions that either are or are very close to anaerobic;
 High proportion of biodegradable materials;
 A pH between 6.5 and 8.5, ideally verging slightly on the acidic between pH 6 to 7;
 Temperature between 25°C and 55°C;
 The ratio of the biochemical and chemical oxygen demands (BOD:COD);
 High permeability;
 Small particle size, as finer subsurface materials possess a greater surface area to provide a growing 'face' for the micro-organisms, but high fines levels reduce permeability and reduces decomposition rate.

For this reason, it is vital that sources of methane and carbon dioxide are identified prior to the commencement of any work on a construction site, and that the ground gas regime is characterised at the worst temporal conditions a site may experience. From this, a risk assessment is carried out to identify the risk at the site from ground gases so that suitable protection measures can be designed and incorporated into a development to prevent a dangerous build-up of gas occurring.

Factors Influencing the Migration and Behaviour of Ground Gases

There are many factors that influence the migration of ground gases which can affect the risk from a gassing source:

driving force – pressure differential along a pathway, diffusion and dissolved in solution;
 meteorological conditions – short term and seasonal conditions including atmospheric pressure changes (e.g., rapidly falling pressure causes gas to expand increasing emission rates), rainfall, frozen ground and thawing, temperature;
 geological and groundwater conditions – these can have the over riding influence on the direction/pathways and quantity of migrating gas;
 anthropogenic influences – man-made pathways include mine shafts, service runs/drains, foundation piles, underground voids/pits/basements, foundation/building design/construction

Current Guidance

Previous versions of Building Regulations Approved Document C provided statutory guidance stating that consideration should be given to appropriate action and / or specific solutions in situations where methane concentration exceeded 1%v/v or carbon dioxide concentrations exceeded 5%v/v. The latest Building Regulations Approved Document C (DoE 2004) no longer endorses this approach and recommends the use of a risk-based approach to interpreting a gas monitoring survey. This is in line with current EA guidance for landfill gas (LFTGN 03, 2004) which recommends the use of a structured risk-based approach like that outlined in CLR 11. On this basis, recent guidance has been produced in 2006 and 2007 with the aim of providing up to date advice in relation to residential and commercial development. The guidance does not address issues associated with gas derived from landfills, for this refer to "Guidance on the Management of Landfill Gas" (Environment Agency 2004) for an overview.

Recent guidance relevant to gas assessments for residential and commercial development includes;

Wilson et al. (CIRIA C665, December 2007) "Assessing Risks Posed by Hazardous Ground Gases for Buildings."

This document provides up to date advice on all aspects of ground gas risk assessment such as investigation, monitoring programmes, data collection and interpretation. The guidance presents separate methodologies for the characterisation of:

All development types except low rise housing with gardens (Situation A)

Low rise housing with gardens (Situation B)

Boyle and Witherington (NHBC / RSK Group, Report 10627-R01(04) January 2007) "Guidance on the Evaluation of Development Proposals on Sites where Methane and Carbon Dioxide are Present."

This document presents the "Traffic Lights System" detailed below and is relevant only for low rise properties (e.g., bungalows and town houses) that have a ventilated sub-floor void (i.e., Situation B as described in CIRIA C665).

British Standard (BS 8485, December 2007) "Code of Practice for the Characterization and Remediation from Ground Gas in Affected Developments"

This document provides an overview of gas characterisation and assessment. The Standard is intended to be used by designers of gas protection measures and regulators involved in the assessment of design solutions.

Further guidance, Wilson, and Card (CIEH) "Ground Gas Handbook for Designers and Regulators" providing practical guidance on ground gas assessments and the design and evaluation of protection measures, is expected to be published in March 2009.

Each of these documents continues to highlight the importance of, and give further guidance towards, carrying out a tiered risk-based decision-making process in accord with government policy on dealing with contamination from historic or natural sources and highlight the importance of the Conceptual Model in site characterisation.

Ground Gas Risk Assessment Methodology

Assessment of risk posed by ground gas is undertaken using the methodology as outlined previously, and summarised hereunder:

Tier 1 Preliminary Risk Assessment

Tier 2 Generic Quantitative Risk Assessment

Tier 3 Detailed Quantitative Risk Assessment

The methodology used in each of the above assessments with concern to ground gas is discussed hereunder.

Tier 1 Preliminary Risk Assessment

All potential sources of methane and carbon dioxide are identified in the Preliminary Conceptual Model and the generation potential determined. The background information discussed earlier is referred to in order to determine the potential for a source to generate ground gas.

CIRIA C665 provides idealised monitoring frequency / period dependant upon generation potential of gas source and sensitivity of the proposed land use as below:

Idealised Frequency and Period of Monitoring (after Table 5.5a and 5.5b, CIRIA C665)

		Generation Potential of Source				
		Very Low	Low	Moderate	High	Very High
Sensitivity of Development	Low (Commercial)	4/1	6/2	6/3	12/6	12/12
	Moderate (Flats)	6/2	6/3	9/6	12/12	24/24
	High (Residential with Gardens)	6/3	9/6	12/6	24/12	24/24

Notes

1. First number is the number of readings and the second is the minimum period in months (e.g., 6/2 – six sets of readings over two months).
2. At least two sets of readings must be at low (preferably under 1,000 mb) and falling pressure.

The monitoring programme is decided using the above table prior to the intrusive site investigation. However, if the intrusive investigation reveals that the potential source is better or worse than anticipated the monitoring programme should be modified accordingly. For example, if the made ground contains no evidence of organic material and comprises entirely granular brick fill, the potential for that made ground to generate ground gas is reduced considerably.

Tier 2 Generic Quantitative Risk Assessment

Generic Quantitative Risk Assessment is undertaken upon completion of the required gas monitoring period.

All three current guidance documents propose that both ground gas concentrations and flow rates are used to calculate the limiting gas well gas volume flow rates for methane and carbon dioxide, based on the ground gas conditions monitored for during the worse-case temporal conditions. This limiting gas well volume flow rate is termed the Gas Screening Value (GSV, note that this was termed borehole gas volume flow), and is calculated as follows:

$$\text{GSV (l/hr)} = [\text{gas well gas concentration (\%v/v)}] \times [\text{gas well flow rate (l/hr)}]$$

GSV's are compared to typical max concentrations and limiting gas screening values derived for either Situation A - All development except low rise housing with gardens, or Situation B low rise housing with gardens (NHBC Traffic Light System). Table 8.5 from CIRIA C665 is used for comparison of gas screening values for "Situation A Developments" and is presented hereunder:

Characteristic Situation (CIRIA R149)	Comparable Partners in Technology gas Regime (see Box 8.2)	Risk Classification	Gas Screening Value (CH ₄ or CO ₂) (l/hr) ¹	Additional Factors	Typical Source of Generation
1	A	Very low risk	<0.07	Typically, methane ≤ 1% and/or carbon dioxide ≤ 5%. Otherwise consider increase to Situation 2	Natural soils with low organic content "Typical" made ground
2	B	Low risk	<0.7	Borehole air flow rate not to exceed 70l/hr. Otherwise consider increase to characteristic Situation 3	Natural soil, high peat/organic content. "Typical" made ground
3	C	Moderate risk	<3.5		Old landfill, inert waste, mineworking flooded
4	D	Moderate to high risk	<15	Quantitative risk assessment required to evaluate scope of protective measures.	Mineworking susceptible to flooding, completed landfill (WMP 26B criteria)
5	E	High risk	<70		Mineworking unflooded inactive with shallow workings near surface
6	F	Very high risk	>70		Recent landfill site

Table 8.5 from CIRIA C665 Modified Wilson and Card Classification

Table 8.7 is used for comparison of gas screening values for "Situation B Developments" and is presented hereunder:

Traffic Light	Methane ¹		Carbon Dioxide ²	
	Typical max concentration ³ (% by volume)	Gas screening value ^{2,4} (litres/hour)	Typical concentration ³ (% max by volume)	Gas screening value ^{2,4} (litres/hour)
Green				
Amber 1	1	0.13	5	0.78
Amber 2	5	0.63	10	1.60
Red	20	1.60	30	3.10

Notes:

1. The worst-case ground gas regime identified on the site, either methane or carbon dioxide, at the worst-case temporal conditions that the site may be expected to encounter will be the decoder as to what Traffic Light is allocated;
2. Borehole Gas Volume Flow Rate, in litres per hour as defined in Wilson and Card (1999), is the borehole flow rate multiplied by the concentration in the air stream of the gas being considered;
3. The Typical Maximum Concentration can be exceeded in certain circumstances should the Conceptual Site Model indicate it is safe to do so;
4. The Gas Screening Value thresholds should not generally be exceeded without the completion of a detailed ground gas risk assessment considering site-specific conditions.

Table 8.7 from CIRIA C665 - NHBC Traffic light system for 150 mm void

Dependant on the outcome of the assessment of risk posed by ground gas it is determined whether gas protection measures are required for the proposed development, and or whether a detailed quantitative risk assessment is required for the site.

Selection & Design of Protective Measures

Table 8.6 and Box 8.4 of CIRIA C665 contain information on the detailed design of protection measures and were initially intended for the purposes of determining then level of protection measures a development requires. These tables and related text include some useful information on the design of gas protection measures, however BS8485:2007, which supersedes the guidance included within CIRIA C665, is used for selection of gas protection measures.

BS8485: 2007 uses a scoring system dependant on the Characteristic Situation / NHBC Traffic Light and proposed end use of the site. The scoring system is summarised in BS8485:2007 Table 2 as presented hereunder:

Characteristic situation, CS	gas	NHBC traffic light	Required gas protection			
			Non-managed property e.g., private housing	Public building (a)	Commercial buildings	Industrial buildings (b)
1		Green	0	0	0	0

2	Amber 1	3	3	2	1 (c)
3	Amber 2	4	3	2	2
4	Red	6 (d)	5(d)	4	3
5			6(e)	5	4
6				7	6

NOTE Traffic light indications are taken from NHBC Report no.:10627-RO1 (04) and are mainly applicable to low-rise residential housing¹. These are for comparative purposes but the boundaries between the traffic light indications and CS values do not coincide.

a) Public buildings include, for example, managed apartments, schools, and hospitals.

b) Industrial buildings are generally open and well ventilated. However, areas such as office pods might require a separate assessment and may be classified as commercial buildings and require a different scope of gas protection to the main building.

c) Maximum methane concentration 20% otherwise consider and increase to CS3.

d) Residential building on higher traffic light/CS sites is not recommended unless the type of construction or site circumstances allow additional levels of protection to be incorporated, e.g., high-performance ventilation or pathway intervention measures, and an associated sustainable system of management of maintenance of the gas control system, e.g., in institutional and/or fully serviced contractual situations.

e) Consideration of issues such as ease of evacuation and how false alarms will be handled are needed when completing the design specification of any gas protection scheme

¹ The NHBC guidance and CIRIA C665 guidance refers to low rise housing (which is up to three storeys without lifts) that is constructed with a 150mm ventilated sub-floor void.

BS8485:2007 Table 2 Required gas protection by characteristic gas situation and type of building

Once a score is assigned, a combination of protection systems / elements is chosen from BS8485:2007 Table 3 shown below:

PROTECTION ELEMENT/SYSTEM		SCORE	COMMENTS
a) Venting/dilution (See Annex A BS8485)			
Passive sub floor ventilation (venting layer can be a clear void or formed using gravel, geocomposites, polystyrene void formers, etc.)A Subfloor ventilation with active abstraction/pressurization (venting layer can be a clear void or formed using gravel, geocomposites, polystyrene void formers, etc.)A Ventilated car park (basement or undercroft)	Very good performance	2.5	Ventilation performance in accordance with Annex A (BS8485)
	Good performance	1	If passive ventilation is poor this is generally unacceptable, and some form of active system will be required.
		2.5	There must be robust management systems in place to ensure the continued maintenance of any ventilation system. Active ventilation can always be designed to meet good performance.
		4	Mechanically assisted systems come in two forms: extraction and positive pressurization.
b) Barriers			
Floor slabs			
Block and beam floor slab		0	It is good practice to install ventilation in all foundation systems to effect pressure relief as a minimum. Breaches in floor slabs such as joints must be effectively sealed against gas ingress in order to maintain these performances.
Reinforced concrete ground bearing slab		0.5	
Reinforced concrete ground bearing foundation raft with limited-service penetrations that are cast into slab		1.5	
Reinforced concrete cast in situ suspended floor slab with minimal service penetrations and water bars around all slab penetrations and at joints		1.5	
Fully tanked basement		2	
c) Membranes			
Taped and sealed membrane to reasonable levels of workmanship/in line with current good practice with validation B,C		0.5	The performance of membranes is heavily dependent on the quality of design of the installation, resistance to damage after installation, and the integrity of joints.
Proprietary gas resistant membrane to reasonable levels of workmanship /in line with good practice under independent inspection (CQA)B,C		1	
Proprietary gas resistant membrane installed to reasonable levels of workmanship/in line with current good practice under CQA with integrity testing and independent validation		2	
d) Monitoring and detection (not applicable to non-managed property, or in isolation)			
Intermittent monitoring using handheld equipment		0.5	Where fitted, permanent monitoring systems ought to be installed in the underfloor venting/dilution system in the first instance but can also be provided within the occupied space as a fail safe.
Permanent monitoring and alarm system A	Installed in the underfloor venting/dilution system	2	
	Installed in the building	1	
e) Pathway Intervention			
Pathway intervention		-	This can consist of site protection measures for off-site or on-site sources (see Annex A, BS8485)
NOTE In practice the choice of materials might well rely on factors such as construction method and the risk of damage after installation. It is important to ensure that the chosen combination gives an appropriate level of protection			
It is possible to test ventilation systems by installing monitoring probes for post installation validation.			
If a 1 200g DPM material is to function as a gas barrier it should be installed according to BRE 212 /BRE 414 being taped and sealed to all penetrations			
Polymeric Materials> 1200 g (proportional to thickness) but their physical properties mean that they are more robust and resistant to damage.			

BS8485:2007 Table 3 Solution Scores

Where the gas situation is 4 or more (and for NHBC Red situations) the site requires a comprehensive risk assessment to confirm the scope of protection measures. These are higher risk sites and reliance on Table 2 and 3 alone is not enough.

For a site which is impacted by migratory gases from an off-site source, the development may be protected by imposing pathway intervention methods, which if successfully validated, could also remove the need for further analysis. It is essential that the gas regime in these circumstances has been fully characterised and that the only source impacting the site is located off site and that the pathway is clearly defined and its interception equally proven before construction commences. Pathway intervention methods may include vertical membrane installations, venting trenches, rows of stone columns, activated trenches and various proprietary systems. These systems are particularly relevant to domestic housing where there is limited scope for foundation type solutions.

CURRENT GUIDANCE ON REMEDIATION

When risk assessment of the site has been completed and it indicates that remedial works are required, the main guidance in managing this process is set out in the DEFRA/EA publication CLR11 (2004) "Model Procedures for the Management of Land Contamination." The stages of managing remediation are as follows:

- (a) Options Appraisal and develop Remediation Strategy;
- (b) Develop Implementation Plan and Verification Plan;
- (c) Remediation, Verification and Monitoring.

The Remediation Strategy sets out the remediation targets, identifies technically feasible remedial solutions and presents an evaluation of the options so that these can be assessed enabling that the most suitable solution is adopted. An outline of the proposed remedial method should be presented. Agreement should be sought of the appropriate statutory bodies for the Remediation Strategy before proceeding to the next stage.

The Implementation Plan is a detailed method statement setting out how the remediation is to be carried out including stating how the site will be managed, welfare procedures, health, and safety considerations together with practical measures such as details of temporary works, programme of works, waste management licences and regulatory consents required. Agreement should again be sought of the appropriate statutory bodies for this Plan.

The Verification Plan sets out the requirements for gathering data to demonstrate that the remediation has met the required remediation objectives and criteria. The Verification Plan presents the requirements for a wide range of issues including the level of supervision, sampling and testing regimes for treated materials, waste and imported materials, required monitoring works during and post remediation, how compliance with all licenses and consents will be checked etc. Agreement should again be sought of the appropriate statutory bodies for the Verification Plan. On completion of the remediation a Verification Report should be produced to provide a complete record of all remediation activities on site and the data collected as required in the Verification Plan. The Verification Report should demonstrate that the remediation has met the remedial targets to show that the site is suitable for the proposed use.

APPENDIX D: COMMERCIAL ENVIRONMENTAL DATA


Land off Queen Street & Whitehall Street, Rochdale, OL12 0TY

Order Details

Date: 03/01/2023
Your ref: CMAPS-AAG-1078975-4165-030123
Our Ref: CMAPS-AAG-1078975-4165-030123EDRGEO

Site Details

Location: 389786 413897
Area: 0.23 ha
Authority: [Rochdale Metropolitan Borough Council](#)



Summary of findings

p. 2

Aerial image

p. 8

OS MasterMap site plan

p.13

groundsure.com/insightuserguide

Contact us with any questions at:

info@groundsure.com

08444 159 000

Summary of findings

Page	Section	Past land use	On site	0-50m	50-250m	250-500m	500-2000m
14	1.1	Historical industrial land uses	1	8	19	66	-
18	1.2	Historical tanks	0	0	3	4	-
19	1.3	Historical energy features	0	2	3	18	-
20	1.4	Historical petrol stations	0	0	0	0	-
20	1.5	Historical garages	0	0	8	22	-
21	1.6	Historical military land	0	0	0	0	-
Page	Section	Past land use - un-grouped	On site	0-50m	50-250m	250-500m	500-2000m
22	2.1	Historical industrial land uses	2	9	25	91	-
27	2.2	Historical tanks	0	0	4	6	-
28	2.3	Historical energy features	0	8	5	41	-
30	2.4	Historical petrol stations	0	0	0	0	-
30	2.5	Historical garages	0	0	19	34	-
Page	Section	Waste and landfill	On site	0-50m	50-250m	250-500m	500-2000m
33	3.1	Active or recent landfill	0	0	0	0	-
33	3.2	Historical landfill (BGS records)	0	0	0	0	-
34	3.3	Historical landfill (LA/mapping records)	0	0	0	0	-
34	3.4	Historical landfill (EA/NRW records)	0	0	0	2	-
34	3.5	Historical waste sites	0	0	0	12	-
36	3.6	Licensed waste sites	0	0	0	16	-
41	3.7	Waste exemptions	0	0	12	49	-
Page	Section	Current industrial land use	On site	0-50m	50-250m	250-500m	500-2000m
47	4.1	Recent industrial land uses	0	6	30	-	-
50	4.2	Current or recent petrol stations	0	0	1	1	-
50	4.3	Electricity cables	0	0	0	0	-
50	4.4	Gas pipelines	0	0	0	0	-
51	4.5	Sites determined as Contaminated Land	0	0	0	0	-



51	4.6	Control of Major Accident Hazards (COMAH)	0	0	0	0	-
51	4.7	Regulated explosive sites	0	0	0	0	-
51	4.8	Hazardous substance storage/usage	0	0	0	0	-
51	4.9	Historical licensed industrial activities (IPC)	0	0	0	0	-
52	4.10	Licensed industrial activities (Part A(1))	0	0	0	0	-
52	4.11	<u>Licensed pollutant release (Part A(2)/B)</u>	0	1	1	2	-
53	4.12	Radioactive Substance Authorisations	0	0	0	0	-
53	4.13	<u>Licensed Discharges to controlled waters</u>	0	0	3	6	-
54	4.14	Pollutant release to surface waters (Red List)	0	0	0	0	-
55	4.15	Pollutant release to public sewer	0	0	0	0	-
55	4.16	List 1 Dangerous Substances	0	0	0	0	-
55	4.17	List 2 Dangerous Substances	0	0	0	0	-
55	4.18	<u>Pollution Incidents (EA/NRW)</u>	0	0	0	2	-
56	4.19	Pollution inventory substances	0	0	0	0	-
56	4.20	Pollution inventory waste transfers	0	0	0	0	-
56	4.21	Pollution inventory radioactive waste	0	0	0	0	-
Page	Section	Hydrogeology	On site	0-50m	50-250m	250-500m	500-2000m
57	5.1	<u>Superficial aquifer</u>	Identified (within 500m)				
59	5.2	<u>Bedrock aquifer</u>	Identified (within 500m)				
61	5.3	<u>Groundwater vulnerability</u>	Identified (within 50m)				
62	5.4	Groundwater vulnerability- soluble rock risk	None (within 0m)				
62	5.5	Groundwater vulnerability- local information	None (within 0m)				
63	5.6	<u>Groundwater abstractions</u>	0	0	0	0	3
64	5.7	<u>Surface water abstractions</u>	0	0	0	0	17
69	5.8	<u>Potable abstractions</u>	0	0	0	0	2
69	5.9	Source Protection Zones	0	0	0	0	-
70	5.10	Source Protection Zones (confined aquifer)	0	0	0	0	-
Page	Section	Hydrology	On site	0-50m	50-250m	250-500m	500-2000m
71	6.1	Water Network (OS MasterMap)	0	0	0	-	-



71	6.2	Surface water features	0	0	0	-	-
72	6.3	<u>WFD Surface water body catchments</u>	1	-	-	-	-
72	6.4	<u>WFD Surface water bodies</u>	0	0	0	-	-
73	6.5	<u>WFD Groundwater bodies</u>	1	-	-	-	-
Page	Section	River and coastal flooding	On site	0-50m	50-250m	250-500m	500-2000m
74	7.1	Risk of flooding from rivers and the sea	None (within 50m)				
74	7.2	Historical Flood Events	0	0	0	-	-
74	7.3	Flood Defences	0	0	0	-	-
75	7.4	Areas Benefiting from Flood Defences	0	0	0	-	-
75	7.5	Flood Storage Areas	0	0	0	-	-
76	7.6	Flood Zone 2	None (within 50m)				
76	7.7	Flood Zone 3	None (within 50m)				
Page	Section	Surface water flooding					
77	8.1	<u>Surface water flooding</u>	1 in 30 year, 0.3m - 1.0m (within 50m)				
Page	Section	Groundwater flooding					
79	9.1	<u>Groundwater flooding</u>	Low (within 50m)				
Page	Section	Environmental designations	On site	0-50m	50-250m	250-500m	500-2000m
80	10.1	<u>Sites of Special Scientific Interest (SSSI)</u>	0	0	0	0	2
81	10.2	Conserved wetland sites (Ramsar sites)	0	0	0	0	0
81	10.3	<u>Special Areas of Conservation (SAC)</u>	0	0	0	0	2
82	10.4	Special Protection Areas (SPA)	0	0	0	0	0
82	10.5	National Nature Reserves (NNR)	0	0	0	0	0
82	10.6	<u>Local Nature Reserves (LNR)</u>	0	0	0	0	1
82	10.7	<u>Designated Ancient Woodland</u>	0	0	0	0	2
83	10.8	Biosphere Reserves	0	0	0	0	0
83	10.9	Forest Parks	0	0	0	0	0
83	10.10	Marine Conservation Zones	0	0	0	0	0
83	10.11	<u>Green Belt</u>	0	0	0	0	2
84	10.12	Proposed Ramsar sites	0	0	0	0	0



84	10.13	Possible Special Areas of Conservation (pSAC)	0	0	0	0	0
84	10.14	Potential Special Protection Areas (pSPA)	0	0	0	0	0
84	10.15	Nitrate Sensitive Areas	0	0	0	0	0
85	10.16	Nitrate Vulnerable Zones	0	0	0	0	0
86	<u>10.17</u>	<u>SSSI Impact Risk Zones</u>	1	-	-	-	-
87	<u>10.18</u>	<u>SSSI Units</u>	0	0	0	0	2
Page	Section	Visual and cultural designations	On site	0-50m	50-250m	250-500m	500-2000m
89	11.1	World Heritage Sites	0	0	0	-	-
90	11.2	Area of Outstanding Natural Beauty	0	0	0	-	-
90	11.3	National Parks	0	0	0	-	-
90	<u>11.4</u>	<u>Listed Buildings</u>	0	0	7	-	-
91	<u>11.5</u>	<u>Conservation Areas</u>	0	0	2	-	-
91	11.6	Scheduled Ancient Monuments	0	0	0	-	-
92	11.7	Registered Parks and Gardens	0	0	0	-	-
Page	Section	Agricultural designations	On site	0-50m	50-250m	250-500m	500-2000m
93	<u>12.1</u>	<u>Agricultural Land Classification</u>	Urban (within 250m)				
94	12.2	Open Access Land	0	0	0	-	-
94	12.3	Tree Felling Licences	0	0	0	-	-
94	12.4	Environmental Stewardship Schemes	0	0	0	-	-
94	12.5	Countryside Stewardship Schemes	0	0	0	-	-
Page	Section	Habitat designations	On site	0-50m	50-250m	250-500m	500-2000m
95	13.1	Priority Habitat Inventory	0	0	0	-	-
95	13.2	Habitat Networks	0	0	0	-	-
96	<u>13.3</u>	<u>Open Mosaic Habitat</u>	0	0	1	-	-
96	13.4	Limestone Pavement Orders	0	0	0	-	-
Page	Section	Geology 1:10,000 scale	On site	0-50m	50-250m	250-500m	500-2000m
97	<u>14.1</u>	<u>10k Availability</u>	Identified (within 500m)				
98	<u>14.2</u>	<u>Artificial and made ground (10k)</u>	0	0	0	4	-
100	<u>14.3</u>	<u>Superficial geology (10k)</u>	1	0	3	4	-



101	14.4	Landslip (10k)	0	0	0	0	-
102	14.5	<u>Bedrock geology (10k)</u>	1	0	3	3	-
103	14.6	Bedrock faults and other linear features (10k)	0	0	0	0	-
Page	Section	Geology 1:50,000 scale	On site	0-50m	50-250m	250-500m	500-2000m
104	15.1	<u>50k Availability</u>	Identified (within 500m)				
105	15.2	Artificial and made ground (50k)	0	0	0	0	-
105	15.3	Artificial ground permeability (50k)	0	0	-	-	-
106	15.4	<u>Superficial geology (50k)</u>	1	0	1	2	-
107	15.5	<u>Superficial permeability (50k)</u>	Identified (within 50m)				
107	15.6	Landslip (50k)	0	0	0	0	-
107	15.7	Landslip permeability (50k)	None (within 50m)				
108	15.8	<u>Bedrock geology (50k)</u>	1	0	2	1	-
109	15.9	<u>Bedrock permeability (50k)</u>	Identified (within 50m)				
109	15.10	Bedrock faults and other linear features (50k)	0	0	0	0	-
Page	Section	Boreholes	On site	0-50m	50-250m	250-500m	500-2000m
110	16.1	<u>BGS Boreholes</u>	1	0	10	-	-
Page	Section	Natural ground subsidence					
112	17.1	<u>Shrink swell clays</u>	Very low (within 50m)				
113	17.2	<u>Running sands</u>	Very low (within 50m)				
114	17.3	<u>Compressible deposits</u>	Negligible (within 50m)				
115	17.4	<u>Collapsible deposits</u>	Very low (within 50m)				
116	17.5	<u>Landslides</u>	Very low (within 50m)				
117	17.6	<u>Ground dissolution of soluble rocks</u>	Negligible (within 50m)				
Page	Section	Mining, ground workings and natural cavities	On site	0-50m	50-250m	250-500m	500-2000m
119	18.1	Natural cavities	0	0	0	0	-
120	18.2	<u>BritPits</u>	0	0	1	1	-
120	18.3	<u>Surface ground workings</u>	0	1	6	-	-
121	18.4	<u>Underground workings</u>	0	0	0	0	3
121	18.5	Historical Mineral Planning Areas	0	0	0	0	-



121	18.6	Non-coal mining	0	0	0	0	0
122	18.7	Mining cavities	0	0	0	0	0
122	18.8	JPB mining areas	None (within 0m)				
122	18.9	<u>Coal mining</u>	Identified (within 0m)				
122	18.10	Brine areas	None (within 0m)				
123	18.11	Gypsum areas	None (within 0m)				
123	18.12	Tin mining	None (within 0m)				
123	18.13	Clay mining	None (within 0m)				
Page	Section	Radon					
124	19.1	<u>Radon</u>	Less than 1% (within 0m)				
Page	Section	Soil chemistry	On site	0-50m	50-250m	250-500m	500-2000m
126	20.1	<u>BGS Estimated Background Soil Chemistry</u>	1	0	-	-	-
126	20.2	BGS Estimated Urban Soil Chemistry	0	0	-	-	-
126	20.3	BGS Measured Urban Soil Chemistry	0	0	-	-	-
Page	Section	Railway infrastructure and projects	On site	0-50m	50-250m	250-500m	500-2000m
127	21.1	Underground railways (London)	0	0	0	-	-
127	21.2	Underground railways (Non-London)	0	0	0	-	-
127	21.3	Railway tunnels	0	0	0	-	-
127	21.4	Historical railway and tunnel features	0	0	0	-	-
127	21.5	Royal Mail tunnels	0	0	0	-	-
128	21.6	Historical railways	0	0	0	-	-
128	21.7	Railways	0	0	0	-	-
128	21.8	Crossrail 1	0	0	0	0	-
128	21.9	Crossrail 2	0	0	0	0	-
128	21.10	HS2	0	0	0	0	-



Recent aerial photograph




Aerial photography supplied by Getmapping PLC. © Copyright Getmapping PLC 2023. All Rights Reserved.

Capture Date: 23/05/2019

Site Area: 0.23ha



Recent site history - 2018 aerial photograph




Aerial photography supplied by Getmapping PLC. © Copyright Getmapping PLC 2023. All Rights Reserved.

Capture Date: 01/07/2018

Site Area: 0.23ha



Recent site history - 2012 aerial photograph



Aerial photography supplied by Getmapping PLC. © Copyright Getmapping PLC 2023. All Rights Reserved.

Capture Date: 26/03/2012

Site Area: 0.23ha



Recent site history - 2000 aerial photograph



Aerial photography supplied by Getmapping PLC. © Copyright Getmapping PLC 2023. All Rights Reserved.

Capture Date: 19/06/2000

Site Area: 0.23ha



Recent site history - 1999 aerial photograph




Aerial photography supplied by Getmapping PLC. © Copyright Getmapping PLC 2023. All Rights Reserved.

Capture Date: 10/09/1999

Site Area: 0.23ha



OS MasterMap site plan




© Crown copyright and database rights 2023. Ordnance Survey licence 100035207

Site Area: 0.23ha



1 Past land use



- Site Outline
- Search buffers in metres (m)
- Historical industrial land uses
- Historical tanks
- Historical energy features
- Historical garages

1.1 Historical industrial land uses

Records within 500m

94

Potentially contaminative land use features digitised from historical Ordnance Survey mapping at 1:10,000 and 1:10,560 scale, intelligently grouped into contiguous features. To prevent misrepresentation of the size of historical features at any given time, features are only grouped if they have similar geometries within immediately preceding or succeeding map editions. See section 2 for a breakdown of grouping if required. Grouped and the original un-grouped features can be cross-referenced across sections 1 and 2 using the 'Group ID'.

Features are displayed on the Past land use map on **page 14**

ID	Location	Land use	Dates present	Group ID
A	On site	Unspecified Works	1975 - 1987	695987



ID	Location	Land use	Dates present	Group ID
B	23m E	Unspecified Mills	1949	774364
B	24m E	Unspecified Commercial/Industrial	1891	764450
B	24m E	Unspecified Mills	1938	736780
B	25m E	Unspecified Mill	1975	657139
B	26m E	Unspecified Commercial/Industrial	1968	764683
B	27m E	Cotton Mills	1851	659337
B	28m E	Unspecified Mills	1908 - 1928	783932
A	31m S	Unspecified Works	1992	724497
B	50m E	Unspecified Commercial/Industrial	1987 - 1992	716726
B	75m E	Chimney	1968 - 1975	744807
B	123m E	Pump	1851	675569
E	123m N	Woollen Mill	1851	670985
F	130m N	Unspecified Commercial/Industrial	1968	757307
F	130m N	Unspecified Mills	1949	789838
F	131m N	Unspecified Commercial/Industrial	1975 - 1987	706201
F	132m N	Unspecified Mills	1938	706053
F	132m N	Unspecified Commercial/Industrial	1891 - 1928	753030
D	143m NW	Pump	1851	675568
F	143m N	Unspecified Mills	1992	746909
G	145m SW	Chimney	1968	684526
E	155m N	Clay Pit	1851	676030
D	168m N	Ambulance Station	1992	676098
H	186m NE	Corporation Depot	1891	685836
F	217m N	Rope Walk	1851	641256
I	224m NE	Unspecified Mill	1976	657138
F	235m N	Shed	1851	659581
J	240m NW	Infirmary	1987 - 1992	707060
J	264m NW	Infirmary	1949	701004



ID	Location	Land use	Dates present	Group ID
J	264m NW	Infirmery	1975	724787
J	264m NW	Infirmery	1968	745287
J	265m NW	Infirmery And Dispensary	1908 - 1938	706331
5	290m NE	Unspecified Depot	1992	668799
J	332m NW	Infirmery And Dispensary	1891	709310
7	339m NE	Railway Sidings	1891	693892
P	339m NE	Railway Sidings	1938 - 1968	751485
P	340m NE	Railway Sidings	1949 - 1954	778967
P	341m NE	Railway Sidings	1928	720342
P	341m NE	Railway Sidings	1908	780765
Q	341m NE	Unspecified Works	1976	678976
9	342m NE	Unspecified Works	1976	678975
R	343m S	Bus Station	1987 - 1992	697681
10	361m E	Unspecified Works	1976	678972
J	366m NW	Industrial House	1851	676228
R	367m S	Police Station	1968 - 1975	754183
Q	372m NE	Railway Building	1938	738135
Q	374m NE	Railway Building	1954 - 1967	707061
Q	375m NE	Railway Building	1908 - 1928	772682
T	377m S	Unspecified Commercial/Industrial	1891 - 1908	754865
T	377m S	Unspecified Mills	1928 - 1938	757037
12	378m SE	Woollen Mill	1851	671039
Q	398m E	Railway Building	1908 - 1938	694963
Q	399m E	Railway Building	1954 - 1967	735115
Q	410m E	Unspecified Depot	1976	668803
P	428m NE	Unspecified Pit	1938	690673
V	431m N	Railway Building	1938	697081
V	431m N	Railway Building	1949	745574



ID	Location	Land use	Dates present	Group ID
V	431m N	Railway Building	1908	730672
V	431m N	Railway Building	1928	782360
Q	432m E	Railway Station	1938	775687
Q	433m E	Railway Station	1891 - 1928	743293
15	433m E	Pump	1851	675583
Q	434m E	Railway Building	1967	670149
Q	434m E	Railway Station	1954	729947
Q	436m E	Railway Buildings	1908 - 1928	714019
Q	436m E	Railway Buildings	1938	751928
Q	437m E	Railway Buildings	1954	744858
W	440m NE	Unspecified Works	1967 - 1976	752956
X	441m N	Railway Sidings	1938	759617
16	441m S	Bus Station	1968	707675
X	442m NE	Railway Sidings	1928	783719
X	442m NE	Railway Sidings	1908	788701
17	443m S	Fire Engine	1851	681278
V	455m N	Cuttings	1908 - 1928	705232
Y	455m S	Butts	1928	702088
V	455m N	Cuttings	1975 - 1992	777653
V	456m N	Cuttings	1968	781396
V	456m N	Cuttings	1949	769318
V	458m N	Cuttings	1938	742252
V	460m N	Cuttings	1890	769145
Y	461m S	Butts	1949	728062
Q	464m E	Railway Building	1908	670133
18	468m NE	Cuttings	1908	642612
19	469m E	Sand Pit	1851	643878
Q	476m E	Railway Building	1908 - 1938	735298



ID	Location	Land use	Dates present	Group ID
20	478m N	Cotton Mill	1851	644265
21	478m SE	Tannery	1851	691826
22	480m SW	Refuse Heap	1851	677423
Q	486m NE	Refuse Heap	1928 - 1938	730677
Q	487m NE	Unspecified Works	1967	678974
Q	489m NE	Unspecified Depot	1976	668801
W	491m NE	Unspecified Ground Workings	1908	648007
W	495m NE	Unspecified Pit	1928 - 1938	732181
24	497m SW	Rope Walk	1851	641260

This data is sourced from Ordnance Survey / Groundsure.

1.2 Historical tanks

Records within 500m

7

Tank features digitised from historical Ordnance Survey mapping at high-detail 1:1,250 and 1:2,500 scale, intelligently grouped into contiguous features. To prevent misrepresentation of the size of historical features at any given time, features are only grouped if they have similar geometries within immediately preceding or succeeding map editions. See section 2 for a breakdown of grouping if required. Grouped and the original ungrouped features can be cross-referenced across sections 1 and 2 using the 'Group ID'.

Features are displayed on the Past land use map on **page 14**

ID	Location	Land use	Dates present	Group ID
G	149m SW	Unspecified Tank	1972	84182
K	248m SW	Unspecified Tank	1988	103744
K	249m SW	Unspecified Tank	1995	94496
M	290m SE	Unspecified Tank	1975	96099
M	290m SE	Unspecified Tank	1983 - 1984	94527
J	296m NW	Tanks	1982 - 1988	94504
J	296m NW	Tanks	1996	92338

This data is sourced from Ordnance Survey / Groundsure.



1.3 Historical energy features

Records within 500m
23

Energy features digitised from historical Ordnance Survey mapping at high-detail 1:1,250 and 1:2,500 scale, intelligently grouped into contiguous features. To prevent misrepresentation of the size of historical features at any given time, features are only grouped if they have similar geometries within immediately preceding or succeeding map editions. See section 2 for a breakdown of grouping if required. Grouped and the original ungrouped features can be cross-referenced across sections 1 and 2 using the 'Group ID'.

Features are displayed on the Past land use map on **page 14**

ID	Location	Land use	Dates present	Group ID
C	32m NW	Electricity Substation	1972 - 1995	47023
A	47m S	Electricity Substation	1988 - 1995	49782
C	57m NW	Electricity Substation	1988	58663
C	57m NW	Electricity Substation	1985 - 1995	52063
2	174m NW	Electricity Substation	1982	45432
I	263m NE	Electricity Substation	1987	52256
I	263m NE	Electricity Substation	1996	50531
I	263m NE	Electricity Substation	1976	55298
L	264m S	Electricity Substation	1988 - 1995	51119
L	268m S	Electricity Substation	1972 - 1985	47001
H	271m NE	Electricity Substation	1982 - 1996	49316
4	281m N	Electricity Substation	1982 - 1996	57572
J	281m NW	Electricity Substation	1982 - 1996	59270
6	315m W	Electricity Substation	1972 - 1990	54892
O	322m E	Electricity Substation	1983 - 1996	58298
O	322m E	Electricity Substation	1975 - 1989	49947
8	342m S	Electricity Substation	1972 - 1995	52697
13	419m SW	Electricity Substation	1972	45431
14	423m N	Electricity Substation	1982 - 1996	56064
Q	467m NE	Electricity Substation	1987 - 1996	48646
AA	476m W	Electricity Substation	1972	48634



ID	Location	Land use	Dates present	Group ID
AA	477m W	Electricity Substation	1985 - 1990	53072
23	485m S	Electricity Substation	1998	45430

This data is sourced from Ordnance Survey / Groundsure.

1.4 Historical petrol stations

Records within 500m

0

Petrol stations digitised from historical Ordnance Survey mapping at high-detail 1:1,250 and 1:2,500 scale, intelligently grouped into contiguous features. To prevent misrepresentation of the size of historical features at any given time, features are only grouped if they have similar geometries within immediately preceding or succeeding map editions. See section 2 for a breakdown of grouping if required. Grouped and the original ungrouped features can be cross-referenced across sections 1 and 2 using the 'Group ID'.

This data is sourced from Ordnance Survey / Groundsure.

1.5 Historical garages

Records within 500m

30

Garages digitised from historical Ordnance Survey mapping at high-detail 1:1,250 and 1:2,500 scale, intelligently grouped into contiguous features. To prevent misrepresentation of the size of historical features at any given time, features are only grouped if they have similar geometries within immediately preceding or succeeding map editions. See section 2 for a breakdown of grouping if required. Grouped and the original ungrouped features can be cross-referenced across sections 1 and 2 using the 'Group ID'.

Features are displayed on the Past land use map on **page 14**

ID	Location	Land use	Dates present	Group ID
1	56m NE	Garage	1982 - 1985	19290
D	83m N	Garage	1958 - 1959	17343
D	83m N	Garage	1982 - 1995	18975
D	83m N	Garage	1959	17012
D	87m N	Garage	1959 - 1985	19479
F	174m N	Garage	1988 - 1996	18167
3	175m NE	Garage	1985 - 1995	17319
F	202m N	Garage	1982	14943
N	298m SE	Garage	1985 - 1988	19618



ID	Location	Land use	Dates present	Group ID
N	330m SE	Garage	1995	18192
S	367m W	Garage	1967	15531
11	376m SE	Garage	1989 - 1996	19410
S	404m W	Garage	1959	16420
S	404m W	Garage	1959 - 1967	19003
U	410m E	Garage	1983 - 1984	19508
U	413m E	Garage	1993 - 1996	17734
U	413m E	Garage	1975 - 1989	18688
Q	436m E	Garage	1996	15596
Q	439m E	Garage	1996	16964
Q	439m E	Garage	1993	19287
Q	457m E	Garage	1989	15989
Z	461m SE	Garage Works	1983 - 1984	17868
Z	464m SE	Garage Works	1975	15382
Q	470m E	Garage	1996	15003
Q	476m E	Garage	1996	17026
Q	479m E	Garage	1983 - 1984	18765
Q	491m E	Garage	1989	15098
AB	493m SE	Garage	1957	15954
AB	494m SE	Garage	1957 - 1975	18151
AB	494m SE	Garage	1982	16436

This data is sourced from Ordnance Survey / Groundsure.

1.6 Historical military land

Records within 500m


0

Areas of military land digitised from multiple sources including the National Archives, local records, MOD records and verified other sources, intelligently grouped into contiguous features.

This data is sourced from Ordnance Survey / Groundsure / other sources.



2 Past land use - un-grouped



- Site Outline
- Search buffers in metres (m)
- Historical industrial land uses
- Historical tanks
- Historical energy features
- Historical garages

2.1 Historical industrial land uses

Records within 500m

127

Potentially contaminative land use features digitised from historical Ordnance Survey mapping at 1:10,000 and 10,560 scale. Any records shown are available intelligently grouped in section 1. Grouped and the original un-grouped features can be cross-referenced across sections 1 and 2 using the 'Group ID'.

Features are displayed on the Past land use - un-grouped map on **page 22**

ID	Location	Land Use	Date	Group ID
A	On site	Unspecified Works	1987	695987
A	On site	Unspecified Works	1975	695987
B	23m E	Unspecified Mills	1949	774364



ID	Location	Land Use	Date	Group ID
B	24m E	Unspecified Mills	1938	736780
B	24m E	Unspecified Commercial/Industrial	1891	764450
B	25m E	Unspecified Mill	1975	657139
B	26m E	Unspecified Commercial/Industrial	1968	764683
B	27m E	Cotton Mills	1851	659337
B	28m E	Unspecified Mills	1928	783932
B	28m E	Unspecified Mills	1908	783932
A	31m S	Unspecified Works	1992	724497
B	50m E	Unspecified Commercial/Industrial	1992	716726
B	50m E	Unspecified Commercial/Industrial	1987	716726
B	75m E	Chimney	1975	744807
B	75m E	Chimney	1968	744807
B	123m E	Pump	1851	675569
F	123m N	Woollen Mill	1851	670985
G	130m N	Unspecified Mills	1949	789838
G	130m N	Unspecified Commercial/Industrial	1968	757307
G	131m N	Unspecified Commercial/Industrial	1987	706201
G	131m N	Unspecified Commercial/Industrial	1975	706201
G	132m N	Unspecified Mills	1938	706053
G	132m N	Unspecified Commercial/Industrial	1928	753030
G	132m N	Unspecified Commercial/Industrial	1908	753030
G	132m N	Unspecified Commercial/Industrial	1891	753030
E	143m NW	Pump	1851	675568
G	143m N	Unspecified Mills	1992	746909
H	145m SW	Chimney	1968	684526
F	155m N	Clay Pit	1851	676030
E	168m N	Ambulance Station	1992	676098
J	186m NE	Corporation Depot	1891	685836



ID	Location	Land Use	Date	Group ID
G	217m N	Rope Walk	1851	641256
K	224m NE	Unspecified Mill	1976	657138
G	235m N	Shed	1851	659581
L	240m NW	Infirmery	1992	707060
L	240m NW	Infirmery	1987	707060
L	264m NW	Infirmery	1975	724787
L	264m NW	Infirmery	1949	701004
L	264m NW	Infirmery	1968	745287
L	265m NW	Infirmery And Dispensary	1938	706331
L	265m NW	Infirmery And Dispensary	1928	706331
L	265m NW	Infirmery And Dispensary	1908	706331
2	290m NE	Unspecified Depot	1992	668799
L	332m NW	Infirmery And Dispensary	1891	709310
3	339m NE	Railway Sidings	1891	693892
T	339m NE	Railway Sidings	1938	751485
T	340m NE	Railway Sidings	1954	778967
T	341m NE	Railway Sidings	1928	720342
T	341m NE	Railway Sidings	1908	780765
U	341m NE	Unspecified Works	1976	678976
T	342m NE	Unspecified Works	1976	678975
W	343m S	Bus Station	1992	697681
W	343m S	Bus Station	1987	697681
4	361m E	Unspecified Works	1976	678972
L	366m NW	Industrial House	1851	676228
W	367m S	Police Station	1975	754183
T	368m NE	Railway Sidings	1967	751485
W	370m S	Police Station	1968	754183
U	372m NE	Railway Building	1938	738135



ID	Location	Land Use	Date	Group ID
Y	373m NE	Railway Sidings	1949	778967
U	374m NE	Railway Building	1967	707061
U	374m NE	Railway Building	1954	707061
U	375m NE	Railway Building	1928	772682
U	375m NE	Railway Building	1908	772682
AA	377m S	Unspecified Mills	1938	757037
AA	377m S	Unspecified Mills	1928	757037
AA	377m S	Unspecified Commercial/Industrial	1908	754865
AA	377m S	Unspecified Commercial/Industrial	1891	754865
Y	378m NE	Railway Sidings	1968	751485
5	378m SE	Woollen Mill	1851	671039
U	398m E	Railway Building	1938	694963
U	399m E	Railway Building	1928	694963
U	399m E	Railway Building	1908	694963
U	399m E	Railway Building	1967	735115
U	399m E	Railway Building	1954	735115
U	410m E	Unspecified Depot	1976	668803
7	428m NE	Unspecified Pit	1938	690673
Y	431m N	Railway Building	1938	697081
Y	431m N	Railway Building	1949	745574
Y	431m N	Railway Building	1928	782360
Y	431m N	Railway Building	1908	730672
U	432m E	Railway Station	1938	775687
U	433m E	Railway Station	1928	743293
U	433m E	Railway Station	1908	743293
U	433m E	Railway Station	1891	743293
8	433m E	Pump	1851	675583
U	434m E	Railway Building	1967	670149



ID	Location	Land Use	Date	Group ID
U	434m E	Railway Station	1954	729947
U	436m E	Railway Buildings	1928	714019
U	436m E	Railway Buildings	1908	714019
U	436m E	Railway Buildings	1938	751928
U	437m E	Railway Buildings	1954	744858
AD	440m NE	Unspecified Works	1976	752956
AD	440m NE	Unspecified Works	1967	752956
Y	441m N	Railway Sidings	1938	759617
9	441m S	Bus Station	1968	707675
Y	442m NE	Railway Sidings	1928	783719
Y	442m NE	Railway Sidings	1908	788701
10	443m S	Fire Engine	1851	681278
Y	455m N	Cuttings	1928	705232
Y	455m N	Cuttings	1908	705232
AE	455m S	Butts	1928	702088
Y	455m N	Cuttings	1992	777653
Y	455m N	Cuttings	1987	777653
Y	455m N	Cuttings	1975	777653
Y	456m N	Cuttings	1968	781396
Y	456m N	Cuttings	1949	769318
Y	458m N	Cuttings	1938	742252
Y	460m N	Cuttings	1890	769145
AE	461m S	Butts	1949	728062
U	464m E	Railway Building	1908	670133
11	468m NE	Cuttings	1908	642612
12	469m E	Sand Pit	1851	643878
U	476m E	Railway Building	1938	735298
13	478m N	Cotton Mill	1851	644265



ID	Location	Land Use	Date	Group ID
14	478m SE	Tannery	1851	691826
U	479m E	Railway Building	1928	735298
U	479m E	Railway Building	1908	735298
15	480m SW	Refuse Heap	1851	677423
U	486m NE	Refuse Heap	1938	730677
U	486m NE	Refuse Heap	1928	730677
U	487m NE	Unspecified Works	1967	678974
U	489m NE	Unspecified Depot	1976	668801
AD	491m NE	Unspecified Ground Workings	1908	648007
AD	495m NE	Unspecified Pit	1938	732181
AD	497m NE	Unspecified Pit	1928	732181
17	497m SW	Rope Walk	1851	641260

This data is sourced from Ordnance Survey / Groundsure.

2.2 Historical tanks

Records within 500m

10

Tank features digitised from historical Ordnance Survey mapping at high-detail 1:1,250 and 1:2,500 scale. Any records shown are available intelligently grouped in section 1. Grouped and the original un-grouped features can be cross-referenced across sections 1 and 2 using the 'Group ID'.

Features are displayed on the Past land use - un-grouped map on **page 22**

ID	Location	Land Use	Date	Group ID
H	149m SW	Unspecified Tank	1972	84182
M	248m SW	Unspecified Tank	1988	103744
M	249m SW	Unspecified Tank	1995	94496
M	249m SW	Unspecified Tank	1995	94496
P	290m SE	Unspecified Tank	1975	96099
P	290m SE	Unspecified Tank	1984	94527
P	290m SE	Unspecified Tank	1983	94527
L	296m NW	Tanks	1982	94504



ID	Location	Land Use	Date	Group ID
L	296m NW	Tanks	1996	92338
L	296m NW	Tanks	1988	94504

This data is sourced from Ordnance Survey / Groundsure.

2.3 Historical energy features

Records within 500m

54

Energy features digitised from historical Ordnance Survey mapping at high-detail 1:1,250 and 1:2,500 scale. Any records shown are available intelligently grouped in section 1. Grouped and the original un-grouped features can be cross-referenced across sections 1 and 2 using the 'Group ID'.

Features are displayed on the Past land use - un-grouped map on **page 22**

ID	Location	Land Use	Date	Group ID
C	32m NW	Electricity Substation	1995	47023
C	32m NW	Electricity Substation	1995	47023
C	32m NW	Electricity Substation	1988	47023
C	32m NW	Electricity Substation	1985	47023
C	32m NW	Electricity Substation	1972	47023
A	47m S	Electricity Substation	1988	49782
A	48m S	Electricity Substation	1995	49782
A	48m S	Electricity Substation	1995	49782
C	57m NW	Electricity Substation	1988	58663
C	57m NW	Electricity Substation	1995	52063
C	57m NW	Electricity Substation	1995	52063
C	57m NW	Electricity Substation	1985	52063
1	174m NW	Electricity Substation	1982	45432
K	263m NE	Electricity Substation	1987	52256
K	263m NE	Electricity Substation	1996	50531
K	263m NE	Electricity Substation	1976	55298
N	264m S	Electricity Substation	1988	51119
N	264m S	Electricity Substation	1995	51119



ID	Location	Land Use	Date	Group ID
N	264m S	Electricity Substation	1995	51119
N	268m S	Electricity Substation	1985	47001
N	268m S	Electricity Substation	1972	47001
J	271m NE	Electricity Substation	1988	49316
J	271m NE	Electricity Substation	1982	49316
J	272m NE	Electricity Substation	1996	49316
O	281m N	Electricity Substation	1982	57572
L	281m NW	Electricity Substation	1996	59270
O	281m N	Electricity Substation	1988	57572
L	281m NW	Electricity Substation	1982	59270
L	281m NW	Electricity Substation	1988	59270
O	281m N	Electricity Substation	1996	57572
R	315m W	Electricity Substation	1972	54892
R	316m W	Electricity Substation	1985	54892
R	316m W	Electricity Substation	1990	54892
S	322m E	Electricity Substation	1984	58298
S	322m E	Electricity Substation	1983	58298
S	322m E	Electricity Substation	1975	49947
S	322m E	Electricity Substation	1989	49947
S	323m E	Electricity Substation	1996	58298
S	323m E	Electricity Substation	1993	58298
V	342m S	Electricity Substation	1988	52697
V	342m S	Electricity Substation	1985	52697
V	342m S	Electricity Substation	1972	52697
V	343m S	Electricity Substation	1995	52697
V	343m S	Electricity Substation	1995	52697
6	419m SW	Electricity Substation	1972	45431
AC	423m N	Electricity Substation	1988	56064



ID	Location	Land Use	Date	Group ID
AC	424m N	Electricity Substation	1982	56064
AC	424m N	Electricity Substation	1996	56064
U	467m NE	Electricity Substation	1987	48646
U	468m NE	Electricity Substation	1996	48646
AG	476m W	Electricity Substation	1972	48634
AG	477m W	Electricity Substation	1985	53072
AG	477m W	Electricity Substation	1990	53072
16	485m S	Electricity Substation	1998	45430

This data is sourced from Ordnance Survey / Groundsure.

2.4 Historical petrol stations

Records within 500m

0

Petrol stations digitised from historical Ordnance Survey mapping at high-detail 1:1,250 and 1:2,500 scale. Any records shown are available intelligently grouped in section 1. Grouped and the original un-grouped features can be cross-referenced across sections 1 and 2 using the 'Group ID'.

This data is sourced from Ordnance Survey / Groundsure.

2.5 Historical garages

Records within 500m

53

Garages digitised from historical Ordnance Survey mapping at high-detail 1:1,250 and 1:2,500 scale. Any records shown are available intelligently grouped in section 1. Grouped and the original un-grouped features can be cross-referenced across sections 1 and 2 using the 'Group ID'.

Features are displayed on the Past land use - un-grouped map on **page 22**

ID	Location	Land Use	Date	Group ID
D	56m NE	Garage	1985	19290
D	77m NE	Garage	1982	19290
E	83m N	Garage	1982	18975
E	83m N	Garage	1958	17343
E	83m N	Garage	1959	17343



ID	Location	Land Use	Date	Group ID
E	83m N	Garage	1959	17012
E	84m N	Garage	1995	18975
E	84m N	Garage	1995	18975
E	86m N	Garage	1988	18975
E	87m N	Garage	1959	19479
E	87m N	Garage	1985	19479
E	87m N	Garage	1972	19479
G	174m N	Garage	1996	18167
I	175m NE	Garage	1985	17319
I	175m NE	Garage	1995	17319
I	175m NE	Garage	1995	17319
I	176m NE	Garage	1988	17319
G	185m N	Garage	1988	18167
G	202m N	Garage	1982	14943
Q	298m SE	Garage	1985	19618
Q	298m SE	Garage	1988	19618
Q	330m SE	Garage	1995	18192
Q	330m SE	Garage	1995	18192
X	367m W	Garage	1967	15531
Z	376m SE	Garage	1989	19410
Z	376m SE	Garage	1996	19410
Z	376m SE	Garage	1993	19410
X	404m W	Garage	1959	16420
X	404m W	Garage	1959	19003
X	404m W	Garage	1967	19003
AB	410m E	Garage	1984	19508
AB	410m E	Garage	1983	19508
AB	413m E	Garage	1996	17734




ID	Location	Land Use	Date	Group ID
AB	413m E	Garage	1993	17734
AB	413m E	Garage	1975	18688
AB	413m E	Garage	1989	18688
U	436m E	Garage	1996	15596
U	439m E	Garage	1996	16964
U	439m E	Garage	1993	19287
U	457m E	Garage	1989	15989
AF	461m SE	Garage Works	1984	17868
AF	461m SE	Garage Works	1983	17868
AF	464m SE	Garage Works	1975	15382
U	470m E	Garage	1996	15003
U	470m E	Garage	1993	19287
U	476m E	Garage	1996	17026
U	479m E	Garage	1984	18765
U	479m E	Garage	1983	18765
U	491m E	Garage	1989	15098
AH	493m SE	Garage	1957	15954
AH	494m SE	Garage	1957	18151
AH	494m SE	Garage	1975	18151
AH	494m SE	Garage	1982	16436

This data is sourced from Ordnance Survey / Groundsure.



3 Waste and landfill



- Site Outline
- Search buffers in metres (m)
- Historical landfill (EA/NRW)
- Historical waste sites
- Licensed waste sites
- Waste exemptions

3.1 Active or recent landfill

Records within 500m

0

Active or recently closed landfill sites under Environment Agency/Natural Resources Wales regulation.

This data is sourced from the Environment Agency and Natural Resources Wales.

3.2 Historical landfill (BGS records)

Records within 500m

0

Landfill sites identified on a survey carried out on behalf of the DoE in 1973. These sites may have been closed or operational at this time.

This data is sourced from the British Geological Survey.



3.3 Historical landfill (LA/mapping records)

Records within 500m

0

Landfill sites identified from Local Authority records and high detail historical mapping.

This data is sourced from the Ordnance Survey/Groundsure and Local Authority records.

3.4 Historical landfill (EA/NRW records)

Records within 500m

2

Known historical (closed) landfill sites (e.g. sites where there is no PPC permit or waste management licence currently in force). This includes sites that existed before the waste licensing regime and sites that have been licensed in the past but where a licence has been revoked, ceased to exist or surrendered and a certificate of completion has been issued.

Features are displayed on the Waste and landfill map on **page 33**

ID	Location	Details		
3	351m NE	Site Address: Carrex Metals Limited, Regent Street, Rochdale, Greater Manchester Licence Holder Address: -	Waste Licence: - Site Reference: D085 Waste Type: - Environmental Permitting Regulations (Waste) Reference: - Licence Issue: - Licence Surrender: -	Operator: - Licence Holder: - First Recorded: - Last Recorded: -
5	453m N	Site Address: Disused Railway cutting between, Taylor Street and Greenbank Road, Rochdale Licence Holder Address: Rochdale MBC, Telegraph House, Baillie Street, Rochdale	Waste Licence: Yes Site Reference: D086, RD/LIC/504/88 Waste Type: Inert Environmental Permitting Regulations (Waste) Reference: - Licence Issue: 20/04/1988 Licence Surrender: -	Operator: - Licence Holder: Rochdale Borough Planning and Estates Officer First Recorded 30/04/1988 Last Recorded: 31/10/1988

This data is sourced from the Environment Agency and Natural Resources Wales.

3.5 Historical waste sites

Records within 500m

12

Waste site records derived from Local Authority planning records and high detail historical mapping.

Features are displayed on the Waste and landfill map on **page 33**



ID	Location	Address	Further Details	Date
F	337m NE	Site Address: N/A	Type of Site: Scrap Yard Planning application reference: N/A Description: N/A Data source: Historic Mapping Data Type: Polygon	1987
F	337m NE	Site Address: N/A	Type of Site: Scrap Yard Planning application reference: N/A Description: N/A Data source: Historic Mapping Data Type: Polygon	1996
F	367m NE	Site Address: Taylor Street, ROCHDALE, Greater Manchester, OL12 0	Type of Site: Waste Transfer Station Planning application reference: D29276 Description: Scheme includes perimeter screen fencing & concrete hardstanding with reduction of level of part of site. Portable messroom included. An application (ref: D29276) for Detailed Planning permission was submitted to Rochdale B.C. on 15th January 1993. Data source: Historic Planning Application Data Type: Point	-
H	372m NE	Site Address: N/A	Type of Site: Scrap Yard Planning application reference: N/A Description: N/A Data source: Historic Mapping Data Type: Polygon	1988
H	373m NE	Site Address: N/A	Type of Site: Scrap Yard Planning application reference: N/A Description: N/A Data source: Historic Mapping Data Type: Polygon	1981
H	373m NE	Site Address: N/A	Type of Site: Scrap Yard Planning application reference: N/A Description: N/A Data source: Historic Mapping Data Type: Polygon	1996
K	441m NE	Site Address: Topline House, 1, Lawton Street, ROCHDALE, Greater Manchester, OL12 0LQ	Type of Site: Recycling Unit (Conversion) Planning application reference: 11/D54898 Description: Scheme comprises change of use to non ferrous & ferrous metal reclaimers & processors, including construction of 1500mm high external storage area for waste tank. An application (ref: 11/D54898) for detailed planning permission was granted by Rochdale B. C. A detailed planning application has been granted. Data source: Historic Planning Application Data Type: Point	07/04/2012



ID	Location	Address	Further Details	Date
K	484m NE	Site Address: N/A	Type of Site: Scrap Yard Planning application reference: N/A Description: N/A Data source: Historic Mapping Data Type: Polygon	1987
K	485m NE	Site Address: N/A	Type of Site: Scrap Yard Planning application reference: N/A Description: N/A Data source: Historic Mapping Data Type: Polygon	1996
K	485m NE	Site Address: Eagle Works, Rugby Road, ROCHDALE, Greater Manchester, OL12 0D	Type of Site: Waste Transfer Station Planning application reference: 03/D41914 Description: Scheme comprises of a waste transfer station. An application (ref: 03/D41914) for Detailed Planning permission was submitted to Rochdale B.C. on 4th July 2003. Data source: Historic Planning Application Data Type: Point	-
K	491m E	Site Address: N/A	Type of Site: Scrap Yard Planning application reference: N/A Description: N/A Data source: Historic Mapping Data Type: Polygon	1987
K	492m E	Site Address: N/A	Type of Site: Scrap Yard Planning application reference: N/A Description: N/A Data source: Historic Mapping Data Type: Polygon	1996

This data is sourced from Ordnance Survey/Groundsure and Local Authority records.

3.6 Licensed waste sites

Records within 500m

16

Active or recently closed waste sites under Environment Agency/Natural Resources Wales regulation.

Features are displayed on the Waste and landfill map on **page 33**



ID	Location	Details		
C	275m NE	Site Name: Princess Street Depot Site Address: Highways And Maintenance Unit, Princess Street, Rochdale, Lancashire, OL12 0HA Correspondence Address: Highways And Maintenance Unit, Princess Street Depot, Rochdale, Lancashire, OL12 0HA	Type of Site: Transfer Station taking Non-Biodegradable Wastes Size: 25000 tonnes Environmental Permitting Regulations (Waste) Licence Number: MC001 EPR reference: - Operator: Alfred Mc Alpine Construction Ltd Waste Management licence No: 50089 Annual Tonnage: 24999	Issue Date: 31/07/2002 Effective Date: - Modified: - Surrendered Date: - Expiry Date: - Cancelled Date: - Status: Issued
C	275m NE	Site Name: Princess Street Depot Site Address: Highways And Maintenance Unit, Princess Street, Rochdale, Lancashire, OL12 0HA Correspondence Address: Highways And Maintenance Unit, Princess Street Depot, Rochdale, Lancashire, OL12 0HA	Type of Site: Transfer Station taking Non-Biodegradable Wastes Size: 25000 tonnes Environmental Permitting Regulations (Waste) Licence Number: MC001 EPR reference: - Operator: Alfred Mc Alpine Government Services Ltd Waste Management licence No: 50089 Annual Tonnage: 24999	Issue Date: 31/07/2002 Effective Date: - Modified: - Surrendered Date: - Expiry Date: - Cancelled Date: - Status: Issued
C	275m NE	Site Name: Princess Street Depot Site Address: Highways And Maintenance Unit, Princess Street, Rochdale, Lancashire, OL12 0HA Correspondence Address: Mr Nigel Dyer, Highways And Maintenance Unit, Princess Street Depot, Rochdale, Lancashire, OL12 0HA	Type of Site: Transfer Station taking Non-Biodegradable Wastes Size: 25000 tonnes Environmental Permitting Regulations (Waste) Licence Number: MC001 EPR reference: - Operator: Alfred Mc Alpine Construction Ltd Waste Management licence No: 50089 Annual Tonnage: 24999	Issue Date: 31/07/2002 Effective Date: - Modified: - Surrendered Date: - Expiry Date: - Cancelled Date: - Status: Issued



ID	Location	Details		
C	275m NE	Site Name: Rochdale Depot Site Address: Rochdale Depot, Princess Street, Rochdale, Lancashire, OL12 0HA Correspondence Address: -	Type of Site: Household, Commercial & Industrial Waste T Stn Size: 25000 tonnes Environmental Permitting Regulations (Waste) Licence Number: BAL161 EPR reference: EA/EPR/AB3006UT/T001 Operator: Balfour Beatty Living Places Limited Waste Management licence No: 50089 Annual Tonnage: 24999	Issue Date: 31/07/2002 Effective Date: 11/12/2013 Modified: 31/01/2008 Surrendered Date: - Expiry Date: - Cancelled Date: - Status: Transferred
C	275m NE	Site Name: Princess Street Depot Site Address: Princess Street Depot, Princess Street, Rochdale, Lancashire, OL12 0HA Correspondence Address: -	Type of Site: Household, Commercial & Industrial Waste T Stn Size: 25000 tonnes Environmental Permitting Regulations (Waste) Licence Number: BAL081 EPR reference: EA/EPR/FP3298VC/T001 Operator: Balfour Beatty Workplace Ltd Waste Management licence No: 50089 Annual Tonnage: 24999	Issue Date: 31/07/2002 Effective Date: 31/12/2009 Modified: 31/01/2008 Surrendered Date: - Expiry Date: - Cancelled Date: - Status: Transferred
C	275m NE	Site Name: Princess Street Depot Site Address: Highways And Maintenance Unit, Princess Street, Rochdale, Lancashire, OL12 0HA Correspondence Address: -	Type of Site: Household, Commercial & Industrial Waste T Stn Size: 25000 tonnes Environmental Permitting Regulations (Waste) Licence Number: MC001 EPR reference: - Operator: Alfred Mc Alpine Government Services Ltd Waste Management licence No: 50089 Annual Tonnage: 0	Issue Date: 31/07/2002 Effective Date: - Modified: 31/01/2008 Surrendered Date: - Expiry Date: - Cancelled Date: - Status: Modified



ID	Location	Details		
C	275m NE	Site Name: Rochdale Depot Site Address: Rochdale Depot, Princess Street, Rochdale, Lancashire, OL12 0HA Correspondence Address: -	Type of Site: Household, Commercial & Industrial Waste T Stn Size: 25000 tonnes Environmental Permitting Regulations (Waste) Licence Number: BAL161 EPR reference: EA/EPR/AB3006UT/T001 Operator: Balfour Beatty Living Places Ltd Waste Management licence No: 50089 Annual Tonnage: 24999	Issue Date: 31/07/2002 Effective Date: 11/12/2013 Modified: 31/01/2008 Surrendered Date: - Expiry Date: - Cancelled Date: - Status: Transferred
F	364m NE	Site Name: Regent Street Transfer Station L Site Address: Land/premises At, Regent Street, Rochdale, Lancashire, OL12 0HQ Correspondence Address: -	Type of Site: Household, Commercial & Industrial Waste T Stn Size: 25000 tonnes Environmental Permitting Regulations (Waste) Licence Number: CAS003 EPR reference: EA/EPR/TP3496CG/T003 Operator: P Casey Enviro Ltd Waste Management licence No: 53747 Annual Tonnage: 6250	Issue Date: 24/12/1991 Effective Date: 22/04/2004 Modified: 28/09/2001 Surrendered Date: - Expiry Date: - Cancelled Date: - Status: Transferred
F	364m NE	Site Name: Regent Street Transfer Station L Site Address: Land/premises At, Regent Street, Rochdale, Lancashire, OL12 0HQ Correspondence Address: -	Type of Site: Household, Commercial & Industrial Waste T Stn Size: >= 25000 tonnes 75000 tonnes Environmental Permitting Regulations (Waste) Licence Number: CAS003 EPR reference: EA/EPR/TP3496CG/T003 Operator: P Casey Enviro Ltd Waste Management licence No: 53747 Annual Tonnage: 6250	Issue Date: 24/12/1991 Effective Date: 22/04/2004 Modified: 28/09/2001 Surrendered Date: - Expiry Date: - Cancelled Date: - Status: Transferred



ID	Location	Details		
J	462m E	Site Name: C A R. I. P Limited Site Address: 3, Jermyn Street, Rochdale, Manchester, Lancashire, OL12 0DP Correspondence Address: 21, Lichfield Terrace, Rochdale, Manchester, OL16 4XL	Type of Site: Metal Recycling Site (Vehicle Dismantler) Size: 25000 tonnes Environmental Permitting Regulations (Waste) Licence Number: CAR011 EPR reference: - Operator: Car. I. P. Ltd Waste Management licence No: 50467 Annual Tonnage: 0	Issue Date: 04/09/2006 Effective Date: - Modified: - Surrendered Date: - Expiry Date: - Cancelled Date: - Status: Issued
J	462m E	Site Name: C A R. I. P Limited Site Address: 3, Jermyn Street, Rochdale, Manchester, OL12 0DP Correspondence Address: -	Type of Site: ELV Facility Size: 25000 tonnes Environmental Permitting Regulations (Waste) Licence Number: CAR011 EPR reference: EA/EPR/YP3694CC/A001 Operator: Car I P Ltd Waste Management licence No: 50467 Annual Tonnage: 2500	Issue Date: 04/09/2006 Effective Date: - Modified: - Surrendered Date: - Expiry Date: - Cancelled Date: - Status: Issued
J	462m E	Site Name: CAR.I.P Limited Site Address: 3, Jermyn Street, Rochdale, Manchester, OL12 0DP Correspondence Address: -	Type of Site: ELV Facility Size: 25000 tonnes Environmental Permitting Regulations (Waste) Licence Number: CAR011 EPR reference: EA/EPR/YP3694CC/V002 Operator: CAR.I.P Limited Waste Management licence No: 50467 Annual Tonnage: 2500	Issue Date: 04/09/2006 Effective Date: - Modified: 19/09/2017 Surrendered Date: - Expiry Date: - Cancelled Date: - Status: Modified
J	462m E	Site Name: C A R. I. P Limited Site Address: 3, Jermyn Street, Rochdale, Manchester, OL12 0DP Correspondence Address: -	Type of Site: ELV Facility Size: 25000 tonnes Environmental Permitting Regulations (Waste) Licence Number: CAR011 EPR reference: EA/EPR/YP3694CC/A001 Operator: Car. I. P. Ltd Waste Management licence No: 50467 Annual Tonnage: 2500	Issue Date: 04/09/2006 Effective Date: - Modified: - Surrendered Date: - Expiry Date: - Cancelled Date: - Status: Issued



ID	Location	Details		
J	462m E	Site Name: C A R. I. P. Limited Site Address: 3, Jermyn Street, Rochdale, Manchester, OL12 0DP Correspondence Address: -	Type of Site: ELV Facility Size: 25000 tonnes Environmental Permitting Regulations (Waste) Licence Number: CAR011 EPR reference: EA/EPR/YP3694CC/V002 Operator: C A R. I. P. Limited Waste Management licence No: 50467 Annual Tonnage: 2500	Issue Date: 04/09/2006 Effective Date: - Modified: 19/09/2017 Surrendered Date: - Expiry Date: - Cancelled Date: - Status: Modified
7	480m N	Site Name: Regent Street Transfer Station Site Address: Regent Street, Rochdale, Lancashire, OL12 0HQ Correspondence Address: Lancashire House, 24, Winckley Square, Preston, Lancashire, PR1 3JJ	Type of Site: Household, Commercial & Industrial Waste T Stn Size: >= 25000 tonnes 75000 tonnes Environmental Permitting Regulations (Waste) Licence Number: LA001 EPR reference: - Operator: S I T A (Lancashire) Ltd Waste Management licence No: 53747 Annual Tonnage: 6250	Issue Date: 24/12/1991 Effective Date: 29/09/2001 Modified: 28/09/2001 Surrendered Date: - Expiry Date: - Cancelled Date: - Status: Modified
K	494m NE	Site Name: D Howarth Vehicle Dismantlers Site Address: 80, Rugby Road, Rochdale, Lancashire, OL12 0DY Correspondence Address: -	Type of Site: Metal Recycling Site (Vehicle Dismantler) Size: 25000 tonnes Environmental Permitting Regulations (Waste) Licence Number: DHO001 EPR reference: EA/EPR/HP3096CF/V002 Operator: Howarth Dennis Waste Management licence No: 53753 Annual Tonnage: 2100	Issue Date: 25/02/1994 Effective Date: - Modified: 31/03/2003 Surrendered Date: - Expiry Date: - Cancelled Date: - Status: Modified

This data is sourced from the Environment Agency and Natural Resources Wales.

3.7 Waste exemptions

Records within 500m

61

Activities involving the storage, treatment, use or disposal of waste that are exempt from needing a permit. Exemptions have specific limits and conditions that must be adhered to.

Features are displayed on the Waste and landfill map on **page 33**



ID	Location	Site	Reference	Category	Sub-Category	Description
1	98m N	48, WHITWORTH ROAD, ROCHDALE, OL12 0EZ	WEX227128	Treating waste exemption	Not on a farm	Sorting and de-naturing of controlled drugs for disposal
A	210m NE	Balfour Beatty Living Places Ltd, Princess Street Depot, Princess Street, Rochdale, OL12 0HA	WEX159308	Using waste exemption	Not on a Farm	Use of waste for a specified purpose
A	210m NE	Balfour Beatty Living Places Ltd, Princess Street Depot, Princess Street, Rochdale, OL12 0HA	WEX159308	Using waste exemption	Not on a Farm	Use of waste in construction
A	210m NE	Balfour Beatty Living Places Ltd, Princess Street Depot, Princess Street, Rochdale, OL12 0HA	WEX159308	Storing waste exemption	Not on a Farm	Storage of waste in secure containers
A	210m NE	Balfour Beatty Living Places Ltd, Princess Street Depot, Princess Street, Rochdale, OL12 0HA	WEX159308	Storing waste exemption	Not on a Farm	Storage of waste in a secure place
A	222m NE	BBLP Princess Street Depot Princess Street OL12 0HA	EPR/XF0006V N/A001	Storing waste exemption	Non-Agricultural Waste Only	Storage of waste in secure containers
A	222m NE	BBLP Princess Street Depot Princess Street OL12 0HA	EPR/XF0006V N/A001	Storing waste exemption	Non-Agricultural Waste Only	Storage of waste in a secure place
A	222m NE	BBLP Princess Street Depot Princess Street OL12 0HA	EPR/XF0006V N/A001	Using waste exemption	Non-Agricultural Waste Only	Use of waste in construction
A	222m NE	BBLP Princess Street Depot Princess Street OL12 0HA	EPR/XF0006V N/A001	Using waste exemption	Non-Agricultural Waste Only	Use of waste for a specified purpose
B	243m S	79, YORKSHIRE STREET, ROCHDALE, OL16 1DB	WEX156666	Treating waste exemption	Not on a Farm	Sorting and de-naturing of controlled drugs for disposal
B	248m S	79 Yorkshire Street Rochdale Rochdale OL16 1DB	EPR/PF0300H H/A001	Treating waste exemption	Non-Agricultural Waste Only	Sorting and de-naturing of controlled drugs for disposal
B	249m S	Rochdale Pharmacy, 79 Yorkshire St, Rochdale, OL16 1DB	WEX074442	Treating waste exemption	Not on a farm	Sorting and de-naturing of controlled drugs for disposal
2	290m SE	Arien House John Street Rochdale OL16 2HP	EA/EPR/VP375 5EF/A001	Treating waste exemption	Non-Agricultural Waste Only	Repair or refurbishment of WEEE
D	305m SE	-	WEX253596	Using waste exemption	Not on a farm	Use of waste in construction



ID	Location	Site	Reference	Category	Sub-Category	Description
D	305m SE	-	WEX253596	Treating waste exemption	Not on a farm	Screening and blending of waste
E	315m E	PIONEER HOUSE, REGENT STREET, ROCHDALE, OL12 0HQ	WEX321341	Treating waste exemption	Not on a Farm	Treatment of waste toner cartridges by sorting, dismantling, cleaning or refilling
E	315m E	PIONEER HOUSE, REGENT STREET, ROCHDALE, OL12 0HQ	WEX254255	Treating waste exemption	Not on a farm	Treatment of waste toner cartridges by sorting, dismantling, cleaning or refilling
E	315m E	PIONEER HOUSE, REGENT STREET, ROCHDALE, OL12 0HQ	WEX254255	Storing waste exemption	Not on a farm	Storage of waste in a secure place
E	315m E	PIONEER HOUSE, REGENT STREET, ROCHDALE, OL12 0HQ	WEX194890	Treating waste exemption	Not on a farm	Treatment of waste toner cartridges by sorting, dismantling, cleaning or refilling
E	315m E	PIONEER HOUSE, REGENT STREET, ROCHDALE, OL12 0HQ	WEX113338	Storing waste exemption	Not on a farm	Storage of waste in a secure place
E	315m E	PIONEER HOUSE, REGENT STREET, ROCHDALE, OL12 0HQ	WEX113338	Treating waste exemption	Not on a farm	Treatment of waste toner cartridges by sorting, dismantling, cleaning or refilling
E	315m E	PIONEER HOUSE, REGENT STREET, ROCHDALE, OL12 0HQ	WEX031551	Treating waste exemption	Not on a farm	Treatment of waste toner cartridges by sorting, dismantling, cleaning or refilling
E	323m E	Pioneer House Regent Street ROCHDALE Lancashire OL12 0HQ	EPR/EH0276CE /A001	Treating waste exemption	Non-Agricultural Waste Only	Treatment of waste toner cartridges by sorting, dismantling, cleaning or refilling
D	338m SE	-	WEX283043	Using waste exemption	Not on a farm	Use of waste in construction
G	353m W	-	WEX249707	Treating waste exemption	Not on a farm	Screening and blending of waste
G	353m W	-	WEX249707	Using waste exemption	Not on a farm	Use of waste in construction
4	379m E	Unit 3 Jermyn Street ROCHDALE Lancashire OL12 0DP	EPR/CE5088VK /A001	Treating waste exemption	Non-Agricultural Waste Only	Recovery of scrap metal



ID	Location	Site	Reference	Category	Sub-Category	Description
I	391m NW	WHITEHALL STREET, ROCHDALE, OL12 0NB	WEX219682	Treating waste exemption	Not on a farm	Sorting and de-naturing of controlled drugs for disposal
I	391m NW	WHITEHALL STREET, ROCHDALE, OL12 0NB	WEX223016	Treating waste exemption	Not on a farm	Sorting and de-naturing of controlled drugs for disposal
I	391m NW	WHITEHALL STREET, ROCHDALE, OL12 0NB	WEX074492	Treating waste exemption	Not on a farm	Sorting and de-naturing of controlled drugs for disposal
I	391m NW	Rochdale Infirmary, WHITEHALL STREET, ROCHDALE, OL12 0NB	WEX076565	Treating waste exemption	Not on a farm	Sorting and de-naturing of controlled drugs for disposal
I	393m NW	Rochdale Infirmary Whitehall Street Rochdale Lancashire OL12 0NB	EPR/TF0130NR /A001	Treating waste exemption	Non-Agricultural Waste Only	Sorting and de-naturing of controlled drugs for disposal
J	421m E	A & A COMPLEX, UNIT 4, LAWTON STREET, ROCHDALE, OL12 0LQ	WEX283159	Treating waste exemption	Not on a Farm	Preparatory treatments (baling, sorting, shredding etc)
J	421m E	A & A COMPLEX, UNIT 4, LAWTON STREET, ROCHDALE, OL12 0LQ	WEX283159	Treating waste exemption	Not on a farm	Sorting mixed waste
J	421m E	Qu Part, Yard 1, A&A Complex, Rochdale, ol120lq	WEX235179	Using waste exemption	Not on a farm	Use of depolluted end-of- life vehicles for vehicle parts
J	421m E	A & A COMPLEX, UNIT 4, LAWTON STREET, ROCHDALE, OL12 0LQ	WEX142637	Treating waste exemption	Not on a farm	Sorting mixed waste
J	421m E	A & A COMPLEX, UNIT 4, LAWTON STREET, ROCHDALE, OL12 0LQ	WEX142637	Treating waste exemption	Not on a farm	Preparatory treatments (baling, sorting, shredding etc)
J	422m E	Qu Part, Yard 1, A&A Complex, Rochdale, ol120lq	WEX090331	Using waste exemption	Not on a farm	Use of depolluted end-of- life vehicles for vehicle parts
J	445m E	Unit 1 A and A Complex Lawton Street ROCHDALE Lancashire OL12 0LQ	EPR/HF0800C G/A001	Treating waste exemption	Both agricultural and non-agricultural waste	Sorting mixed waste
J	445m E	Unit 1 A and A Complex Lawton Street ROCHDALE Lancashire OL12 0LQ	EPR/HF0800C G/A001	Treating waste exemption	Both agricultural and non-agricultural waste	Preparatory treatments (baling, sorting, shredding etc)



ID	Location	Site	Reference	Category	Sub-Category	Description
J	446m E	Unit 1 A and A Complex Lawton Street ROCHDALE Lancashire OL12 0LQ	EPR/BF0204CY /A001	Storing waste exemption	Non-Agricultural Waste Only	Storage of waste in secure containers
J	446m E	Unit 1 A and A Complex Lawton Street ROCHDALE Lancashire OL12 0LQ	EPR/BF0204CY /A001	Storing waste exemption	Non-Agricultural Waste Only	Storage of waste in a secure place
J	446m E	Unit 1 A and A Complex Lawton Street ROCHDALE Lancashire OL12 0LQ	EPR/BF0204CY /A001	Treating waste exemption	Non-Agricultural Waste Only	Sorting mixed waste
J	446m E	Unit 1 A and A Complex Lawton Street ROCHDALE Lancashire OL12 0LQ	EPR/BF0204CY /A001	Treating waste exemption	Non-Agricultural Waste Only	Preparatory treatments (baling, sorting, shredding etc)
J	446m E	Unit 1 A and A Complex Lawton Street ROCHDALE Lancashire OL12 0LQ	EPR/BF0204CY /A001	Treating waste exemption	Non-Agricultural Waste Only	Recovery of scrap metal
L	458m SW	LINEAR NETWORK - ROCHDALE	EPR/UF0907S M/A001	Disposing of waste exemption	Non-Agricultural Waste Only	Deposit of waste from dredging of inland waters
L	458m SW	LINEAR NETWORK - ROCHDALE	EPR/UF0907S M/A001	Using waste exemption	Non-Agricultural Waste Only	Use of waste in construction
J	468m E	UNIT 3, JERMYN STREET, ROCHDALE, OL12 0DP	WEX218147	Using waste exemption	Not on a farm	Use of depolluted end-of- life vehicles for vehicle parts
J	468m E	UNIT 3, JERMYN STREET, ROCHDALE, OL12 0DP	WEX218147	Treating waste exemption	Not on a farm	Recovery of scrap metal
J	468m E	UNIT 3, JERMYN STREET, ROCHDALE, OL12 0DP	WEX218147	Storing waste exemption	Not on a farm	Storage of waste in secure containers
J	468m E	UNIT 3, JERMYN STREET, ROCHDALE, OL12 0DP	WEX218147	Storing waste exemption	Not on a farm	Storage of waste in a secure place
J	468m E	UNIT 3, JERMYN STREET, ROCHDALE, OL12 0DP	WEX323208	Treating waste exemption	Not on a Farm	Recovery of scrap metal
J	468m E	UNIT 3, JERMYN STREET, ROCHDALE, OL12 0DP	WEX323208	Treating waste exemption	Not on a Farm	Preparatory treatments (baling, sorting, shredding etc)
J	468m E	UNIT 3, JERMYN STREET, ROCHDALE, OL12 0DP	WEX189381	Treating waste exemption	Not on a farm	Preparatory treatments (baling, sorting, shredding etc)
J	468m E	UNIT 3, JERMYN STREET, ROCHDALE, OL12 0DP	WEX189381	Treating waste exemption	Not on a farm	Recovery of scrap metal




ID	Location	Site	Reference	Category	Sub-Category	Description
J	468m E	UNIT 3, JERMYN STREET, ROCHDALE, OL12 0DP	WEX073188	Storing waste exemption	Not on a farm	Storage of waste in secure containers
J	468m E	UNIT 3, JERMYN STREET, ROCHDALE, OL12 0DP	WEX073188	Storing waste exemption	Not on a farm	Storage of waste in a secure place
J	468m E	UNIT 3, JERMYN STREET, ROCHDALE, OL12 0DP	WEX073188	Treating waste exemption	Not on a farm	Recovery of scrap metal
J	468m E	UNIT 3, JERMYN STREET, ROCHDALE, OL12 0DP	WEX073188	Using waste exemption	Not on a farm	Use of depolluted end-of- life vehicles for vehicle parts
J	468m E	UNIT 3, JERMYN STREET, ROCHDALE, OL12 0DP	WEX033235	Treating waste exemption	Not on a farm	Recovery of scrap metal
6	479m SE	Willmot Dixon Office, Off John Street, Rochdale, OL16 1YH	WEX159260	Using waste exemption	Not on a Farm	Use of waste in construction

This data is sourced from the Environment Agency and Natural Resources Wales.



4 Current industrial land use



- Site Outline
- Search buffers in metres (m)
- Recent industrial land uses
- △ Current or recent petrol stations
- Licensed pollutant release (Part A(2)/B)
- Licensed Discharges to controlled waters
- Pollution Incidents (EA/NRW)

4.1 Recent industrial land uses

Records within 250m

36

Current potentially contaminative industrial sites.

Features are displayed on the Current industrial land use map on **page 47**

ID	Location	Company	Address	Activity	Category
A	16m NE	Frank Key	27, Whitworth Road, Rochdale, Greater Manchester, OL12 0RA	Construction and Tool Hire	Hire Services
A	31m N	Boltons Textiles	Duke Street Mill, Duke Street, Rochdale, Greater Manchester, OL12 0LW	Textiles, Fabrics, Silk and Machinery	Industrial Products
A	31m N	Bolton Textiles	Duke Street Mill, Duke Street, Rochdale, Greater Manchester, OL12 0LW	Carpets, Flooring, Rugs and Soft Furnishings	Consumer Products



ID	Location	Company	Address	Activity	Category
A	35m N	Tri-cast Composite Tubes Ltd	Watson Works, Duke Street, Rochdale, Greater Manchester, OL12 0LT	Hobby, Sports and Pastime Products	Consumer Products
A	40m NW	Electricity Sub Station	Greater Manchester, OL12	Electrical Features	Infrastructure and Facilities
1	48m S	Electricity Sub Station	Greater Manchester, OL12	Electrical Features	Infrastructure and Facilities
A	64m NW	Electricity Sub Station	Greater Manchester, OL12	Electrical Features	Infrastructure and Facilities
A	78m NW	H Rothwell & Co Ltd	Duke Street, Rochdale, Greater Manchester, OL12 0LS	General Construction Supplies	Industrial Products
A	99m NW	Works	Greater Manchester, OL12	Unspecified Works Or Factories	Industrial Features
A	102m NW	Ringtag Internationa l	50, Whitehall Street, Rochdale, Greater Manchester, OL12 0LN	Textiles, Fabrics, Silk and Machinery	Industrial Products
A	103m N	Discount Clearance Centre	80, Howard Street, Rochdale, Greater Manchester, OL12 0LU	Distribution and Haulage	Transport, Storage and Delivery
A	105m NW	Duke Street Autopoint Ltd	Duke Street, Rochdale, Greater Manchester, OL12 0LT	Vehicle Repair, Testing and Servicing	Repair and Servicing
A	105m NW	Wren Prestige	Duke Street, Rochdale, Greater Manchester, OL12 0LT	New Vehicles	Motoring
A	123m N	Spring Court Auto Centre & Motorcycle Centre	Spring Court Autocare, Howard Street, Rochdale, Greater Manchester, OL12 0LU	Vehicle Repair, Testing and Servicing	Repair and Servicing
2	125m NE	Electricity Sub Station	Greater Manchester, OL12	Electrical Features	Infrastructure and Facilities
A	126m N	M O T Test & Repair Centre	70, Whitworth Road, Rochdale, Greater Manchester, OL12 0EZ	Vehicle Repair, Testing and Servicing	Repair and Servicing
A	126m N	The M O T & Repair Centre	70, Whitworth Road, Rochdale, Greater Manchester, OL12 0EZ	Vehicle Repair, Testing and Servicing	Repair and Servicing
A	134m NE	N R G Telecom Ltd	33, Princess Street, Rochdale, Greater Manchester, OL12 0HA	Radar and Telecommunications Equipment	Industrial Products



ID	Location	Company	Address	Activity	Category
3	142m E	Electricity Sub Station	Greater Manchester, OL12	Electrical Features	Infrastructure and Facilities
A	157m N	Kwik-Fit (GB) Limited	Whitworth Road, Rochdale, Greater Manchester, OL12 0QX	Vehicle Repair, Testing and Servicing	Repair and Servicing
4	170m S	T J Booth Associates	20a, Eastgate Street, Rochdale, Greater Manchester, OL16 1DH	Civil Engineers	Engineering Services
5	180m NE	Works	Greater Manchester, OL12	Unspecified Works Or Factories	Industrial Features
A	184m N	Saw Mills	Greater Manchester, OL12	Wood Products Including Charcoal, Paper, Card and Board	Industrial Products
C	191m NE	Works	Greater Manchester, OL12	Unspecified Works Or Factories	Industrial Features
6	192m NW	Rochdale Ambulance Station	Greater Manchester, OL12	Ambulance and Medical Transportation Services	Health Support Services
C	200m NE	Rochdale Re-tool Ltd	Unit 5e, Princess Street, Rochdale, Greater Manchester, OL12 0HA	Tools Including Machine Shops	Industrial Products
C	201m E	Works	Greater Manchester, OL12	Unspecified Works Or Factories	Industrial Features
C	206m NE	Burns Motor Works	Unit 1, Haynes Street, Rochdale, Greater Manchester, OL12 0UW	Vehicle Repair, Testing and Servicing	Repair and Servicing
C	210m NE	Isaac Butterworth Ltd	Units 2 and 3, Princess Street, Rochdale, Greater Manchester, OL12 0HA	Industrial Engineers	Engineering Services
7	216m SE	Rochdale Mobility	140, Yorkshire Street, Rochdale, Greater Manchester, OL16 1LD	Disability and Mobility Equipment	Consumer Products
B	216m S	Mobile Planet	7, Cheetham Street, Rochdale, Greater Manchester, OL16 1DG	Electrical Equipment Repair and Servicing	Repair and Servicing
C	227m NE	Motaquip	Unit 2, Haynes Street, Rochdale, Greater Manchester, OL12 0UW	Vehicle Parts and Accessories	Motoring
C	227m NE	Motaquip Autocentre	Unit 2, Haynes Street, Rochdale, Greater Manchester, OL12 0UW	Vehicle Repair, Testing and Servicing	Repair and Servicing
A	234m N	Anwar & Co Failsworth Service Station	111, Whitworth Road, Rochdale, Greater Manchester, OL12 0RA	Petrol and Fuel Stations	Road and Rail



ID	Location	Company	Address	Activity	Category
C	242m NE	Works	Greater Manchester, OL12	Unspecified Works Or Factories	Industrial Features
8	248m SW	E V M Sports & Prestige	Waterhouse Street, Rochdale, Greater Manchester, OL12 0AF	Secondhand Vehicles	Motoring

This data is sourced from Ordnance Survey.

4.2 Current or recent petrol stations

Records within 500m

2

Open, closed, under development and obsolete petrol stations.

Features are displayed on the Current industrial land use map on **page 47**

ID	Location	Company	Address	LPG	Status
A	210m N	GULF	111, Whitworth Road, Rochdale, Greater Manchester, OL12 0RA	No	Open
D	421m E	SHELL	278, Yorkshire Street, Rochdale, Greater Manchester, OL16 2DR	No	Open

This data is sourced from Experian.

4.3 Electricity cables

Records within 500m

0

High voltage underground electricity transmission cables.

This data is sourced from National Grid.

4.4 Gas pipelines

Records within 500m

0

High pressure underground gas transmission pipelines.

This data is sourced from National Grid.



4.5 Sites determined as Contaminated Land

Records within 500m**0**

Contaminated Land Register of sites designated under Part 2a of the Environmental Protection Act 1990.

This data is sourced from Local Authority records.

4.6 Control of Major Accident Hazards (COMAH)

Records within 500m**0**

Control of Major Accident Hazards (COMAH) sites. This data includes upper and lower tier sites, and includes a historical archive of COMAH sites and Notification of Installations Handling Hazardous Substances (NIHHS) records.

This data is sourced from the Health and Safety Executive.

4.7 Regulated explosive sites

Records within 500m**0**

Sites registered and licensed by the Health and Safety Executive under the Manufacture and Storage of Explosives Regulations 2005 (MSER). The last update to this data was in April 2011.

This data is sourced from the Health and Safety Executive.

4.8 Hazardous substance storage/usage

Records within 500m**0**

Consents granted for a site to hold certain quantities of hazardous substances at or above defined limits in accordance with the Planning (Hazardous Substances) Regulations 2015.

This data is sourced from Local Authority records.

4.9 Historical licensed industrial activities (IPC)

Records within 500m**0**

Integrated Pollution Control (IPC) records of substance releases to air, land and water. This data represents a historical archive as the IPC regime has been superseded.

This data is sourced from the Environment Agency and Natural Resources Wales.

4.10 Licensed industrial activities (Part A(1))

Records within 500m

0

Records of Part A(1) installations regulated under the Environmental Permitting (England and Wales) Regulations 2016 for the release of substances to the environment.

This data is sourced from the Environment Agency and Natural Resources Wales.

4.11 Licensed pollutant release (Part A(2)/B)

Records within 500m

4

Records of Part A(2) and Part B installations regulated under the Environmental Permitting (England and Wales) Regulations 2016 for the release of substances to the environment.

Features are displayed on the Current industrial land use map on **page 47**

ID	Location	Address	Details	
A	28m N	Anwar and Co Ltd, Whitworth Road Service Station, 111 Whitworth Road, Rochdale, Lancashire, OL12 0RA	Process: Unloading of Petrol into Storage at Service Stations Status: Current Permit Permit Type: Part B	Enforcement: No Enforcements Notified Date of enforcement: No Enforcements Notified Comment: No Enforcements Notified
A	206m N	Manson Timber, Whitworth Road, Rochdale	Process: Timber Manufacture Status: Historical Permit Permit Type: Part B	Enforcement: No Enforcements Notified Date of enforcement: No Enforcements Notified Comment: No Enforcements Notified
D	419m E	Ceylon Service Station, 278 Yorkshire Street, Rochdale, Lancashire, OL16 2DR	Process: Unloading of Petrol into Storage at Service Stations Status: Current Permit Permit Type: Part B	Enforcement: No Enforcements Notified Date of enforcement: No Enforcements Notified Comment: No Enforcements Notified
10	442m N	Imperial Dry Cleaners, 160 Whitworth Road, Rochdale, Lancashire, OL12 0JG	Process: Dry Cleaning Status: Current Permit Permit Type: Part B	Enforcement: No Enforcements Notified Date of enforcement: No Enforcements Notified Comment: No Enforcements Notified

This data is sourced from Local Authority records.



4.12 Radioactive Substance Authorisations

Records within 500m

0

Records of the storage, use, accumulation and disposal of radioactive substances regulated under the Radioactive Substances Act 1993.

This data is sourced from the Environment Agency and Natural Resources Wales.

4.13 Licensed Discharges to controlled waters

Records within 500m

9

Discharges of treated or untreated effluent to controlled waters under the Water Resources Act 1991.

Features are displayed on the Current industrial land use map on **page 47**

ID	Location	Address	Details	
B	139m S	ST MARYS GATE/CHEETHAM STREET CSO, 16 CHEETHAM STREET, (ST MARYS GATE), ROCHDALE, GREATER MANCHESTER, OL16 1DG	Effluent Type: SEWAGE DISCHARGES - SEWER STORM OVERFLOW - WATER COMPANY Permit Number: 01ROC0055 Permit Version: 1 Receiving Water: -	Status: REVOKED - UNSPECIFIED Issue date: - Effective Date: 01/04/1991 Revocation Date: 31/12/1994
B	139m S	ST MARYS GATE/CHEETHAM STREET CSO, 16 CHEETHAM STREET, (ST MARYS GATE), ROCHDALE, GREATER MANCHESTER, OL16 1DG	Effluent Type: SEWAGE DISCHARGES - SEWER STORM OVERFLOW - WATER COMPANY Permit Number: 01ROC0055 Permit Version: 2 Receiving Water: .	Status: POST NRA LEGISLATION WHERE ISSUE DATE > 31-AUG-89 (HISTORIC ONLY) Issue date: - Effective Date: 01/01/1995 Revocation Date: 14/04/2020
B	186m S	ST MARYS GATE/CHEETHAM STREET CSO, 16 CHEETHAM STREET, (ST MARYS GATE), ROCHDALE, GREATER MANCHESTER, OL16 1DG	Effluent Type: SEWAGE DISCHARGES - SEWER STORM OVERFLOW - WATER COMPANY Permit Number: EPRQB3591EA Permit Version: 1 Receiving Water: LORD BURN, TRIB OF RIVER ROCH	Status: VARIED UNDER EPR 2010 Issue date: 15/04/2020 Effective Date: 15/04/2020 Revocation Date: -
E	448m S	DRAKE STREET CSO (35038), DRAKE STREET (THE WELLINGTON), ROCHDALE, GREATER MANCHESTER, OL16 1RE	Effluent Type: SEWAGE DISCHARGES - SEWER STORM OVERFLOW - WATER COMPANY Permit Number: 01ROC0078 Permit Version: 4 Receiving Water: CULVERTED RIVER ROCH VIA SWS	Status: VARIED UNDER EPR 2010 Issue date: 01/10/2020 Effective Date: 01/10/2020 Revocation Date: -



ID	Location	Address	Details	
E	455m S	PENN ST W44, ROCHDALE, GREATER MANCHESTER	Effluent Type: SEWAGE DISCHARGES - SEWER STORM OVERFLOW - WATER COMPANY Permit Number: 01ROC0079 Permit Version: 1 Receiving Water: -	Status: REVOKED - UNSPECIFIED Issue date: - Effective Date: 01/04/1991 Revocation Date: 31/12/1994
E	455m S	PENN ST W44, ROCHDALE, GREATER MANCHESTER	Effluent Type: SEWAGE DISCHARGES - SEWER STORM OVERFLOW - WATER COMPANY Permit Number: 01ROC0079 Permit Version: 2 Receiving Water: -	Status: SURRENDERED UNDER EPR 2010 Issue date: - Effective Date: 01/01/1995 Revocation Date: 29/04/2019
E	465m S	DRAKE STREET CSO (35038), DRAKE STREET (THE WELLINGTON), ROCHDALE, GREATER MANCHESTER, OL16 1RE	Effluent Type: SEWAGE DISCHARGES - SEWER STORM OVERFLOW - WATER COMPANY Permit Number: 01ROC0078 Permit Version: 1 Receiving Water: -	Status: REVOKED - UNSPECIFIED Issue date: - Effective Date: 01/04/1991 Revocation Date: 31/12/1994
E	465m S	DRAKE STREET CSO (35038), DRAKE STREET (THE WELLINGTON), ROCHDALE, GREATER MANCHESTER, OL16 1RE	Effluent Type: SEWAGE DISCHARGES - SEWER STORM OVERFLOW - WATER COMPANY Permit Number: 01ROC0078 Permit Version: 2 Receiving Water: RIVER ROCH	Status: POST NRA LEGISLATION WHERE ISSUE DATE > 31-AUG-89 (HISTORIC ONLY) Issue date: 01/01/1995 Effective Date: 01/01/1995 Revocation Date: 29/06/2006
E	467m S	DRAKE STREET CSO (35038), DRAKE STREET (THE WELLINGTON), ROCHDALE, GREATER MANCHESTER, OL16 1RE	Effluent Type: SEWAGE DISCHARGES - SEWER STORM OVERFLOW - WATER COMPANY Permit Number: 01ROC0078 Permit Version: 3 Receiving Water: RIVER ROCH	Status: MODIFIED - (WRA 91 SCHED 10 - AS AMENDED BY ENV ACT 1995) Issue date: 11/07/2005 Effective Date: 30/06/2006 Revocation Date: 30/09/2020

This data is sourced from the Environment Agency and Natural Resources Wales.

4.14 Pollutant release to surface waters (Red List)

Records within 500m

0

Discharges of specified substances under the Environmental Protection (Prescribed Processes and Substances) Regulations 1991.

This data is sourced from the Environment Agency and Natural Resources Wales.



4.15 Pollutant release to public sewer

Records within 500m

0

Discharges of Special Category Effluents to the public sewer.

This data is sourced from the Environment Agency and Natural Resources Wales.

4.16 List 1 Dangerous Substances

Records within 500m

0

Discharges of substances identified on List I of European Directive E 2006/11/EC, and regulated under the Environmental Damage (Prevention and Remediation) Regulations 2015.

This data is sourced from the Environment Agency and Natural Resources Wales.

4.17 List 2 Dangerous Substances

Records within 500m

0

Discharges of substances identified on List II of European Directive E 2006/11/EC, and regulated under the Environmental Damage (Prevention and Remediation) Regulations 2015.

This data is sourced from the Environment Agency and Natural Resources Wales.

4.18 Pollution Incidents (EA/NRW)

Records within 500m

2

Records of substantiated pollution incidents. Since 2006 this data has only included category 1 (major) and 2 (significant) pollution incidents.

Features are displayed on the Current industrial land use map on **page 47**

ID	Location	Details	
9	278m N	Incident Date: 06/07/2001 Incident Identification: 14171 Pollutant: Inert Materials and Wastes Pollutant Description: Construction and Demolition Materials and Wastes	Water Impact: Category 4 (No Impact) Land Impact: Category 3 (Minor) Air Impact: Category 4 (No Impact)
11	457m SW	Incident Date: 22/11/2001 Incident Identification: 44441 Pollutant: Pollutant Not Identified Pollutant Description: Not Identified	Water Impact: Category 3 (Minor) Land Impact: Category 4 (No Impact) Air Impact: Category 4 (No Impact)

This data is sourced from the Environment Agency and Natural Resources Wales.

4.19 Pollution inventory substances

Records within 500m**0**

The pollution inventory (substances) includes reporting on annual emissions of certain regulated substances to air, controlled waters and land. A reporting threshold for each substance is also included. Where emissions fall below the reporting threshold, no value will be given. The data is given for the most recent complete year available.

This data is sourced from the Environment Agency and the Scottish Environment Protection Agency.

4.20 Pollution inventory waste transfers

Records within 500m**0**

The pollution inventory (waste transfers) includes reporting on annual transfers and recovery/disposal of controlled wastes from a site. A reporting threshold for each waste type is also included. Where releases fall below the reporting threshold, no value will be given. The data is given for the most recent complete year available.

This data is sourced from the Environment Agency and the Scottish Environment Protection Agency.

4.21 Pollution inventory radioactive waste


Records within 500m**0**

The pollution inventory (radioactive wastes) includes reporting on annual releases of radioactive substances from a site, including the means of release. Where releases fall below the reporting threshold, no value will be given. The data is given for the most recent complete year available.

This data is sourced from the Environment Agency and the Scottish Environment Protection Agency.



5 Hydrogeology - Superficial aquifer



- Site Outline
- Search buffers in metres (m)
- Principal
 - Secondary A
 - Secondary B
 - Secondary Undifferentiated
 - Unproductive
 - Unknown

5.1 Superficial aquifer

Records within 500m

6

Aquifer status of groundwater held within superficial geology.

Features are displayed on the Hydrogeology map on **page 57**

ID	Location	Designation	Description
1	On site	Secondary Undifferentiated	Assigned where it is not possible to attribute either category A or B to a rock type. In general these layers have previously been designated as both minor and non-aquifer in different locations due to the variable characteristics of the rock type
2	126m S	Secondary A	Permeable layers capable of supporting water supplies at a local rather than strategic scale, and in some cases forming an important source of base flow to rivers. These are generally aquifers formerly classified as minor aquifers




ID	Location	Designation	Description
3	179m E	Secondary Undifferentiated	Assigned where it is not possible to attribute either category A or B to a rock type. In general these layers have previously been designated as both minor and non-aquifer in different locations due to the variable characteristics of the rock type
4	203m SE	Secondary A	Permeable layers capable of supporting water supplies at a local rather than strategic scale, and in some cases forming an important source of base flow to rivers. These are generally aquifers formerly classified as minor aquifers
5	301m SE	Secondary Undifferentiated	Assigned where it is not possible to attribute either category A or B to a rock type. In general these layers have previously been designated as both minor and non-aquifer in different locations due to the variable characteristics of the rock type
6	301m SE	Secondary Undifferentiated	Assigned where it is not possible to attribute either category A or B to a rock type. In general these layers have previously been designated as both minor and non-aquifer in different locations due to the variable characteristics of the rock type

This data is sourced from the British Geological Survey, the Environment Agency and Natural Resources Wales.



Bedrock aquifer



- Site Outline**
- Search buffers in metres (m)**
- Principal
 - Secondary A
 - Secondary B
 - Secondary Undifferentiated
 - Unproductive

5.2 Bedrock aquifer

Records within 500m

2

Aquifer status of groundwater held within bedrock geology.

Features are displayed on the Bedrock aquifer map on **page 59**



ID	Location	Designation	Description
1	On site	Secondary A	Permeable layers capable of supporting water supplies at a local rather than strategic scale, and in some cases forming an important source of base flow to rivers. These are generally aquifers formerly classified as minor aquifers
2	179m E	Secondary A	Permeable layers capable of supporting water supplies at a local rather than strategic scale, and in some cases forming an important source of base flow to rivers. These are generally aquifers formerly classified as minor aquifers



This data is sourced from the British Geological Survey, the Environment Agency and Natural Resources Wales.



Groundwater vulnerability



5.3 Groundwater vulnerability

Records within 50m

1

An assessment of the vulnerability of groundwater to a pollutant discharged at ground level based on the hydrological, geological, hydrogeological and soil properties within a one kilometre square grid. Groundwater vulnerability is described as High, Medium or Low as follows:

- High - Areas able to easily transmit pollution to groundwater. They are likely to be characterised by high leaching soils and the absence of low permeability superficial deposits.
- Medium - Intermediate between high and low vulnerability.
- Low - Areas that provide the greatest protection from pollution. They are likely to be characterised by low leaching soils and/or the presence of superficial deposits characterised by a low permeability.

Features are displayed on the Groundwater vulnerability map on **page 61**



ID	Location	Summary	Soil / surface	Superficial geology	Bedrock geology
1	On site	Summary Classification: Secondary superficial aquifer - High Vulnerability Combined classification: Productive Bedrock Aquifer, Productive Superficial Aquifer	Leaching class: High Infiltration value: >70% Dilution value: >550mm/year	Vulnerability: High Aquifer type: Secondary Thickness: >10m Patchiness value: >90% Recharge potential: High	Vulnerability: Low Aquifer type: Secondary Flow mechanism: Well connected fractures

This data is sourced from the British Geological Survey, the Environment Agency and Natural Resources Wales.

5.4 Groundwater vulnerability- soluble rock risk

Records on site	0
------------------------	----------

This dataset identifies areas where solution features that enable rapid movement of a pollutant may be present within a 1km grid square.

This data is sourced from the British Geological Survey and the Environment Agency.


5.5 Groundwater vulnerability- local information

Records on site	0
------------------------	----------

This dataset identifies areas where additional local information affecting vulnerability is held by the Environment Agency. Further information can be obtained by contacting the Environment Agency local Area groundwater team through the Environment Agency National Customer Call Centre on 03798 506 506 or by email on enquiries@environment-agency.gov.uk.

This data is sourced from the British Geological Survey and the Environment Agency.

Abstractions and Source Protection Zones



- Site Outline
- Search buffers in metres (m)**
- Source Protection Zone 1
Inner catchment
- Source Protection Zone 2
Outer catchment
- Source Protection Zone 3
Total catchment
- Source Protection Zone 4
Zone of Special Interest
- Source Protection Zone 1c
Inner catchment - confined aquifer
- Source Protection Zone 2c
Outer catchment - confined aquifer
- Source Protection Zone 3c
Total catchment - confined aquifer
- Drinking water abstraction licences
Polygon features
- Drinking water abstraction licences
Linear features
- Groundwater abstraction licence (point)
- Groundwater abstraction licence (area)
- Groundwater abstraction licence (linear)
- Surface Water Abstractions (point)
- Surface Water Abstractions (area)
- Surface Water Abstractions (linear)

5.6 Groundwater abstractions

Records within 2000m

3

Licensed groundwater abstractions for sites extracting more than 20 cubic metres of water a day and includes active and historical records. The data may be for a single abstraction point, between two points (line data) or a larger area.

Features are displayed on the Abstractions and Source Protection Zones map on **page 63**



ID	Location	Details	
-	1125m W	Status: Historical Licence No: 2569002050 Details: Process water Direct Source: Ground Water - North West Region Point: "BOREHOLE AT PREMISES, SPOTLAND, ROCHDALE" Data Type: Point Name: ALEXANDER DREW & SONS LTD Easting: 388700 Northing: 413500	Annual Volume (m³): - Max Daily Volume (m³): - Original Application No: - Original Start Date: 10/02/1966 Expiry Date: - Issue No: 101 Version Start Date: 02/05/2000 Version End Date: -
-	1125m W	Status: Historical Licence No: 2569002050 Details: Process water Direct Source: Ground Water - North West Region Point: BOREHOLE AT PREMISES, SPOTLAND, ROCHDALE Data Type: Point Name: ALEXANDER DREW LTD. Easting: 388700 Northing: 413500	Annual Volume (m³): - Max Daily Volume (m³): - Original Application No: - Original Start Date: 10/02/1966 Expiry Date: - Issue No: 102 Version Start Date: 01/04/2003 Version End Date: -
-	1125m W	Status: Historical Licence No: 2569002050 Details: Process water Direct Source: Ground Water - North West Region Point: BOREHOLE AT PREMISES SPOTLAND ROCHDALE Data Type: Point Name: ALEXANDER DREW LTD Easting: 388700 Northing: 413500	Annual Volume (m³): 500000 Max Daily Volume (m³): 2100 Original Application No: - Original Start Date: 10/02/1966 Expiry Date: - Issue No: 102 Version Start Date: 01/04/2003 Version End Date: -

This data is sourced from the Environment Agency and Natural Resources Wales.

5.7 Surface water abstractions

Records within 2000m

17

Licensed surface water abstractions for sites extracting more than 20 cubic metres of water a day and includes active and historical records. The data may be for a single abstraction point, a stretch of watercourse or a larger area.

Features are displayed on the Abstractions and Source Protection Zones map on **page 63**



ID	Location	Details	
A	558m S	Status: Active Licence No: NW/069/0002/003 Details: Transfer Between Sources (Post Water Act 2003) Direct Source: Surface, Non-Tidal - North West Region Point: RIVER ROCH AT ROCHDALE WEIR Data Type: Point Name: Transport for Greater Manchester Easting: 389916 Northing: 413325	Annual Volume (m³): - Max Daily Volume (m³): - Original Application No: NPS/WR/007633 Original Start Date: 15/06/2010 Expiry Date: 31/03/2026 Issue No: 2 Version Start Date: 23/06/2011 Version End Date: -
A	558m S	Status: Active Licence No: NW/069/0002/001 Details: Hydroelectric Power Generation Direct Source: Surface, Non-Tidal - North West Region Point: RIVER ROCH AT ROCHDALE WEIR Data Type: Point Name: Transport for Greater Manchester Easting: 389917 Northing: 413325	Annual Volume (m³): 36,100,000 Max Daily Volume (m³): 164,160 Original Application No: NPS/WR/007499 Original Start Date: 15/06/2010 Expiry Date: 31/03/2026 Issue No: 2 Version Start Date: 01/04/2015 Version End Date: -
-	875m N	Status: Historical Licence No: 2569002268 Details: Non-Evaporative Cooling Direct Source: "Surface, Non-Tidal - North West Region" Point: "FOXHOLES BROOK AT FIELDHOUSE INDUSTRIAL ESTATE, ROCHDALE" Data Type: Point Name: RIVERSIDE TRADING LTD Easting: 389700 Northing: 414800	Annual Volume (m³): - Max Daily Volume (m³): - Original Application No: - Original Start Date: - Expiry Date: - Issue No: 100 Version Start Date: 10/11/1998 Version End Date: -
-	875m N	Status: Historical Licence No: 2569002268 Details: Non-Evaporative Cooling Direct Source: Surface, Non-Tidal - North West Region Point: FOXHOLES BROOK AT FIELDHOUSE INDUSTRIAL ESTATE, ROCHDALE Data Type: Point Name: RIVERSIDE TRADING LTD Easting: 389700 Northing: 414800	Annual Volume (m³): - Max Daily Volume (m³): - Original Application No: - Original Start Date: - Expiry Date: - Issue No: 100 Version Start Date: 10/11/1998 Version End Date: -

ID	Location	Details	
-	983m E	Status: Historical Licence No: 2569002249 Details: Process water Direct Source: "Surface, Non-Tidal - North West Region" Point: "RIVER ROCH AT MELLOROID WORKS, BELFIELD ROAD" Data Type: Point Name: BRITISH MILLERAIN 1922 CO LTD Easting: 390800 Northing: 413800	Annual Volume (m³): - Max Daily Volume (m³): - Original Application No: - Original Start Date: 04/11/1991 Expiry Date: - Issue No: 100 Version Start Date: 04/11/1991 Version End Date: -
-	983m E	Status: Historical Licence No: 2569002249 Details: Process water Direct Source: Surface, Non-Tidal - North West Region Point: RIVER ROCH AT MELLOROID WORKS, BELFIELD ROAD Data Type: Point Name: BRITISH MILLERAIN 1922 CO LTD Easting: 390800 Northing: 413800	Annual Volume (m³): - Max Daily Volume (m³): - Original Application No: - Original Start Date: 04/11/1991 Expiry Date: - Issue No: 100 Version Start Date: 04/11/1991 Version End Date: -
-	983m E	Status: Historical Licence No: 2569002249 Details: Process Water Direct Source: Surface, Non-Tidal - North West Region Point: RIVER ROCH AT MELLOROID WORKS BELFIELD ROAD Data Type: Point Name: BRITISH MILLERAIN 1922 CO LTD Easting: 390800 Northing: 413800	Annual Volume (m³): 213662 Max Daily Volume (m³): 1136.49 Original Application No: - Original Start Date: 04/11/1991 Expiry Date: - Issue No: 100 Version Start Date: 04/11/1991 Version End Date: -
-	1523m N	Status: Historical Licence No: 2569002193 Details: Potable Water Supply - Direct Direct Source: "Surface, Non-Tidal - North West Region" Point: "WATERGROVE, BROWN HOUSE WHAM, HAMER PASTURE AND BUCKLEY[12]" Data Type: Point Name: UNITED UTILITIES WATER PLC Easting: 390200 Northing: 415400	Annual Volume (m³): - Max Daily Volume (m³): - Original Application No: - Original Start Date: 22/03/1966 Expiry Date: - Issue No: 100 Version Start Date: 22/03/1966 Version End Date: -



ID	Location	Details	
-	1523m N	Status: Active Licence No: 2569002193 Details: Potable Water Supply - Direct Direct Source: Surface, Non-Tidal - North West Region Point: WATERGROVE, BROWN HOUSE WHAM, HAMER PASTURE AND BUCKLEY[12] Data Type: Point Name: United Utilities Water Ltd Easting: 390200 Northing: 415400	Annual Volume (m³): 5,909,800 Max Daily Volume (m³): 5,909,800 Original Application No: 1592 Original Start Date: 22/03/1966 Expiry Date: - Issue No: 100 Version Start Date: 22/03/1966 Version End Date: -
-	1650m S	Status: Historical Licence No: 2569002076 Details: Boiler Feed Direct Source: Surface, Non-Tidal - North West Region Point: ROCHDALE CANAL AT ROCHDALE, LANCS Data Type: Point Name: J & J MAKIN CONVERTORS LTD Easting: 390300 Northing: 412300	Annual Volume (m³): - Max Daily Volume (m³): - Original Application No: - Original Start Date: 18/01/1966 Expiry Date: - Issue No: 100 Version Start Date: 01/04/1993 Version End Date: -
-	1662m W	Status: Historical Licence No: 2569002018 Details: General Cooling (Existing Licences Only) (Low Loss) Direct Source: Surface, Non-Tidal - North West Region Point: LODGE FED BY R SPODDEN AT ROCHDALE Data Type: Point Name: FLEXITALLIC LTD Easting: 388200 Northing: 414500	Annual Volume (m³): 1500211.393 Max Daily Volume (m³): 4546.095 Original Application No: - Original Start Date: 14/02/1966 Expiry Date: - Issue No: 101 Version Start Date: 11/04/1997 Version End Date: -
-	1662m W	Status: Historical Licence No: 2569002018 Details: Boiler Feed Direct Source: Surface, Non-Tidal - North West Region Point: LODGE FED BY R SPODDEN AT ROCHDALE Data Type: Point Name: FLEXITALLIC LTD Easting: 388200 Northing: 414500	Annual Volume (m³): 1500211.393 Max Daily Volume (m³): 4546.095 Original Application No: - Original Start Date: 14/02/1966 Expiry Date: - Issue No: 101 Version Start Date: 11/04/1997 Version End Date: -
-	1662m W	Status: Historical Licence No: 2569002018 Details: Process Water Direct Source: Surface, Non-Tidal - North West Region Point: LODGE FED BY R SPODDEN AT ROCHDALE Data Type: Point Name: FLEXITALLIC LTD Easting: 388200 Northing: 414500	Annual Volume (m³): 1500211.393 Max Daily Volume (m³): 4546.095 Original Application No: - Original Start Date: 14/02/1966 Expiry Date: - Issue No: 101 Version Start Date: 11/04/1997 Version End Date: -



ID	Location	Details	
-	1927m S	Status: Historical Licence No: 2569002107 Details: Boiler Feed Direct Source: "Surface, Non-Tidal - North West Region" Point: "ROCHDALE CANAL AT QUEENSWAY,ROCHDALE" Data Type: Point Name: SEALOCRETE PLA LTD Easting: 390070 Northing: 411960	Annual Volume (m³): - Max Daily Volume (m³): - Original Application No: - Original Start Date: 02/02/1966 Expiry Date: - Issue No: 100 Version Start Date: 20/12/1993 Version End Date: -
-	1927m S	Status: Historical Licence No: 2569002107 Details: General Cooling (Existing Licences Only) (Low Loss) Direct Source: "Surface, Non-Tidal - North West Region" Point: "ROCHDALE CANAL AT QUEENSWAY,ROCHDALE" Data Type: Point Name: SEALOCRETE PLA LTD Easting: 390070 Northing: 411960	Annual Volume (m³): - Max Daily Volume (m³): - Original Application No: - Original Start Date: 02/02/1966 Expiry Date: - Issue No: 100 Version Start Date: 20/12/1993 Version End Date: -
-	1927m S	Status: Historical Licence No: 2569002107 Details: Boiler Feed Direct Source: Surface, Non-Tidal - North West Region Point: ROCHDALE CANAL AT QUEENSWAY,ROCHDALE Data Type: Point Name: SEALOCRETE PLA LTD Easting: 390070 Northing: 411960	Annual Volume (m³): 10455.8 Max Daily Volume (m³): 45.46 Original Application No: - Original Start Date: 02/02/1966 Expiry Date: - Issue No: 100 Version Start Date: 01/04/2008 Version End Date: -
-	1927m S	Status: Historical Licence No: 2569002107 Details: General Cooling (Existing Licences Only) (Low Loss) Direct Source: Surface, Non-Tidal - North West Region Point: ROCHDALE CANAL AT QUEENSWAY,ROCHDALE Data Type: Point Name: SEALOCRETE PLA LTD Easting: 390070 Northing: 411960	Annual Volume (m³): 10455.8 Max Daily Volume (m³): 45.46 Original Application No: - Original Start Date: 02/02/1966 Expiry Date: - Issue No: 100 Version Start Date: 01/04/2008 Version End Date: -

This data is sourced from the Environment Agency and Natural Resources Wales.



5.8 Potable abstractions

Records within 2000m

2

Licensed potable water abstractions for sites extracting more than 20 cubic metres of water a day and includes active and historical records. The data may be for a single abstraction point, a stretch of watercourse or a larger area.

Features are displayed on the Abstractions and Source Protection Zones map on **page 63**

ID	Location	Details	
-	1523m N	Status: Historical Licence No: 2569002193 Details: Potable Water Supply - Direct Direct Source: "Surface, Non-Tidal - North West Region" Point: "WATERGROVE, BROWN HOUSE WHAM, HAMER PASTURE AND BUCKLEY[12]" Data Type: Point Name: UNITED UTILITIES WATER PLC Easting: 390200 Northing: 415400	Annual Volume (m ³): - Max Daily Volume (m ³): - Original Application No: - Original Start Date: 22/03/1966 Expiry Date: - Issue No: 100 Version Start Date: 22/03/1966 Version End Date: -
-	1523m N	Status: Active Licence No: 2569002193 Details: Potable Water Supply - Direct Direct Source: Surface, Non-Tidal - North West Region Point: WATERGROVE, BROWN HOUSE WHAM, HAMER PASTURE AND BUCKLEY[12] Data Type: Point Name: United Utilities Water Ltd Easting: 390200 Northing: 415400	Annual Volume (m ³): 5,909,800 Max Daily Volume (m ³): 5,909,800 Original Application No: 1592 Original Start Date: 22/03/1966 Expiry Date: - Issue No: 100 Version Start Date: 22/03/1966 Version End Date: -

This data is sourced from the Environment Agency and Natural Resources Wales.

5.9 Source Protection Zones

Records within 500m

0

Source Protection Zones define the sensitivity of an area around a potable abstraction site to contamination.

This data is sourced from the Environment Agency and Natural Resources Wales.



5.10 Source Protection Zones (confined aquifer)

Records within 500m


0

Source Protection Zones in the confined aquifer define the sensitivity around a deep groundwater abstraction to contamination. A confined aquifer would normally be protected from contamination by overlying geology and is only considered a sensitive resource if deep excavation/drilling is taking place.

This data is sourced from the Environment Agency and Natural Resources Wales.



6 Hydrology



- Site Outline
- Search buffers in metres (m)
- Water Network (OS MasterMap)
- Surface water features (wider than 5m)
- Surface water features (narrower than 5m)
- - - WFD River, canal and surface water transfer water bodies
- WFD Lake water bodies
- WFD Transitional and coastal water bodies
- WFD Surface water body catchments boundaries
- WFD Groundwater body boundaries

6.1 Water Network (OS MasterMap)

Records within 250m

0

Detailed water network of Great Britain showing the flow and precise central course of every river, stream, lake and canal.

This data is sourced from the Ordnance Survey.

6.2 Surface water features

Records within 250m

0

Covering rivers, streams and lakes (some overlap with OS MasterMap Water Network data in previous section) but additionally covers smaller features such as ponds. Rivers and streams narrower than 5m are represented as a single line. Lakes, ponds and rivers or streams wider than 5m are represented as polygons.



This data is sourced from the Ordnance Survey.

6.3 WFD Surface water body catchments

Records on site

1

The Water Framework Directive is an EU-led framework for the protection of inland surface waters, estuaries, coastal waters and groundwater through river basin-level management planning. In terms of surface water, these basins are broken down into smaller units known as management, operational and water body catchments.

Features are displayed on the Hydrology map on **page 71**

ID	Location	Type	Water body catchment	Water body ID	Operational catchment	Management catchment
A	On site	River	Roch (Source to Spodden)	GB112069064720	Roch Irk Medlock	Irwell

This data is sourced from the Environment Agency and Natural Resources Wales.

6.4 WFD Surface water bodies

Records identified

1

Surface water bodies under the Directive may be rivers, lakes, estuary or coastal. To achieve the purpose of the Directive, environmental objectives have been set and are reported on for each water body. The progress towards delivery of the objectives is then reported on by the relevant competent authorities at the end of each six-year cycle. The river water body directly associated with the catchment listed in the previous section is detailed below, along with any lake, canal, coastal or artificial water body within 250m of the site. Click on the water body ID in the table to visit the EA Catchment Explorer to find out more about each water body listed.

Features are displayed on the Hydrology map on **page 71**

ID	Location	Type	Name	Water body ID	Overall rating	Chemical rating	Ecological rating	Year
1	431m S	River	Roch (Source to Spodden)	GB112069064720	Moderate	Fail	Moderate	2019

This data is sourced from the Environment Agency and Natural Resources Wales.



6.5 WFD Groundwater bodies

Records on site

1

Groundwater bodies are also covered by the Directive and the same regime of objectives and reporting detailed in the previous section is in place. Click on the water body ID in the table to visit the EA Catchment Explorer to find out more about each groundwater body listed.

Features are displayed on the Hydrology map on **page 71**

ID	Location	Name	Water body ID	Overall rating	Chemical rating	Quantitative	Year
A	On site	Northern Manchester Carboniferous Aquifers	<u>GB41202G101800</u>	Poor	Poor	Good	2019

This data is sourced from the Environment Agency and Natural Resources Wales.



7 River and coastal flooding

7.1 Risk of flooding from rivers and the sea

Records within 50m

0

The chance of flooding from rivers and/or the sea in any given year, based on cells of 50m within the Risk of Flooding from Rivers and Sea (RoFRaS)/Flood Risk Assessment Wales (FRAW) models. Each cell is allocated one of four flood risk categories, taking into account flood defences and their condition. The risk categories for RoFRaS for rivers and the sea and FRAW for rivers are; Very low (less than 1 in 1000 chance in any given year), Low (less than 1 in 100 but greater than or equal to 1 in 1000 chance), Medium (less than 1 in 30 but greater than or equal to 1 in 100 chance) or High (greater than or equal to 1 in 30 chance). The risk categories for FRAW for the sea are; Very low (less than 1 in 1000 chance in any given year), Low (less than 1 in 200 but greater than or equal to 1 in 1000 chance), Medium (less than 1 in 30 but greater than or equal to 1 in 200 chance) or High (greater than or equal to 1 in 30 chance).

This data is sourced from the Environment Agency and Natural Resources Wales.

7.2 Historical Flood Events

Records within 250m

0

Records of historic flooding from rivers, the sea, groundwater and surface water. Records began in 1946 when predecessor bodies started collecting detailed information about flooding incidents, although limited details may be included on flooding incidents prior to this date. Takes into account the presence of defences, structures, and other infrastructure where they existed at the time of flooding, and includes flood extents that may have been affected by overtopping, breaches or blockages.

This data is sourced from the Environment Agency and Natural Resources Wales.

7.3 Flood Defences

Records within 250m

0

Records of flood defences owned, managed or inspected by the Environment Agency and Natural Resources Wales. Flood defences can be structures, buildings or parts of buildings. Typically these are earth banks, stone and concrete walls, or sheet-piling that is used to prevent or control the extent of flooding.

This data is sourced from the Environment Agency and Natural Resources Wales.



7.4 Areas Benefiting from Flood Defences

Records within 250m

0

Areas that would benefit from the presence of flood defences in a 1 in 100 (1%) chance of flooding each year from rivers or 1 in 200 (0.5%) chance of flooding each year from the sea.

This data is sourced from the Environment Agency and Natural Resources Wales.

7.5 Flood Storage Areas

Records within 250m

0

Areas that act as a balancing reservoir, storage basin or balancing pond to attenuate an incoming flood peak to a flow level that can be accepted by the downstream channel or to delay the timing of a flood peak so that its volume is discharged over a longer period.

This data is sourced from the Environment Agency and Natural Resources Wales.



River and coastal flooding - Flood Zones

7.6 Flood Zone 2

Records within 50m

0

Areas of land at risk of flooding, when the presence of flood defences are ignored. Covering land between Flood Zone 3 (see next section) and the extent of the flooding from rivers or the sea with a 1 in 1000 (0.1%) chance of flooding each year.

This data is sourced from the Environment Agency and Natural Resources Wales.

7.7 Flood Zone 3

Records within 50m

0

Areas of land at risk of flooding, when the presence of flood defences are ignored. Covering land with a 1 in 100 (1%) or greater chance of flooding each year from rivers or a 1 in 200 (0.5%) or greater chance of flooding each year from the sea.

This data is sourced from the Environment Agency and Natural Resources Wales.



8 Surface water flooding



— Site Outline

Search buffers in metres (m)

1 in 1000 return period

- Depth between 0.1m - 0.3m
- Depth between 0.3m - 1.0m
- Depth greater than 1.0m

1 in 250 return period

- Depth between 0.1m - 0.3m
- Depth between 0.3m - 1.0m
- Depth greater than 1.0m

1 in 100 return period

- Depth between 0.1m - 0.3m
- Depth between 0.3m - 1.0m
- Depth greater than 1.0m

1 in 30 return period

- Depth between 0.1m - 0.3m
- Depth between 0.3m - 1.0m
- Depth greater than 1.0m

8.1 Surface water flooding

Highest risk on site

Negligible

Highest risk within 50m

1 in 30 year, 0.3m - 1.0m

Ambiental Risk Analytics surface water (pluvial) FloodMap identifies areas likely to flood as a result of extreme rainfall events, i.e. land naturally vulnerable to surface water ponding or flooding. This data set was produced by simulating 1 in 30 year, 1 in 100 year, 1 in 250 year and 1 in 1,000 year rainfall events. Modern urban drainage systems are typically built to cope with rainfall events between 1 in 20 and 1 in 30 years, though some older ones may flood in a 1 in 5 year rainfall event.

Features are displayed on the Surface water flooding map on **page 77**

The data shown on the map and in the table above shows the highest likelihood of flood events happening at the site. Lower likelihood events may have greater flood depths and hence a greater potential impact on a site.


The table below shows the maximum flood depths for a range of return periods for the site.

Return period	Maximum modelled depth
1 in 1000 year	Negligible
1 in 250 year	Negligible
1 in 100 year	Negligible
1 in 30 year	Negligible

This data is sourced from Ambiantal Risk Analytics.



9 Groundwater flooding



— Site Outline
Search buffers in metres (m)

- High
- Moderate - High
- Moderate
- Low
- Negligible

9.1 Groundwater flooding

Highest risk on site

Low

Highest risk within 50m

Low

Groundwater flooding is caused by unusually high groundwater levels. It occurs when the water table rises above the ground surface or within underground structures such as basements or cellars. Groundwater flooding tends to exhibit a longer duration than surface water flooding, possibly lasting for weeks or months, and as a result it can cause significant damage to property. This risk assessment is based on a 1 in 100 year return period and a 5m Digital Terrain Model (DTM).

Features are displayed on the Groundwater flooding map on **page 79**

This data is sourced from Ambiantal Risk Analytics.

10 Environmental designations



- Site Outline
- Search buffers in metres (m)
- Sites of Special Scientific Interest (SSSI)
- + Special Areas of Conservation (SAC)
- + Local Nature Reserves (LNR)
- Designated Ancient Woodland
- Green Belt

10.1 Sites of Special Scientific Interest (SSSI)

Records within 2000m

2

Sites providing statutory protection for the best examples of UK flora, fauna, or geological or physiographical features. Originally notified under the National Parks and Access to the Countryside Act 1949, SSSIs were re-notified under the Wildlife and Countryside Act 1981. Improved provisions for the protection and management of SSSIs were introduced by the Countryside and Rights of Way Act 2000 (in England and Wales) and (in Scotland) by the Nature Conservation (Scotland) Act 2004 and the Wildlife and Natural Environment (Scotland) Act 2010.

Features are displayed on the Environmental designations map on **page 80**

ID	Location	Name	Data source
-	1546m S	Rochdale Canal	Natural England



ID	Location	Name	Data source
-	1861m E	Rochdale Canal	Natural England

This data is sourced from Natural England, Natural Resources Wales and Scottish Natural Heritage.

10.2 Conserved wetland sites (Ramsar sites)

Records within 2000m

0

Ramsar sites are designated under the Convention on Wetlands of International Importance, agreed in Ramsar, Iran, in 1971. They cover all aspects of wetland conservation and wise use, recognizing wetlands as ecosystems that are extremely important for biodiversity conservation in general and for the well-being of human communities. These sites cover a broad definition of wetland; marsh, fen, peatland or water, whether natural or artificial, permanent or temporary, with water that is static or flowing, fresh, brackish or salt, and even some marine areas.

This data is sourced from Natural England, Natural Resources Wales and Scottish Natural Heritage.

10.3 Special Areas of Conservation (SAC)

Records within 2000m

2

Areas which have been identified as best representing the range and variety within the European Union of habitats and (non-bird) species listed on Annexes I and II to the Directive. SACs are designated under the EC Habitats Directive.

Features are displayed on the Environmental designations map on **page 80**

ID	Location	Name	Features of interest	Habitat description	Data source
-	1546m S	Rochdale Canal	Floating water-plantain.	Other land (including Towns, Villages, Roads, Waste places, Mines, Industrial sites); Inland water bodies (Standing water, Running water)	Natural England
-	1861m E	Rochdale Canal	Floating water-plantain.	Other land (including Towns, Villages, Roads, Waste places, Mines, Industrial sites); Inland water bodies (Standing water, Running water)	Natural England

This data is sourced from Natural England, Natural Resources Wales and Scottish Natural Heritage.

10.4 Special Protection Areas (SPA)

Records within 2000m**0**

Sites classified by the UK Government under the EC Birds Directive, SPAs are areas of the most important habitat for rare (listed on Annex I to the Directive) and migratory birds within the European Union.

This data is sourced from Natural England, Natural Resources Wales and Scottish Natural Heritage.

10.5 National Nature Reserves (NNR)

Records within 2000m**0**

Sites containing examples of some of the most important natural and semi-natural terrestrial and coastal ecosystems in Great Britain. They are managed to conserve their habitats, provide special opportunities for scientific study or to provide public recreation compatible with natural heritage interests.

This data is sourced from Natural England, Natural Resources Wales and Scottish Natural Heritage.

10.6 Local Nature Reserves (LNR)

Records within 2000m**1**

Sites managed for nature conservation, and to provide opportunities for research and education, or simply enjoying and having contact with nature. They are declared by local authorities under the National Parks and Access to the Countryside Act 1949 after consultation with the relevant statutory nature conservation agency. Features are displayed on the Environmental designations map on **page 80**

ID	Location	Name	Data source
-	1823m NW	Healey Dell	Natural England

This data is sourced from Natural England, Natural Resources Wales and Scottish Natural Heritage.

10.7 Designated Ancient Woodland

Records within 2000m**2**

Ancient woodlands are classified as areas which have been wooded continuously since at least 1600 AD. This includes semi-natural woodland and plantations on ancient woodland sites. 'Wooded continuously' does not mean there is or has previously been continuous tree cover across the whole site, and not all trees within the woodland have to be old.

Features are displayed on the Environmental designations map on **page 80**



ID	Location	Name	Woodland Type
-	1680m NE	Buckley Wood	Ancient & Semi-Natural Woodland
-	1702m NE	Buckley Wood	Ancient Replanted Woodland

This data is sourced from Natural England, Natural Resources Wales and Scottish Natural Heritage.

10.8 Biosphere Reserves

Records within 2000m **0**

Biosphere Reserves are internationally recognised by UNESCO as sites of excellence to balance conservation and socioeconomic development between nature and people. They are recognised under the Man and the Biosphere (MAB) Programme with the aim of promoting sustainable development founded on the work of the local community.

This data is sourced from Natural England, Natural Resources Wales and Scottish Natural Heritage.

10.9 Forest Parks

Records within 2000m **0**

These are areas managed by the Forestry Commission designated on the basis of recreational, conservation or scenic interest.

This data is sourced from the Forestry Commission.

10.10 Marine Conservation Zones

Records within 2000m **0**

A type of marine nature reserve in UK waters established under the Marine and Coastal Access Act (2009). They are designated with the aim to protect nationally important, rare or threatened habitats and species.

This data is sourced from Natural England, Natural Resources Wales and Scottish Natural Heritage.

10.11 Green Belt

Records within 2000m **2**

Areas designated to prevent urban sprawl by keeping land permanently open.

Features are displayed on the Environmental designations map on **page 80**

ID	Location	Name	Local Authority name
1	1006m NE	Merseyside and Greater Manchester	Rochdale



ID	Location	Name	Local Authority name
-	1683m NW	Merseyside and Greater Manchester	Rochdale

This data is sourced from the Ministry of Housing, Communities and Local Government.

10.12 Proposed Ramsar sites

Records within 2000m

0

Ramsar sites are areas listed as a Wetland of International Importance under the Convention on Wetlands of International Importance especially as Waterfowl Habitat (the Ramsar Convention) 1971. The sites here supplied have a status of 'Proposed' having been identified for potential adoption under the framework.

This data is sourced from Natural England.

10.13 Possible Special Areas of Conservation (pSAC)

Records within 2000m

0

Special Areas of Conservation are areas which have been identified as best representing the range and variety within the European Union of habitats and (non-bird) species listed on Annexes I and II to the Directive. SACs are designated under the EC Habitats Directive. Those sites supplied here are those with a status of 'Possible' having been identified for potential adoption under the framework.

This data is sourced from Natural England and Natural Resources Wales.

10.14 Potential Special Protection Areas (pSPA)

Records within 2000m

0

Special Protection Areas (SPAs) are areas designated (or 'classified') under the European Union Wild Birds Directive for the protection of nationally and internationally important populations of wild birds. Those sites supplied here are those with a status of 'Potential' having been identified for potential adoption under the framework.

This data is sourced from Natural England.

10.15 Nitrate Sensitive Areas

Records within 2000m

0

Areas where nitrate concentrations in drinking water sources exceeded or was at risk of exceeding the limit of 50 mg/l set by the 1980 EC Drinking Water Directive. Voluntary agricultural measures as a means of reducing the levels of nitrate were introduced by DEFRA as MAFF, with payments being made to farmers who complied. The scheme was started as a pilot in 1990 in ten areas, later implemented within 32 areas. The scheme was closed to further new entrants in 1998, although existing agreements continued for their full term. All Nitrate



Sensitive Areas fall within the areas designated as Nitrate Vulnerable Zones (NVZs) in 1996 under the EC Nitrate Directive (91/676/EEC).

This data is sourced from Natural England.

10.16 Nitrate Vulnerable Zones

Records within 2000m


0

Areas at risk from agricultural nitrate pollution designated under the EC Nitrate Directive (91/676/EEC). These are areas of land that drain into waters polluted by nitrates. Farmers operating within these areas have to follow mandatory rules to tackle nitrate loss from agriculture.

This data is sourced from Natural England and Natural Resources Wales.



SSSI Impact Zones and Units



- Site Outline
- Search buffers in metres (m)
- SSSI Impact Risk Zones
- SSSI Units
- Not recorded
- Favourable
- Unfavourable - Recovering
- Unfavourable - No change
- Unfavourable - Declining
- Partially destroyed
- Destroyed

10.17 SSSI Impact Risk Zones

Records on site

1

Developed to allow rapid initial assessment of the potential risks to SSSIs posed by development proposals. They define zones around each SSSI which reflect the particular sensitivities of the features for which it is notified and indicate the types of development proposal which could potentially have adverse impacts.

Features are displayed on the SSSI Impact Zones and Units map on **page 86**

ID	Location	Type of developments requiring consultation
1	On site	Infrastructure - Pipelines, pylons and overhead cables. any transport proposal including road, rail and by water (excluding routine maintenance). airports, helipads and other aviation proposals. Minerals, Oil and Gas - Planning applications for quarries, including: new proposals, review of minerals permissions (romp), extensions, variations to conditions etc. oil & gas exploration/extraction. Air pollution - Any industrial/agricultural development that could cause air pollution (incl: industrial processes, livestock & poultry units with floorspace > 500m², slurry lagoons & digestate stores > 200m², manure stores > 250t). Combustion - General combustion processes >20mw energy input. incl: energy from waste incineration, other incineration, landfill gas generation plant, pyrolysis/gasification, anaerobic digestion, sewage treatment works, other incineration/ combustion. Waste - Landfill. incl: inert landfill, non-hazardous landfill, hazardous landfill. Composting - Any composting proposal with more than 75000 tonnes maximum annual operational throughput. incl: open windrow composting, in-vessel composting, anaerobic digestion, other waste management. Water supply - Large infrastructure such as warehousing / industry where total net additional gross internal floorspace following development is 1,000m² or more.

This data is sourced from Natural England.

10.18 SSSI Units

Records within 2000m	2
-----------------------------	----------

Divisions of SSSIs used to record management and condition details. Units are the smallest areas for which Natural England gives a condition assessment, however, the size of units varies greatly depending on the types of management and the conservation interest.

Features are displayed on the SSSI Impact Zones and Units map on **page 86**

ID: -
 Location: 1546m S
 SSSI name: Rochdale Canal
 Unit name: Failsworth
 Broad habitat: Standing Open Water And Canals
 Condition: Unfavourable - Recovering
 Reportable features:

Feature name	Feature condition	Date of assessment
Population of Schedule 8 plant - Luronium natans, Floating Water-plantain	Unfavourable - Recovering	25/11/2010



ID: -
Location: 1861m E
SSSI name: Rochdale Canal
Unit name: Failsworth
Broad habitat: Standing Open Water And Canals
Condition: Unfavourable - Recovering
Reportable features:

Feature name	Feature condition	Date of assessment
Population of Schedule 8 plant - Luronium natans, Floating Water-plantain	Unfavourable - Recovering	25/11/2010

This data is sourced from Natural England and Natural Resources Wales.



11 Visual and cultural designations



- Site Outline
- Search buffers in metres (m)
- Listed buildings
- Conservation areas
- Conservation areas - no data
- National Parks
- Areas of Outstanding Natural Beauty
- Registered parks and gardens
- Scheduled Monuments
- World Heritage Sites

11.1 World Heritage Sites

Records within 250m

0

Sites designated for their globally important cultural or natural interest requiring appropriate management and protection measures. World Heritage Sites are designated to meet the UK's commitments under the World Heritage Convention.

This data is sourced from Historic England, Cadw and Historic Environment Scotland.

11.2 Area of Outstanding Natural Beauty

Records within 250m

0

Areas of Outstanding Natural Beauty (AONB) are conservation areas, chosen because they represent 18% of the finest countryside. Each AONB has been designated for special attention because of the quality of their flora, fauna, historical and cultural associations, and/or scenic views. The National Parks and Access to the Countryside Act of 1949 created AONBs and the Countryside and Rights of Way Act, 2000 added further regulation and protection. There are likely to be restrictions to some developments within these areas.

This data is sourced from Natural England, Natural Resources Wales and Scottish Natural Heritage.

11.3 National Parks

Records within 250m

0

In England and Wales, the purpose of National Parks is to conserve and enhance landscapes within the countryside whilst promoting public enjoyment of them and having regard for the social and economic well-being of those living within them. In Scotland National Parks have the additional purpose of promoting the sustainable use of the natural resources of the area and the sustainable social and economic development of its communities. The National Parks and Access to the Countryside Act 1949 established the National Park designation in England and Wales, and The National Parks (Scotland) Act 2000 in Scotland.

This data is sourced from Natural England, Natural Resources Wales and the Scottish Government.

11.4 Listed Buildings

Records within 250m

7

Buildings listed for their special architectural or historical interest. Building control in the form of 'listed building consent' is required in order to make any changes to that building which might affect its special interest. Listed buildings are graded to indicate their relative importance, however building controls apply to all buildings equally, irrespective of their grade, and apply to the interior and exterior of the building in its entirety, together with any curtilage structures.

Features are displayed on the Visual and cultural designations map on **page 89**

ID	Location	Name	Grade	Reference Number	Listed date
1	111m W	Hope Chapel and Parsons House Parson's House, Central Rochdale, Rochdale, OL12	II*	1057694	12/02/1985
3	180m S	1 and 3, Whitehall Street (See Details For Further Address information), Milkstone and Deepdish, Rochdale, OL12	II	1084259	12/02/1985
4	182m SE	Ukrainian Catholic Church of Saint Mary, Central Rochdale, Rochdale, OL16	II	1346258	12/02/1985



ID	Location	Name	Grade	Reference Number	Listed date
5	222m S	128, Yorkshire Street, Milkstone and Deeplish, Rochdale, OL16	II	1084226	16/03/1984
6	233m SE	170, 172 and 174, Yorkshire Street, Central Rochdale, Rochdale, OL16	II	1346257	12/02/1985
8	241m SE	Town Head House Department of Social Services, Town Head offices, Milkstone and Deeplish, Rochdale, OL16	II	1084282	12/02/1985
9	246m E	188a, 190 and 190a, Yorkshire Street (See Details For Further Address information), Central Rochdale, Rochdale, OL16	II	1084227	12/02/1985

This data is sourced from Historic England, Cadw and Historic Environment Scotland.

11.5 Conservation Areas

Records within 250m

2

Local planning authorities are obliged to designate as conservation areas any parts of their own area that are of special architectural or historic interest, the character and appearance of which it is desirable to preserve or enhance. Designation of a conservation area gives broader protection than the listing of individual buildings. All the features within the area, listed or otherwise, are recognised as part of its character. Conservation area designation is the means of recognising the importance of all factors and of ensuring that planning decisions address the quality of the landscape in its broadest sense.

Features are displayed on the Visual and cultural designations map on **page 89**

ID	Location	Name	District	Date of designation
2	132m S	Town Head	Rochdale	2008
7	239m SW	Toad Lane	Rochdale	23/11/1977

This data is sourced from Historic England, Cadw and Historic Environment Scotland.

11.6 Scheduled Ancient Monuments

Records within 250m

0

A scheduled monument is an historic building or site that is included in the Schedule of Monuments kept by the Secretary of State for Digital, Culture, Media and Sport. The regime is set out in the Ancient Monuments and Archaeological Areas Act 1979. The Schedule of Monuments has c.20,000 entries and includes sites such as Roman remains, burial mounds, castles, bridges, earthworks, the remains of deserted villages and industrial sites. Monuments are not graded, but all are, by definition, considered to be of national importance.

This data is sourced from Historic England, Cadw and Historic Environment Scotland.



11.7 Registered Parks and Gardens

Records within 250m


0

Parks and gardens assessed to be of particular interest and of special historic interest. The emphasis being on 'designed' landscapes, rather than on planting or botanical importance. Registration is a 'material consideration' in the planning process, meaning that planning authorities must consider the impact of any proposed development on the special character of the landscape.

This data is sourced from Historic England, Cadw and Historic Environment Scotland.



12 Agricultural designations



- Site Outline
- Search buffers in metres (m)
- Grade 1 - excellent quality
- Grade 2 - very good quality
- Grade 3 - good to moderate quality
- Grade 3a - good quality
- Grade 3b - moderate quality
- Grade 4 - poor quality
- Grade 5 - very poor quality
- Non-agricultural land
- Urban land
- Exclusion land
- Tree felling licences
- Open Access land

12.1 Agricultural Land Classification

Records within 250m

1

Classification of the quality of agricultural land taking into consideration multiple factors including climate, physical geography and soil properties. It should be noted that the categories for the grading of agricultural land are not consistent across England, Wales and Scotland.

Features are displayed on the Agricultural designations map on **page 93**

ID	Location	Classification	Description
1	On site	Urban	-

This data is sourced from Natural England.



12.2 Open Access Land

Records within 250m**0**

The Countryside and Rights of Way Act 2000 (CROW Act) gives a public right of access to land without having to use paths. Access land includes mountains, moors, heaths and downs that are privately owned. It also includes common land registered with the local council and some land around the England Coast Path. Generally permitted activities on access land are walking, running, watching wildlife and climbing.

This data is sourced from Natural England and Natural Resources Wales.

12.3 Tree Felling Licences

Records within 250m**0**

Felling Licence Application (FLA) areas approved by Forestry Commission England. Anyone wishing to fell trees must ensure that a licence or permission under a grant scheme has been issued by the Forestry Commission before any felling is carried out or that one of the exceptions apply.

This data is sourced from the Forestry Commission.

12.4 Environmental Stewardship Schemes

Records within 250m**0**

Environmental Stewardship covers a range of schemes that provide financial incentives to farmers, foresters and land managers to look after and improve the environment. The schemes identified may be historical schemes that have now expired, or may still be active.

This data is sourced from Natural England.

12.5 Countryside Stewardship Schemes

Records within 250m**0**

Countryside Stewardship covers a range of schemes that provide financial incentives to farmers, foresters and land managers to look after and improve the environment. Main objectives are to improve the farmed environment for wildlife and to reduce diffuse water pollution.

This data is sourced from Natural England.

13 Habitat designations



- Site Outline
- Search buffers in metres (m)
- Priority Habitat Inventory
- Open Mosaic Habitat
- Limestone Pavement Orders
- Habitat Networks
- Primary Habitat
- Restorable Habitat
- Associated Habitats
- Habitat Restoration-Creation
- Network Enhancement Zone 1
- Network Enhancement Zone 2

13.1 Priority Habitat Inventory

Records within 250m

0

Habitats of principal importance as named under Natural Environment and Rural Communities Act (2006) Section 41.

This data is sourced from Natural England.

13.2 Habitat Networks

Records within 250m

0

Habitat networks for 18 priority habitat networks (based primarily, but not exclusively, on the priority habitat inventory) and areas suitable for the expansion of networks through restoration and habitat creation.

This data is sourced from Natural England.



13.3 Open Mosaic Habitat

Records within 250m

1

Sites verified as Open Mosaic Habitat. Mosaic habitats are brownfield sites that are identified under the UK Biodiversity Action Plan as a priority habitat due to the habitat variation within a single site, supporting an array of invertebrates.

Features are displayed on the Habitat designations map on **page 95**

ID	Location	Site reference	Identification confidence	Primary source	Secondary source	Tertiary source
1	127m SW	NLUD Ref: 422500030	Low	National Land Use Database - Previously Developed Land	UK Perspectives Aerial Photography	-

This data is sourced from Natural England.

13.4 Limestone Pavement Orders


Records within 250m

0

Limestone pavements are outcrops of limestone where the surface has been worn away by natural means over millennia. These rocks have the appearance of paving blocks, hence their name. Not only do they have geological interest, they also provide valuable habitats for wildlife. These habitats are threatened due to their removal for use in gardens and water features. Many limestone pavements have been designated as SSSIs which affords them some protection. In addition, Section 34 of the Wildlife and Countryside Act 1981 gave them additional protection via the creation of Limestone Pavement Orders, which made it a criminal offence to remove any part of the outcrop. The associated Limestone Pavement Priority Habitat is part of the UK Biodiversity Action Plan priority habitat in England.

This data is sourced from Natural England.

14 Geology 1:10,000 scale - Availability



— Site Outline
Search buffers in metres (m)

- Full coverage
- Partial coverage
- No coverage

14.1 10k Availability

Records within 500m

2

An indication on the coverage of 1:10,000 scale geology data for the site, the most detailed dataset provided by the British Geological Survey. Either 'Full', 'Partial' or 'No coverage' for each geological theme.


Features are displayed on the Geology 1:10,000 scale - Availability map on **page 97**

ID	Location	Artificial	Superficial	Bedrock	Mass movement	Sheet No.
1	On site	Full	Full	Full	Full	SD81SE
2	179m E	Full	Full	Full	Full	SD91SW

This data is sourced from the British Geological Survey.



Geology 1:10,000 scale - Artificial and made ground



— Site Outline
Search buffers in metres (m)

- Reclaimed ground
- Made ground
- Worked ground
- Infilled ground
- Disturbed ground
- Landscaped ground

14.2 Artificial and made ground (10k)

Records within 500m

4

Details of made, worked, infilled, disturbed and landscaped ground at 1:10,000 scale. Artificial ground can be associated with potentially contaminated material, unpredictable engineering conditions and instability.

Features are displayed on the Geology 1:10,000 scale - Artificial and made ground map on **page 98**


ID	Location	LEX Code	Description	Rock description
1	350m NE	WMGR-ARTDP	Infilled Ground	Artificial Deposit
A	384m NE	WMGR-ARTDP	Infilled Ground	Artificial Deposit
A	440m N	WGR-VOID	Worked Ground (Undivided)	Void
A	471m NE	WGR-VOID	Worked Ground (Undivided)	Void



This data is sourced from the British Geological Survey.



Geology 1:10,000 scale - Superficial



Site Outline

Search buffers in metres (m)

Landslip (10k)

Superficial geology (10k)
Please see table for more details.

14.3 Superficial geology (10k)

Records within 500m

8

Superficial geological deposits at 1:10,000 scale. Also known as 'drift', these are the youngest geological deposits, formed during the Quaternary. They rest on older deposits or rocks referred to as bedrock.

Features are displayed on the Geology 1:10,000 scale - Superficial map on **page 100**

ID	Location	LEX Code	Description	Rock description
1	On site	TILLD-DMTN	Till, Devensian - Diamicton	Diamicton
2	120m S	GFDUD-XSV	Glaciofluvial Deposits, Devensian - Sand And Gravel	Sand And Gravel
3	179m E	TILLD-DMTN	Till, Devensian - Diamicton	Diamicton



ID	Location	LEX Code	Description	Rock description
4	203m SE	GFDUD-XSV	Glaciofluvial Deposits, Devensian - Sand And Gravel	Sand And Gravel
5	300m SE	TILLD-DMTN	Till, Devensian - Diamicton	Diamicton
6	301m SE	TILLD-DMTN	Till, Devensian - Diamicton	Diamicton
7	370m S	ALV-XCZSV	Alluvium - Clay, Silt, Sand And Gravel	Clay, Silt, Sand And Gravel
8	395m SE	ALV-XCZSV	Alluvium - Clay, Silt, Sand And Gravel	Clay, Silt, Sand And Gravel

This data is sourced from the British Geological Survey.

14.4 Landslip (10k)

Records within 500m


0

Mass movement deposits on BGS geological maps at 1:10,000 scale. Primarily superficial deposits that have moved down slope under gravity to form landslips. These affect bedrock, other superficial deposits and artificial ground.

This data is sourced from the British Geological Survey.



Geology 1:10,000 scale - Bedrock



Site Outline

Search buffers in metres (m)

..... Bedrock faults and other linear features (10k)

Bedrock geology (10k)
Please see table for more details.

14.5 Bedrock geology (10k)

Records within 500m

7

Bedrock geology at 1:10,000 scale. The main mass of rocks forming the Earth and present everywhere, whether exposed at the surface in outcrops or concealed beneath superficial deposits or water.

Features are displayed on the Geology 1:10,000 scale - Bedrock map on **page 102**

ID	Location	LEX Code	Description	Rock age
1	On site	OL-SDST	Old Lawrence Rock - Sandstone	Langsettian Sub-age
2	87m NW	PLCM-MDSS	Pennine Lower Coal Measures Formation - Mudstone, Siltstone And Sandstone	Langsettian Sub-age
3	98m SW	PLCM-MDSS	Pennine Lower Coal Measures Formation - Mudstone, Siltstone And Sandstone	Langsettian Sub-age



ID	Location	LEX Code	Description	Rock age
4	179m E	OL-SDST	Old Lawrence Rock - Sandstone	Langsettian Sub-age
5	440m NE	PLCM-MDSS	Pennine Lower Coal Measures Formation - Mudstone, Siltstone And Sandstone	Langsettian Sub-age
6	468m NE	PLCM-MDSS	Pennine Lower Coal Measures Formation - Mudstone, Siltstone And Sandstone	Langsettian Sub-age
7	482m SE	PLCM-MDSS	Pennine Lower Coal Measures Formation - Mudstone, Siltstone And Sandstone	Langsettian Sub-age

This data is sourced from the British Geological Survey.

14.6 Bedrock faults and other linear features (10k)

Records within 500m


0

Linear features at the ground or bedrock surface at 1:10,000 scale of six main types; rock, fault, fold axis, mineral vein, alteration area or landform. Features are either observed or inferred, and relate primarily to bedrock.

This data is sourced from the British Geological Survey.



15 Geology 1:50,000 scale - Availability



— Site Outline
Search buffers in metres (m)

□ Geological map tile

15.1 50k Availability

Records within 500m

1

An indication on the coverage of 1:50,000 scale geology data for the site. Either 'Full' or 'No coverage' for each geological theme.

Features are displayed on the Geology 1:50,000 scale - Availability map on **page 104**

ID	Location	Artificial	Superficial	Bedrock	Mass movement	Sheet No.
1	On site	No coverage	Full	Full	Full	EW076_rochdale_v4

This data is sourced from the British Geological Survey.



Geology 1:50,000 scale - Artificial and made ground

15.2 Artificial and made ground (50k)

Records within 500m

0

Details of made, worked, infilled, disturbed and landscaped ground at 1:50,000 scale. Artificial ground can be associated with potentially contaminated material, unpredictable engineering conditions and instability.

This data is sourced from the British Geological Survey.

15.3 Artificial ground permeability (50k)

Records within 50m


0

A qualitative classification of estimated rates of vertical movement of water from the ground surface through the unsaturated zone of any artificial deposits (the zone between the land surface and the water table).

This data is sourced from the British Geological Survey.



Geology 1:50,000 scale - Superficial



Site Outline

Search buffers in metres (m)

Landslip (50k)

Superficial geology (50k)
Please see table for more details.

15.4 Superficial geology (50k)

Records within 500m

4

Superficial geological deposits at 1:50,000 scale. Also known as 'drift', these are the youngest geological deposits, formed during the Quaternary. They rest on older deposits or rocks referred to as bedrock.

Features are displayed on the Geology 1:50,000 scale - Superficial map on **page 106**

ID	Location	LEX Code	Description	Rock description
1	On site	TILLD-DMTN	TILL, DEVENSIAN	DIAMICTON
2	126m S	GFDUD-XSV	GLACIOFLUVIAL DEPOSITS, DEVENSIAN	SAND AND GRAVEL
3	301m SE	TILLD-DMTN	TILL, DEVENSIAN	DIAMICTON



ID	Location	LEX Code	Description	Rock description
4	378m S	ALV-XCZSV	ALLUVIUM	CLAY, SILT, SAND AND GRAVEL

This data is sourced from the British Geological Survey.

15.5 Superficial permeability (50k)

Records within 50m	1
---------------------------	----------

A qualitative classification of estimated rates of vertical movement of water from the ground surface through the unsaturated zone of any superficial deposits (the zone between the land surface and the water table).

Location	Flow type	Maximum permeability	Minimum permeability
On site	Mixed	High	Low

This data is sourced from the British Geological Survey.

15.6 Landslip (50k)

Records within 500m	0
----------------------------	----------

Mass movement deposits on BGS geological maps at 1:50,000 scale. Primarily superficial deposits that have moved down slope under gravity to form landslips. These affect bedrock, other superficial deposits and artificial ground.

This data is sourced from the British Geological Survey.


15.7 Landslip permeability (50k)

Records within 50m	0
---------------------------	----------

A qualitative classification of estimated rates of vertical movement of water from the ground surface through the unsaturated zone of any landslip deposits (the zone between the land surface and the water table).

This data is sourced from the British Geological Survey.

Geology 1:50,000 scale - Bedrock



— Site Outline

Search buffers in metres (m)

.... Bedrock faults and other linear features (50k)

Bedrock geology (50k)
Please see table for more details.

15.8 Bedrock geology (50k)

Records within 500m

4

Bedrock geology at 1:50,000 scale. The main mass of rocks forming the Earth and present everywhere, whether exposed at the surface in outcrops or concealed beneath superficial deposits or water.

Features are displayed on the Geology 1:50,000 scale - Bedrock map on **page 108**

ID	Location	LEX Code	Description	Rock age
1	On site	OL-SDST	OLD LAWRENCE ROCK - SANDSTONE	WESTPHALIAN
2	86m NW	PLCM-MDSS	PENNINE LOWER COAL MEASURES FORMATION - MUDSTONE, SILTSTONE AND SANDSTONE	WESTPHALIAN
3	98m SW	PLCM-MDSS	PENNINE LOWER COAL MEASURES FORMATION - MUDSTONE, SILTSTONE AND SANDSTONE	WESTPHALIAN



ID	Location	LEX Code	Description	Rock age
4	440m NE	PLCM-MDSS	PENNINE LOWER COAL MEASURES FORMATION - MUDSTONE, SILTSTONE AND SANDSTONE	WESTPHALIAN

This data is sourced from the British Geological Survey.

15.9 Bedrock permeability (50k)

Records within 50m

1

A qualitative classification of estimated rates of vertical movement of water from the ground surface through the unsaturated zone of bedrock (the zone between the land surface and the water table).

Location	Flow type	Maximum permeability	Minimum permeability
On site	Fracture	High	Moderate

This data is sourced from the British Geological Survey.

15.10 Bedrock faults and other linear features (50k)

Records within 500m

0

Linear features at the ground or bedrock surface at 1:50,000 scale of six main types; rock, fault, fold axis, mineral vein, alteration area or landform. Features are either observed or inferred, and relate primarily to bedrock.

This data is sourced from the British Geological Survey.



16 Boreholes



— Site Outline
Search buffers in metres (m)

- Confidential
- 0 - 10m
- 10 - 30m
- 30m+
- Unknown

© Crown copyright and database rights 2023. Ordnance Survey licence 100035207

16.1 BGS Boreholes

Records within 250m

11

The Single Onshore Boreholes Index (SOBI); an index of over one million records of boreholes, shafts and wells from all forms of drilling and site investigation work held by the British Geological Survey. Covering onshore and nearshore boreholes dating back to at least 1790 and ranging from one to several thousand metres deep.

Features are displayed on the Boreholes map on **page 110**

ID	Location	Grid reference	Name	Length	Confidential	Web link
1	On site	389800 413900	HOLCROFT CASTING & FORGING LTD (2 WELLS &)	-1.0	N	30282
A	123m SE	389900 413800	ROCHDALE GSC. 4	24.95	N	29778




ID	Location	Grid reference	Name	Length	Confidential	Web link
A	123m SE	389900 413800	ROCHDALE GSC. 2	25.0	N	29777
A	123m SE	389900 413800	ROCHDALE GSC. 6	16.0	N	29779
A	123m SE	389900 413800	ROCHDALE GSC. 9	16.0	N	29782
A	123m SE	389900 413800	ROCHDALE GSC. 8	16.0	N	29781
A	123m SE	389900 413800	ROCHDALE GSC. 7	15.9	N	29780
2	211m NW	389570 414010	ROCHDALE INFIRMARY BH8	4.3	N	30218
3	218m W	389540 413850	FALINGE RD ROCHDALE 2	6.24	N	29899
4	219m NW	389600 414060	ROCHDALE INFIRMARY BH11	6.25	N	30221
5	244m SW	389540 413780	FALINGE RD ROCHDALE 4	4.88	N	29901

This data is sourced from the British Geological Survey.



17 Natural ground subsidence - Shrink swell clays



- Site Outline**
- Search buffers in metres (m)
- ☐ No data
 - ☐ Negligible
 - ☒ Very low
 - ☐ Low
 - ☐ Moderate
 - ☐ High

17.1 Shrink swell clays

Records within 50m

1

The potential hazard presented by soils that absorb water when wet (making them swell), and lose water as they dry (making them shrink). This shrink-swell behaviour is controlled by the type and amount of clay in the soil, and by seasonal changes in the soil moisture content (related to rainfall and local drainage).


Features are displayed on the Natural ground subsidence - Shrink swell clays map on **page 112**

Location	Hazard rating	Details
On site	Very low	Ground conditions predominantly low plasticity.

This data is sourced from the British Geological Survey.



Natural ground subsidence - Running sands



— Site Outline
Search buffers in metres (m)

- ☐ No data
- ☐ Negligible
- ☒ Very low
- ☐ Low
- ☐ Moderate
- ☐ High

© Crown copyright and database rights 2023. Ordnance Survey licence 100035207

17.2 Running sands

Records within 50m

1

The potential hazard presented by rocks that can contain loosely-packed sandy layers that can become fluidised by water flowing through them. Such sands can 'run', removing support from overlying buildings and causing potential damage.


Features are displayed on the Natural ground subsidence - Running sands map on **page 113**

Location	Hazard rating	Details
On site	Very low	Running sand conditions are unlikely. No identified constraints on land use due to running conditions unless water table rises rapidly.

This data is sourced from the British Geological Survey.



Natural ground subsidence - Compressible deposits



— Site Outline
Search buffers in metres (m)

- ☐ No data
- ☐ Negligible
- ☐ Very low
- ☐ Low
- ☐ Moderate
- ☐ High

© Crown copyright and database rights 2023. Ordnance Survey licence 100035207

17.3 Compressible deposits

Records within 50m

1

The potential hazard presented by types of ground that may contain layers of very soft materials like clay or peat and may compress if loaded by overlying structures, or if the groundwater level changes, potentially resulting in depression of the ground and disturbance of foundations.


Features are displayed on the Natural ground subsidence - Compressible deposits map on **page 114**

Location	Hazard rating	Details
On site	Negligible	Compressible strata are not thought to occur.

This data is sourced from the British Geological Survey.



Natural ground subsidence - Collapsible deposits



— Site Outline
Search buffers in metres (m)

- ☐ No data
- ☐ Negligible
- ☒ Very low
- ☐ Low
- ☐ Moderate
- ☐ High

© Crown copyright and database rights 2023. Ordnance Survey licence 100035207

17.4 Collapsible deposits

Records within 50m

1

The potential hazard presented by natural deposits that could collapse when a load (such as a building) is placed on them or they become saturated with water.



Features are displayed on the Natural ground subsidence - Collapsible deposits map on **page 115**

Location	Hazard rating	Details
On site	Very low	Deposits with potential to collapse when loaded and saturated are unlikely to be present.

This data is sourced from the British Geological Survey.



Natural ground subsidence - Landslides



17.5 Landslides

Records within 50m

1

The potential for landsliding (slope instability) to be a hazard assessed using 1:50,000 scale digital maps of superficial and bedrock deposits, combined with information from the BGS National Landslide Database and scientific and engineering reports.



Features are displayed on the Natural ground subsidence - Landslides map on **page 116**

Location	Hazard rating	Details
On site	Very low	Slope instability problems are not likely to occur but consideration to potential problems of adjacent areas impacting on the site should always be considered.

This data is sourced from the British Geological Survey.



Natural ground subsidence - Ground dissolution of soluble rocks



17.6 Ground dissolution of soluble rocks

Records within 50m

1

The potential hazard presented by ground dissolution, which occurs when water passing through soluble rocks produces underground cavities and cave systems. These cavities reduce support to the ground above and can cause localised collapse of the overlying rocks and deposits.


Features are displayed on the Natural ground subsidence - Ground dissolution of soluble rocks map on **page 117**

Location	Hazard rating	Details
On site	Negligible	Soluble rocks are either not thought to be present within the ground, or not prone to dissolution. Dissolution features are unlikely to be present.

This data is sourced from the British Geological Survey.



18 Mining, ground workings and natural cavities



- Site Outline
- Search buffers in metres (m)
- Natural cavities (Area)
- Natural cavities (Point)
- BritPits
- Surface ground workings
- Underground workings
- Historical Mineral Planning Areas
- Mining Cavities
- Non Coal Mining
 - Sporadic underground mining of restricted extent possible
 - Localised small scale underground mining possible
 - Small scale mining possible
 - Underground mining known or likely within or in close proximity
 - Underground mining known within or in very close proximity

18.1 Natural cavities

Records within 500m

0

Industry recognised national database of natural cavities. Sinkholes and caves are formed by the dissolution of soluble rock, such as chalk and limestone, gulls and fissures by cambering. Ground instability can result from movement of loose material contained within these cavities, often triggered by water.

This data is sourced from Stantec UK Ltd.

18.2 BritPits

Records within 500m

2

BritPits (an abbreviation of British Pits) is a database maintained by the British Geological Survey of currently active and closed surface and underground mineral workings. Details of major mineral handling sites, such as wharfs and rail depots are also held in the database.

Features are displayed on the Mining, ground workings and natural cavities map on **page 119**

ID	Location	Details	Description
B	171m N	Name: Green Hayes Clay Pit Address: Town Head, ROCHDALE, Lancashire Commodity: Clay & Shale Status: Ceased	Type: A surface mineral working. It may be termed Quarry, Sand Pit, Clay Pit or Opencast Coal Site Status description: Site which, at date of entry, has ceased to extract minerals. May be considered as Closed by operator. May be considered to have Active, Dormant or Expired planning permissions by Mineral Planning Authority
E	474m E	Name: Rock House Sand Pit Address: Town Head, ROCHDALE, Lancashire Commodity: Sand Status: Ceased	Type: A surface mineral working. It may be termed Quarry, Sand Pit, Clay Pit or Opencast Coal Site Status description: Site which, at date of entry, has ceased to extract minerals. May be considered as Closed by operator. May be considered to have Active, Dormant or Expired planning permissions by Mineral Planning Authority

This data is sourced from the British Geological Survey.

18.3 Surface ground workings

Records within 250m

7

Historical land uses identified from Ordnance Survey mapping that involved ground excavation at the surface. These features may or may not have been subsequently backfilled.

Features are displayed on the Mining, ground workings and natural cavities map on **page 119**

ID	Location	Land Use	Year of mapping	Mapping scale
A	32m E	Ponds	1851	1:10560
A	60m E	Reservoir	1949	1:10560
A	65m E	Reservoir	1938	1:10560
A	66m E	Reservoir	1928	1:10560
A	66m E	Reservoir	1908	1:10560
B	141m N	Pond	1851	1:10560



ID	Location	Land Use	Year of mapping	Mapping scale
B	155m N	Clay Pit	1851	1:10560

This data is sourced from Ordnance Survey/Groundsure.

18.4 Underground workings

Records within 1000m

3

Historical land uses identified from Ordnance Survey mapping that indicate the presence of underground workings e.g. mine shafts.

Features are displayed on the Mining, ground workings and natural cavities map on **page 119**

ID	Location	Land Use	Year of mapping	Mapping scale
L	638m N	Unspecified Old Shaft	1928	1:10560
L	649m N	Unspecified Disused Shaft	1968	1:10560
-	662m N	Unspecified Old Shaft	1890	1:10560

This data is sourced from Ordnance Survey/Groundsure.

18.5 Historical Mineral Planning Areas

Records within 500m

0

Boundaries of mineral planning permissions for England and Wales. This data was collated between the 1940s (and retrospectively to the 1930s) and the mid 1980s. The data includes permitted, withdrawn and refused permissions.

This data is sourced from the British Geological Survey.

18.6 Non-coal mining

Records within 1000m

0

The potential for historical non-coal mining to have affected an area. The assessment is drawn from expert knowledge and literature in addition to the digital geological map of Britain. Mineral commodities may be divided into seven general categories - vein minerals, chalk, oil shale, building stone, bedded ores, evaporites and 'other' commodities (including ball clay, jet, black marble, graphite and chert).

This data is sourced from the British Geological Survey.



18.7 Mining cavities

Records within 1000m**0**

Industry recognised national database of mining cavities. Degraded mines may result in hazardous subsidence (crown holes). Climatic conditions and water escape can also trigger subsidence over mine entrances and workings.

This data is sourced from Stantec UK Ltd.

18.8 JPB mining areas

Records on site**0**

Areas which could be affected by former coal and other mining. This data includes some mine plans unavailable to the Coal Authority.

This data is sourced from Johnson Poole and Bloomer.

18.9 Coal mining

Records on site**1**

Areas which could be affected by past, current or future coal mining.

Location	Details
On site	The site is located within a coal mining area as defined by the Coal Authority. A Consultants Coal Mining Report is recommended to further assess coal mining issues at the site. This can be ordered directly through Groundsure or your preferred search provider.

This data is sourced from the Coal Authority.

18.10 Brine areas

Records on site**0**

The Cheshire Brine Compensation District indicates areas that may be affected by salt and brine extraction in Cheshire and where compensation would be available where damage from this mining has occurred. Damage from salt and brine mining can still occur outside this district, but no compensation will be available.

This data is sourced from the Cheshire Brine Subsidence Compensation Board.



18.11 Gypsum areas

Records on site	0
-----------------	---

Generalised areas that may be affected by gypsum extraction.

This data is sourced from British Gypsum.

18.12 Tin mining

Records on site	0
-----------------	---

Generalised areas that may be affected by historical tin mining.

This data is sourced from Groundsure.

18.13 Clay mining


Records on site	0
-----------------	---

Generalised areas that may be affected by kaolin and ball clay extraction.

This data is sourced from the Kaolin and Ball Clay Association (UK).



19 Radon



— Site Outline
Search buffers in metres (m)

- Greater than 30%
- Between 10% and 30%
- Between 5% and 10%
- Between 3% and 5%
- Between 1% and 3%
- Less than 1%

19.1 Radon

Records on site

1

The Radon Potential data classifies areas based on their likelihood of a property having a radon level at or above the Action Level in Great Britain. The dataset is intended for use at 1:50,000 scale and was derived from both geological assessments and indoor radon measurements (more than 560,000 records). A minimum 50m buffer should be considered when searching the maps, as the smallest detectable feature at this scale is 50m. The findings of this section should supersede any estimations derived from the Indicative Atlas of Radon in Great Britain (1:100,000 scale).

Features are displayed on the Radon map on **page 124**

Location	Estimated properties affected	Radon Protection Measures required
On site	Less than 1%	None



This data is sourced from the British Geological Survey and UK Health Security Agency.



20 Soil chemistry

20.1 BGS Estimated Background Soil Chemistry

Records within 50m

1

The estimated values provide the likely background concentration of the potentially harmful elements Arsenic, Cadmium, Chromium, Lead and Nickel in topsoil. The values are estimated primarily from rural topsoil data collected at a sample density of approximately 1 per 2 km². In areas where rural soil samples are not available, estimation is based on stream sediment data collected from small streams at a sampling density of 1 per 2.5 km²; this is the case for most of Scotland, Wales and southern England. The stream sediment data are converted to soil-equivalent concentrations prior to the estimation.

Location	Arsenic	Bioaccessible Arsenic	Lead	Bioaccessible Lead	Cadmium	Chromium	Nickel
On site	15 - 25 mg/kg	No data	600 - 1200 mg/kg	360 - 720 mg/kg	3.0 - 6.0 mg/kg	60 - 90 mg/kg	30 - 45 mg/kg

This data is sourced from the British Geological Survey.

20.2 BGS Estimated Urban Soil Chemistry

Records within 50m

0

Estimated topsoil chemistry of Arsenic, Cadmium, Chromium, Copper, Nickel, Lead, Tin and Zinc and bioaccessible Arsenic and Lead in 23 urban centres across Great Britain. These estimates are derived from interpolation of the measured urban topsoil data referred to above and provide information across each city between the measured sample locations (4 per km²).

This data is sourced from the British Geological Survey.

20.3 BGS Measured Urban Soil Chemistry

Records within 50m

0

The locations and measured total concentrations (mg/kg) of Arsenic, Cadmium, Chromium, Copper, Nickel, Lead, Tin and Zinc in urban topsoil samples from 23 urban centres across Great Britain. These are collected at a sample density of 4 per km².

This data is sourced from the British Geological Survey.



21 Railway infrastructure and projects

21.1 Underground railways (London)

Records within 250m**0**

Details of all active London Underground lines, including approximate tunnel roof depth and operational hours.

This data is sourced from publicly available information by Groundsure.

21.2 Underground railways (Non-London)

Records within 250m**0**

Details of the Merseyrail system, the Tyne and Wear Metro and the Glasgow Subway. Not all parts of all systems are located underground. The data contains location information only and does not include a depth assessment.

This data is sourced from publicly available information by Groundsure.

21.3 Railway tunnels

Records within 250m**0**

Railway tunnels taken from contemporary Ordnance Survey mapping.

This data is sourced from the Ordnance Survey.

21.4 Historical railway and tunnel features

Records within 250m**0**

Railways and tunnels digitised from historical Ordnance Survey mapping as scales of 1:1,250, 1:2,500, 1:10,000 and 1:10,560.

This data is sourced from Ordnance Survey/Groundsure.

21.5 Royal Mail tunnels

Records within 250m**0**

The Post Office Railway, otherwise known as the Mail Rail, is an underground railway running through Central London from Paddington Head District Sorting Office to Whitechapel Eastern Head Sorting Office. The line is 10.5km long. The data includes details of the full extent of the tunnels, the depth of the tunnel, and the depth to track level.



This data is sourced from Groundsure/the Postal Museum.

21.6 Historical railways

Records within 250m

0

Former railway lines, including dismantled lines, abandoned lines, disused lines, historic railways and razed lines.

This data is sourced from OpenStreetMap.

21.7 Railways

Records within 250m

0

Currently existing railway lines, including standard railways, narrow gauge, funicular, trams and light railways.

This data is sourced from Ordnance Survey and OpenStreetMap.

21.8 Crossrail 1

Records within 500m

0

The Crossrail railway project links 41 stations over 100 kilometres from Reading and Heathrow in the west, through underground sections in central London, to Shenfield and Abbey Wood in the east.

This data is sourced from publicly available information by Groundsure.

21.9 Crossrail 2

Records within 500m

0

Crossrail 2 is a proposed railway linking the national rail networks in Surrey and Hertfordshire via an underground tunnel through London.

This data is sourced from publicly available information by Groundsure.

21.10 HS2

Records within 500m

0

HS2 is a proposed high speed rail network running from London to Manchester and Leeds via Birmingham. Main civils construction on Phase 1 (London to Birmingham) of the project began in 2019, and it is currently anticipated that this phase will be fully operational by 2026. Construction on Phase 2a (Birmingham to Crewe) is anticipated to commence in 2021, with the service fully operational by 2027. Construction on Phase 2b (Crewe to Manchester and Birmingham to Leeds) is scheduled to begin in 2023 and be operational by 2033.

This data is sourced from HS2 Ltd.




Data providers

Groundsure works with respected data providers to bring you the most relevant and accurate information. To find out who they are and their areas of expertise see <https://www.groundsure.com/sources-reference>.

Terms and conditions

Groundsure's Terms and Conditions can be accessed at this link: <https://www.groundsure.com/terms-and-conditions-jan-2020/>.





Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY


Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: 1056 Scale Town Plan

Map date: 1851

Scale: 1:1,056

Printed at: 1:1,056



Surveyed N/A
Revised N/A
Edition N/A
Copyright N/A
Levelled N/A



Produced by
Groundsure Insights
www.groundsure.com




Supplied by:
www.centremapslive.com
groundsure@centremaps.com


© Crown copyright and database rights 2018 Ordnance Survey 1 00035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsure_legend.pdf







Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY


Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: County Series Town Plan

Map date: 1892


Scale: 1:500

Printed at: 1:1,000



Surveyed 1892
Revised N/A
Edition N/A
Copyright N/A
Levelled N/A

Surveyed 1892
Revised N/A
Edition N/A
Copyright N/A
Levelled N/A



Surveyed 1892
Revised N/A
Edition N/A
Copyright N/A
Levelled N/A

Surveyed 1892
Revised N/A
Edition N/A
Copyright N/A
Levelled N/A



Produced by
Groundsure Insights
www.groundsure.com




Supplied by:
www.centremapslive.com
groundsure@centremaps.com

© Crown copyright and database rights 2018 Ordnance Survey 1 00035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsure_legend.pdf



0 50m



Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY


Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: County Series

Map date: 1910

Scale: 1:2.500

Printed at: 1:2.500



Surveyed 1910
Revised 1910
Edition N/A
Copyright N/A
Levelled N/A



Produced by
Groundsure Insights
www.groundsure.com



Supplied by:
www.centremapslive.com
groundsure@centremaps.com

© Crown copyright and database rights 2018 Ordnance Survey 1 00035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsure_legend.pdf





Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY



Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: County Series

Map date: 1930

Scale: 1:2.500

Printed at: 1:2.500



Surveyed 1930
Revised 1930
Edition N/A
Copyright N/A
Levelled N/A



Produced by
Groundsure Insights
www.groundsure.com



Supplied by:
www.centremapslive.com
groundsure@centremaps.com

© Crown copyright and database rights 2018 Ordnance Survey 1 00035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsure_legend.pdf





Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY


Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: National Grid

Map date: 1957-1959

Scale: 1:1,250

Printed at: 1:2,000



Surveyed 1958
Revised 1958
Edition N/A
Copyright 1959
Levelled N/A

Surveyed 1959
Revised 1959
Edition N/A
Copyright 1959
Levelled 1956

Surveyed 1957
Revised 1957
Edition N/A
Copyright N/A
Levelled 1928

Surveyed 1957
Revised 1957
Edition N/A
Copyright N/A
Levelled 1928



Produced by
Groundsure Insights
www.groundsure.com




Supplied by:
www.centremapslive.com
groundsure@centremaps.com


© Crown copyright and database rights 2018 Ordnance Survey 1 00035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsure_legend.pdf





Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY


Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: National Grid


Map date: 1958-1959

Scale: 1:1,250

Printed at: 1:2,000



Surveyed 1958
Revised N/A
Edition N/A
Copyright 1959
Levelled 1956



Surveyed 1957
Revised N/A
Edition N/A
Copyright 1958
Levelled 1928



Produced by
Groundsure Insights
www.groundsure.com




Supplied by:
www.centremapslive.com
groundsure@centremaps.com

© Crown copyright and database rights 2018 Ordnance Survey 1 00035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsure_legend.pdf





Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY


Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: National Grid

Map date: 1958-1959


Scale: 1:2.500

Printed at: 1:2.500



Surveyed 1959
Revised 1959
Edition N/A
Copyright N/A
Levelled N/A

Surveyed 1958
Revised 1958
Edition N/A
Copyright N/A
Levelled N/A



Surveyed 1959
Revised 1959
Edition N/A
Copyright N/A
Levelled N/A



Produced by
Groundsure Insights
www.groundsure.com




Supplied by:
www.centremapslive.com
groundsure@centremaps.com

© Crown copyright and database rights 2018 Ordnance Survey 1 00035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsure_legend.pdf





Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY


Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: National Grid

Map date: 1972-1974

Scale: 1:1,250

Printed at: 1:2,000



Surveyed N/A
Revised N/A
Edition N/A
Copyright 1974
Levelled N/A

Surveyed N/A
Revised N/A
Edition N/A
Copyright 1974
Levelled N/A



Produced by
Groundsure Insights
www.groundsure.com




Supplied by:
www.centremapslive.com
groundsure@centremaps.com


© Crown copyright and database rights 2018 Ordnance Survey 1 00035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsure_legend.pdf





Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY

Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: National Grid

Map date: 1976-1977

Scale: 1:1,250

Printed at: 1:2,000



Surveyed N/A
Revised N/A
Edition N/A
Copyright 1977
Levelled 1982

Surveyed N/A
Revised N/A
Edition N/A
Copyright 1975
Levelled N/A



Produced by
Groundsure Insights
www.groundsure.com




Supplied by:
www.centremapslive.com
groundsure@centremaps.com


© Crown copyright and database rights 2018 Ordnance Survey 1 00035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsurre_legend.pdf





Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY


Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: National Grid


Map date: 1975-1978

Scale: 1:1,250

Printed at: 1:2,000



Surveyed N/A
Revised N/A
Edition N/A
Copyright 1975
Levelled N/A



Surveyed 1957
Revised 1974
Edition N/A
Copyright 1975
Levelled 1962



Produced by
Groundsure Insights
www.groundsure.com



Supplied by:
www.centremapslive.com
groundsure@centremaps.com

© Crown copyright and database rights 2018 Ordnance Survey 1 00035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsurre_legend.pdf





Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY


Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: National Grid

Map date: 1982-1987

Scale: 1:1,250

Printed at: 1:2,000



Surveyed 1958
Revised 1981
Edition N/A
Copyright 1982
Levelled 1982

Surveyed 1956
Revised 1987
Edition N/A
Copyright 1987
Levelled 1956

Surveyed N/A
Revised N/A
Edition N/A
Copyright 1981
Levelled 1956

Surveyed 1962
Revised 1984
Edition N/A
Copyright 1984
Levelled 1962



Produced by
Groundsure Insights
www.groundsure.com




Supplied by:
www.centremapslive.com
groundsure@centremaps.com

© Crown copyright and database rights 2018 Ordnance Survey 1 00035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsurre_legend.pdf





Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY


Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: National Grid

Map date: 1985-1989

Scale: 1:1,250

Printed at: 1:2,000



Surveyed 1962
Revised 1988
Edition N/A
Copyright 1988
Levelled 1982

Surveyed 1957
Revised 1988
Edition N/A
Copyright 1989
Levelled N/A



Produced by
Groundsure Insights
www.groundsure.com




Supplied by:
www.centremapslive.com
groundsure@centremaps.com

© Crown copyright and database rights 2018 Ordnance Survey 100035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsure_legend.pdf





Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY


Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: National Grid

Map date: 1988-1992

Scale: 1:1,250

Printed at: 1:2,000



Surveyed 1992
Revised N/A
Edition N/A
Copyright 1992
Levelled N/A

Surveyed 1992
Revised N/A
Edition N/A
Copyright 1992
Levelled N/A

Surveyed 1959
Revised 1984
Edition N/A
Copyright 1988
Levelled 1958

Surveyed 1992
Revised N/A
Edition N/A
Copyright 1992
Levelled N/A



Produced by
Groundsure Insights
www.groundsure.com




Supplied by:
www.centremapslive.com
groundsure@centremaps.com

© Crown copyright and database rights 2018 Ordnance Survey 1 00035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsure_legend.pdf





Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY


Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: National Grid

Map date: 1989-1993

Scale: 1:1,250

Printed at: 1:2,000



Surveyed N/A
Revised 1989
Edition N/A
Copyright 1988
Levelled 1958

Surveyed 1993
Revised N/A
Edition N/A
Copyright 1993
Levelled N/A



Produced by
Groundsure Insights
www.groundsure.com




Supplied by:
www.centremapslive.com
groundsure@centremaps.com

© Crown copyright and database rights 2018 Ordnance Survey 1 00035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsure_legend.pdf





Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY


Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: National Grid

Map date: 1992-1993

Scale: 1:1,250

Printed at: 1:2,000



Surveyed 1992
Revised N/A
Edition N/A
Copyright 1992
Levelled N/A

Surveyed N/A
Revised N/A
Edition N/A
Copyright 1993
Levelled N/A



Produced by
Groundsure Insights
www.groundsure.com




Supplied by:
www.centremapslive.com
groundsure@centremaps.com


© Crown copyright and database rights 2018 Ordnance Survey 1 00035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsure_legend.pdf





Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY


Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: National Grid

Map date: 1995

Scale: 1:1,250

Printed at: 1:2,000



Surveyed N/A
Revised N/A
Edition N/A
Copyright 1995
Levelled N/A



Produced by
Groundsure Insights
www.groundsure.com




Supplied by:
www.centremapslive.com
groundsure@centremaps.com

© Crown copyright and database rights 2018 Ordnance Survey 1 00035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsure_legend.pdf





Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY


Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: National Grid

Map date: 1995

Scale: 1:1,250

Printed at: 1:2,000



Surveyed N/A
Revised N/A
Edition N/A
Copyright N/A
Levelled N/A



Produced by
Groundsure Insights
www.groundsure.com




Supplied by:
www.centremapslive.com
groundsure@centremaps.com


© Crown copyright and database rights 2018 Ordnance Survey 1 00035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsure_legend.pdf





Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY



Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: LandLine

Map date: 2003

Scale: 1:1,250

Printed at: 1:1,250



Produced by
Groundsure Insights
www.groundsure.com



Supplied by:
www.centremapslive.com
groundsure@centremaps.com

© Crown copyright and database rights 2018 Ordnance Survey 1 00035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsure_legend.pdf





Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY


Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: County Series


Map date: 1851

Scale: 1:10,560

Printed at: 1:10,560



Surveyed 1848
Revised N/A
Edition 1851
Copyright N/A
Levelled N/A



Surveyed 1847
Revised N/A
Edition 1851
Copyright N/A
Levelled N/A

Surveyed 1848
Revised N/A
Edition 1851
Copyright N/A
Levelled N/A

Surveyed 1848
Revised N/A
Edition 1851
Copyright N/A
Levelled N/A



Produced by
Groundsure Insights
www.groundsure.com




Supplied by:
www.centremapslive.com
groundsure@centremaps.com


© Crown copyright and database rights 2018 Ordnance Survey 1 00035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsurre_legend.pdf





Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY


Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: County Series


Map date: 1890

Scale: 1:10,560

Printed at: 1:10,560



Surveyed 1890
Revised 1890
Edition N/A
Copyright N/A
Levelled N/A



Produced by
Groundsure Insights
www.groundsure.com




Supplied by:
www.centremapslive.com
groundsure@centremaps.com


© Crown copyright and database rights 2018 Ordnance Survey 100035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsurre_legend.pdf





Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY


Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: County Series


Map date: 1890-1891

Scale: 1:10,560

Printed at: 1:10,560



Surveyed 1890
Revised 1890
Edition N/A
Copyright N/A
Levelled N/A



Surveyed 1891
Revised 1891
Edition N/A
Copyright N/A
Levelled N/A

Surveyed 1891
Revised 1891
Edition N/A
Copyright N/A
Levelled N/A



Produced by
Groundsure Insights
www.groundsure.com




Supplied by:
www.centremapslive.com
groundsure@centremaps.com

© Crown copyright and database rights 2018 Ordnance Survey 100035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsure_legend.pdf





Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY


Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: County Series


Map date: 1908-1909

Scale: 1:10,560

Printed at: 1:10,560



Surveyed 1848
Revised 1909
Edition N/A
Copyright N/A
Levelled N/A



Surveyed 1848
Revised 1908
Edition N/A
Copyright N/A
Levelled N/A

Surveyed 1848
Revised 1908
Edition N/A
Copyright N/A
Levelled N/A

Surveyed 1848
Revised 1908
Edition N/A
Copyright N/A
Levelled N/A



Produced by
Groundsure Insights
www.groundsure.com




Supplied by:
www.centremapslive.com
groundsure@centremaps.com

© Crown copyright and database rights 1988 Ordnance Survey 1 00035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsures_legend.pdf





Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY


Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: County Series


Map date: 1928

Scale: 1:10,560

Printed at: 1:10,560



Surveyed 1848
Revised 1928
Edition N/A
Copyright N/A
Levelled N/A



Surveyed 1848
Revised 1928
Edition N/A
Copyright N/A
Levelled N/A

Surveyed 1848
Revised 1928
Edition N/A
Copyright N/A
Levelled N/A

Surveyed 1848
Revised 1928
Edition N/A
Copyright N/A
Levelled N/A



Produced by
Groundsure Insights
www.groundsure.com




Supplied by:
www.centremapslive.com
groundsure@centremaps.com

© Crown copyright and database rights 2018 Ordnance Survey 1 00035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsurre_legend.pdf





Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY


Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: County Series


Map date: 1938

Scale: 1:10,560

Printed at: 1:10,560



Surveyed 1848
Revised 1938
Edition N/A
Copyright N/A
Levelled N/A



Surveyed 1848
Revised 1938
Edition N/A
Copyright N/A
Levelled N/A

Surveyed 1848
Revised 1938
Edition N/A
Copyright N/A
Levelled N/A



Produced by
Groundsure Insights
www.groundsure.com



Supplied by:
www.centremapslive.com
groundsure@centremaps.com


© Crown copyright and database rights 2018 Ordnance Survey 100035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsurre_legend.pdf





Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY


Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: Provisional


Map date: 1949-1954

Scale: 1:10,560

Printed at: 1:10,560



Surveyed 1949
Revised 1949
Edition N/A
Copyright N/A
Levelled N/A



Surveyed 1954
Revised 1954
Edition N/A
Copyright N/A
Levelled N/A



Produced by
Groundsure Insights
www.groundsure.com




Supplied by:
www.centremapslive.com
groundsure@centremaps.com

© Crown copyright and database rights 18 Ordnance Survey 1 00035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsurre_legend.pdf



Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY


Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: Provisional


Map date: 1956

Scale: 1:10,560

Printed at: 1:10,560



Surveyed N/A
Revised 1955
Edition N/A
Copyright 1956
Levelled N/A



Surveyed N/A
Revised 1955
Edition 1956
Copyright N/A
Levelled N/A



Produced by
Groundsure Insights
www.groundsure.com



Supplied by:
www.centremapslive.com
groundsure@centremaps.com


© Crown copyright and database rights 2018 Ordnance Survey 1 00035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsure_legend.pdf





Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY


Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: Provisional

Map date: 1967-1968

Scale: 1:10,560

Printed at: 1:10,560




Surveyed 1967
Revised 1967
Edition N/A
Copyright N/A
Levelled N/A

Surveyed 1968
Revised 1968
Edition N/A
Copyright N/A
Levelled N/A

Surveyed 1967
Revised 1967
Edition N/A
Copyright N/A
Levelled N/A

Surveyed 1968
Revised 1967
Edition N/A
Copyright N/A
Levelled N/A



Produced by
Groundsure Insights
www.groundsure.com



Supplied by:
www.centremapslive.com
groundsure@centremaps.com

© Crown copyright and database rights 2018 Ordnance Survey 1 00035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsure_legend.pdf



Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY


Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: National Grid


Map date: 1975-1979

Scale: 1:10,000

Printed at: 1:10,000



Surveyed 1975
Revised 1979
Edition N/A
Copyright N/A
Levelled N/A



Surveyed 1974
Revised 1975
Edition N/A
Copyright N/A
Levelled N/A

Surveyed 1976
Revised 1976
Edition N/A
Copyright N/A
Levelled N/A



Produced by
Groundsure Insights
www.groundsure.com



Supplied by:
www.centremapslive.com
groundsure@centremaps.com

© Crown copyright and database rights 2018 Ordnance Survey 1 00035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsurre_legend.pdf





Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY


Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: National Grid


Map date: 1987-1989

Scale: 1:10,000

Printed at: 1:10,000



Surveyed 1983
Revised 1989
Edition N/A
Copyright N/A
Levelled N/A



Surveyed 1984
Revised 1987
Edition N/A
Copyright N/A
Levelled N/A



Produced by
Groundsure Insights
www.groundsure.com



Supplied by:
www.centremapslive.com
groundsure@centremaps.com


© Crown copyright and database rights 2018 Ordnance Survey 1 00035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsure_legend.pdf





Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY



Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: National Grid

Map date: 1992

Scale: 1:10,000

Printed at: 1:10,000



Surveyed 1984
Revised 1992
Edition N/A
Copyright N/A
Levelled N/A



Produced by
Groundsure Insights
www.groundsure.com




Supplied by:
www.centremapslive.com
groundsure@centremaps.com

© Crown copyright and database rights 2018 Ordnance Survey 100035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsure_legend.pdf





Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY


Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: National Grid

Map date: 2001

Scale: 1:10,000

Printed at: 1:10,000



2001



Produced by
Groundsure Insights
www.groundsure.com




Supplied by:
www.centremapslive.com
groundsure@centremaps.com

© Crown copyright and database rights 18 Ordnance Survey 1 00035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsurance_legend.pdf





Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY


Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: National Grid

Map date: 2010

Scale: 1:10,000

Printed at: 1:10,000



2010



Produced by
Groundsure Insights
www.groundsure.com



Supplied by:
www.centremapslive.com
groundsure@centremaps.com

© Crown copyright and database rights 2018 Ordnance Survey 100035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsure_legend.pdf





Site Details:

Land off Queen Street &
Whitehall Street, Rochdale,
OL12 0TY


Client Ref: CMAPS-AAG-1078975-4165-030123
Report Ref: CMAPS-AAG-1078975-4165-030123-HIS
Grid Ref: 389786, 413897

Map Name: National Grid

Map date: 2023

Scale: 1:10,000

Printed at: 1:10,000



2023



Produced by
Groundsure Insights
www.groundsure.com




Supplied by:
www.centremapslive.com
groundsure@centremaps.com

© Crown copyright and database rights 2018 Ordnance Survey 100035207

Production date: 03 January 2023

Map legend available at:

www.groundsure.com/sites/default/files/groundsure_legend.pdf



APPENDIX E: SITE PHOTOGRAPHS



1. Roadway leading into study site off Duke Street
2. Northern section of the study site, fronting onto Queen Street





3. As Figure 1 above, shown landscaped verge extending along Queen Street frontage
4. Western section of the study site showing landscaped verge fronting onto Whitehall Street





5. Study site as seen from its western boundary
6. Western section of the study site as seen from its eastern boundary





7. Eastern section of the study site showing landscaped verge fronting onto Duke Street
8. Showing presence of buried services with hard paved surface





9. As Figure 7 above
10. As above

