

Trees

Qty	Abbreviation	Species	Girth (cm)	Height (cm)	Root Zone	Specification
2	Ac	Acer freemanii 'Autumn Blaze'	20-25	500-550	RB	3x; Semi-mature; Clear stem minimum 200cm
2	Ag	Amelanchier x grandiflora 'Ballerina'	n/a	300-350	RB	Multi stem; Clear stem minimum 150cm; 3 breaks; Umbrella form
2	Zs	Zelkova serrata 'Green Vase'	n/a	300-350	RB	Multi stem; Clear stem minimum 150cm; 3 breaks; Umbrella form

Specimen Shrubs

Qty	Abbreviation	Species	Pot Size	Height (cm)	Specification
23	Ps	Pittosporum tenuifolium 'Tom Thumb'	15L	40	Bushy; min 7 breaks
9	Vd	Viburnum davidii	15L	40-60	Bushy; min 6 breaks
21	Pm	Pinus mugo 'Pumilio'	15L	40-50	Bushy
20	Ma	Mahonia 'Soft Caress'	15L	50-60	Bushy; min 3 breaks

Evergreen and Perennial Herbaceous

Qty	Abbreviation	Species	Pot Size	Specification
97	Vb	Verbena bonariensis	3L	Full pot
81	Pb	Persicaria bistorta 'Superba'	3L	Full pot
91	Am	Achillea millefolium	3L	Full pot
178	Lm	Liriope muscari	3L	Full pot
27	Pu	Pulmonaria 'Trevi Fountain'	3L	Full pot
31	Df	Dryopteris filix-mas	3L	Full pot
33	Ln	Luzula nivea	3L	Full pot
41	As	Asplenium scolopendrium	3L	Full pot
31	Hn	Helleborus niger	3L	Full pot
189	Sn	Salvia nemorosa 'Caradonna'	5L	Full pot
36	Pe	Perovskia 'Blue Spire'	5L	Full pot
93	Hy	Hylotelephium telephium 'Purple Emperor'	5L	Full pot
66	Kn	Kniphofia 'Ice Queen'	5L	Full pot
71	Ga	Gaura lindheimeri 'Whirling Butterflies'	5L	Full pot
151	Ru	Rudbeckia fulgida var. sullivantii 'Goldsturm'	5L	Full pot

Ornamental Grasses

Qty	Abbreviation	Species	Pot Size	Specification
275	Cm	Carex morrowii	3L	Full pot
39	Ha	Hakonechloa macra 'Green Hills'	3L	Full pot

Bulb Underplanting

Qty	Abbreviation	Species	Grade	Density per m2	Percentage
-----	--------------	---------	-------	----------------	------------

Planted in Groups of Individual Species

1050	Gn	Galanthus nivalis	Grade 5/6	50	n/a
865	Ge	Galanthus elwesii	Grade 5/6	50	n/a

Bulb Mix 1

289	Nm	Narcissus 'Minnow'	Grade 10/12	30	30%
386	Ns	Narcissus 'Sailboat'	Grade 10/12	30	40%
290	Nw	Narcissus 'Sweetness'	Grade 10/12	30	30%
				Total	100%

Bulb Mix 2

354	Ap	Allium 'Purple Sensation'	Grade 12/+	30	40%
354	Cc	Camassia cusickii	Grade 14/+	30	40%
176	Al	Allium sphaerocephalon	Grade 5/6	30	20%
				Total	100%

PLANTING BED IDENTIFICATION



PLANTING NOTES

Plant material to conform to the National Plant Specification. Plant handling and planting operations to be in accordance with Horticultural Trade Association Good Practice. No plants to be left out of pots for longer than 5 minutes. All bare root stock to be healed in or kept in wind proof root protection until needed for planting.

Imported topsoil to be BS 3882:2007 Topsoil, from an approved source, and to accord with the above specification. Grade: Within the parameters of 'sandy loam' textural class. Imported topsoil to be free from:
- injurious or pernicious weeds, e.g. common ragwort, spear thistle, Japanese knotweed, fat hen, couch grass, bindweed, Himalayan balsam and giant hogweed;
- sharps, plastics and non-soil forming materials;
- notifiable animal or plant diseases;

Any approved sample load to be kept on site for comparison purposes. Soil retained on site for re-use to have following characteristics:
- Free of pests and diseases and chemical or biological contamination.
- Foreign matter: On visual inspection, free of fragments and roots of aggressive weeds, sticks, straw, subsoil, pieces of brick, concrete, glass, wire, large lumps of clay or vegetation, and the like.

Do not use topsoil contaminated with subsoil, rubbish or other deleterious materials.

Subsoil: In areas to receive topsoil or planting media, do not use subsoil contaminated with the above materials.

Give notice: If any evidence or symptoms of soil contamination are discovered on the site or in topsoil or planting media to be imported.

Sanitized and stabilised composted materials certified to PAS 100 for planting beds.

The depth of topsoil spread shall not normally exceed 300 mm. Suitable (loosened) subsoil shall provide the remainder of the minimum rooting depth. The minimum rooting depth shall be normally a minimum of 600 mm for shrubs and 900 mm for trees.

TREES
Trees to be planted in accordance to their size, height and species requirements in accordance with Landscape architect's details. Underground guying to be used unless otherwise specified.

No trees are to be planted within 3m of sewers or services (or any other easement recommended by the relevant statutory undertaker) without the use of an appropriate tree root barriers placed between the tree and services. Contractor to ascertain the location of all the sewers and services prior to tree planting.

Trees to be planted at nursery level.

PLANTING BEDS

Shrubs to be planted in pits 150mm wider and deeper than root spread backfilled with excavated topsoil, and additional topsoil where necessary and compost mixed with an appropriate slow release fertilizer, quantity in accordance with manufacturer's recommendations.

All planting beds to be mulched with matured coniferous bark, with an even particle size between 10-40mm, to a minimum depth of 50mm over weed free soil after completion of all planting and watering operations. Mulch to be free of pests, diseases, fungus and weeds, and with no fines or dust. Mulch source and sample to be approved and retained on site for comparison purposes.

Native tree, scrub and hedge planting to be protected from rabbit damage with spiral guards, tree shelters or Net guards for bushy shrub species.

GENERAL MAINTENANCE NOTES
Maintenance operations to be carried out as specified until planting becomes established (year 5 after completion of planting).

Trees - Check stakes and ties and adjust if necessary in summer and winter. Remove stakes when no longer required, i.e. after 3 years. Prune out damaged branches or deadwood, cutting back so as not to affect branch collar. Progressively raise canopies of new trees to provide clearance for vehicles and pedestrians.

Shrubs - Weed control measures to continue until the canopy of shrubs is closed. Weeds to be cleared by hand or by application of translocated herbicide, with inspections made regularly through the growing season. Prune back any badly damaged shrubs to sound growth.

Cut back plants adjacent to paths and access ways where necessary, retaining a balanced shape. Clear litter and debris from planted areas and cut leggy growth hard back to promote bushy growth.

Watering - In periods of dry weather apply sufficient water to maintain healthy growth. Allow 10L/m² to planting beds and 50L/tree at each operation.

Refirming - Ensure that all trees and shrubs are firmly bedded in the ground after strong winds, frost heave or other disturbances.

Stakes and Shelters - At every maintenance visit inspect tree stakes, guards and shelters for all stock and effect minor repairs and re-setting such as straightening equipment or replacing damaged shelters and stakes.

Protection/ Reinstatement - Regularly inspect all planting e.g. once a month, for any pest damage or vandalism/ damage by others. Any damage to be reported to the Employer and rectified in the next available planting season by replacement planting or, and protective measures if required.

C This drawing is copyright protected and may not be reproduced in whole or part without written authority from the owner.

NOTES:
1. Do not scale from this drawing.
2. Always work to noted dimensions.
3. All dimensions are in millimetres unless otherwise stated.
4. All setting out, levels and dimensions to be agreed on site.
5. The dimensions of all materials must be checked on site before being laid out.
6. This drawing must be read with the relevant specification clauses and detail drawings.
7. Order of construction and setting out to be agreed on site.

Note
This drawing should be read in conjunction with the following drawings:

3546-PLA-XX-XX-DR-L-2002
Soils Plan

3546-PLA-XX-XX-DR-L-2003
Planting Schedule

3546-PLA-XX-XX-DR-L-2004
Detailed Planting Plan (Bed 1 - Plants)

3546-PLA-XX-XX-DR-L-2005
Detailed Planting Plan (Bed 1 - Bulbs)

3546-PLA-XX-XX-DR-L-2006
Detailed Planting Plan (Bed 2 Plants & Bulbs)

3546-PLA-XX-XX-DR-L-2007
Detailed Planting Plan (Bed 3 - Plants)

3546-PLA-XX-XX-DR-L-2008
Detailed Planting Plan (Bed 3 - Bulbs)

3546-PLA-XX-XX-DR-L-2009
Detailed Planting Plan (Bed 4 Plants & Bulbs)

3546-PLA-XX-XX-DR-L-2010
Detailed Planting Plan (Bed 5 Plants & Bulbs)

3546-PLA-XX-XX-DR-L-2011
Detailed Planting Plan (Bed 6 Plants & Bulbs)

Refer to specification:
Section Q28, Q31 and Q35

C01	03/06/25	Stage 5	YH	SPL
Revision	Date	Description	Drawn	Apprvd.

PLANIT

Manchester | London | Liverpool | Leeds | Standish

Manchester
2 Back Grafton Street,
Altrincham,
Cheshire,
WA14 1DY

W: plant-ie.com
E: info@plant-ie.com
T: 0161 928 9281

Client Rochdale Borough Council

Project Heywood Peine Square

Drg Title Planting Schedule

Created on 17-02-25
Created by MB
Approved by SPL

Scale n/a
Size A3
Workstage RIBA 5

Drg No. 3546-PLA-XX-XX-DR-L-2003
Suitability S4
Revision C01