

PLEASE NOTE THAT THIS DRAWING IS ISSUED FOR INFORMATION/TENDER PURPOSES ONLY UNTIL TECHNICAL APPROVAL HAS BEEN GRANTED. ANY WORK UNDERTAKEN PRIOR TO TECHNICAL APPROVAL BEING GRANTED IS AT THE CLIENTS RISK.

The details provided on this drawing are subject to comments by all the relevant approving authorities. Until such time as all comments have been received and incorporated onto the drawings, all the information provided and costings, are used at MCI Developments Ltd risk and no liability will be accepted by ALD Design. Scheme based on Site Layout MCI-000-DR-A-500 PL10

SECTION 104 & 30 NOTES

1. All adoptable drainage works have been designed and are to be constructed in accordance with current Design & Construction Guidance & local practices
2. All clay pipe work shall be Extra Strength Clayware to B.S. EN 295 1991 Part 1
3. All precast concrete pipework shall be to the class stated on the drawings in accordance with BS EN 1916:2002
4. All manholes and chambers shall be to BS EN 1917:2002
5. The Contractor may elect to use nonroad PVC pipes as covered by BS 4660:2000 & BS EN 1401-1
6. Structured well upvc pipes to comply with w4 4-35-01 up to and including 300mm (By prior agreement with adopting authority)
7. MAX. PIPE LENGTH TO BE 3.0m
8. All levels relate to an Ordnance Datum
9. This drawing is to be read in conjunction with all other relevant drawings
10. House drainage connections to sewers must be 150mm Ø and unless otherwise stated lead to the drainout invert level shown
11. Levels given on drag out chambers are incoming pipe levels
12. House drainage runs to be kept within the curtilage of the plot they serve wherever possible
13. The Contractor shall be responsible for ensuring that any existing invert levels indicated on drawings are correct before work commences
14. The Contractor should satisfy himself as to the position and depth of any existing Statutory Undertakers plant which could effect the works before the works are commenced
15. Road gully connections are to be 150mm Ø connecting either directly to manholes shown, or to sewer runs using pre-formed junctions
16. All connections to adoptable sewers shall be by manufactured junction pipes. Saddle connections will not be permitted
17. All sewers for adoption with greater than 1.20 metres cover in roads or 0.9m metres cover in fields shall have Class S granular bed and surround
18. Any sewer for adoption with less than 1.2 metres cover in roads or 0.9 metres cover in fields shall have a minimum of 150mm ST4 concrete surround. Flexibility shall be maintained by the provision of Flexacil or similar approved joint filler breaks in the concrete surround at each pipe joint

ALL PIPES TO HAVE CLASS "S" BED AND SURROUND UNLESS SHOWN OTHERWISE
ALL CONCRETE PIPES TO BE CLASS 120
ALL CLAY PIPES TO BE EXTRA STRENGTH VITRIFIED CLAY
ALL UPVC PIPES TO COMPLY WITH BS 4660:2000 & BS EN 1401-1
STRUCTURED WALL UPVC PIPES TO COMPLY WITH W4 4-35-01
MAX. PIPE LENGTH TO BE 3.0m

FOUNDATIONS TO BE DESIGNED / CONSTRUCTED TO TAKE INTO ACCOUNT THE PROXIMITY AND DEPTH OF ADJACENT SEWERS AND DRAINS IN ACCORDANCE WITH SFA 7TH EDITION PART 8

CONTRACTOR TO BE AWARE OF AND TAKE APPROPRIATE ACTION TO ENSURE DE-STABILISATION OF ANY EXISTING STRUCTURES, TREES, EMBANKMENTS OR OTHER FEATURES DOES NOT OCCUR AS A RESULT OF ANY EXCAVATIONS WORKS UNDERTAKEN IN ACCORDANCE WITH THE DESIGNS SHOWN ON THIS DRAWING IF CONTRACTOR IS UNSURE ABOUT ANY ASPECT OF THE ABOVE HE SHOULD SEEK ADVICE BEFORE COMMENCING EXCAVATION WORK

THE OFF SITE SEWER CONNECTIONS HAVE BEEN DESIGNED TO TIE IN WITH THE EXISTING SEWERS AND WHILE IT IS ANTICIPATED NO CLASHES WITH EXISTING SERVICES WILL OCCUR DUE TO THE INHERENT INACCURACIES IN DEPTHS OF EXISTING SERVICES THIS CANNOT BE GUARANTEED

ALD WOULD ADVISE THE CLIENT TO EMPLOY A SUITABLY EXPERIENCED COMPANY TO UNDERTAKE A SURVEY ALONG THE ROUTE OF THE CONNECTIONS TO ASCERTAIN THE EXISTENCE AND PROXIMITY OF ANY SERVICES AND ADVISE ALD OF ANY POTENTIAL CLASHES TO ASCERTAIN IF DESIGN CHANGES NEED BE MADE

DUE TO THE NEED FOR OFF SITE SEWER WORKS IT IS STRONGLY ADVISED THAT THESE INVESTIGATIONS ARE UNDERTAKEN PRIOR TO ANY CONSTRUCTION ON SITE TO ALLOW DESIGN CHANGES TO BE MADE

ALD WILL NOT BE HELD RESPONSIBLE FOR ANY ABORTIVE WORKS IF THIS PROCEDURE IS NOT FOLLOWED

ALL EXISTING MANHOLE INVERT LEVELS ARE TO BE LOCATED AND SURVEYED PRIOR TO START ON SITE TO ENSURE THAT THEY ARE CORRECT AND ALSO TO ENSURE THAT LEVEL CLASHES ARE AVOIDED AND THAT INTERPOLATED INVERT LEVELS ARE CORRECT. ANY DISCREPANCY TO BE REPORTED TO ALD PRIOR TO START TO ENABLE ANY CHANGES TO BE MADE TO DESIGN THAT PROVE NECESSARY

CIVILS DESIGN RISK MANAGEMENT

Abnormal or unusual residual risks associated with the design outcomes shown on this drawing are:-

1. EXISTING SERVICES
2. DANGER OF COLLAPSE TO ALL EXCAVATIONS - RISK TO BE ASSESSED AND MANAGED BY CONTRACTOR IN ACCORDANCE WITH HSE GUIDANCE
3. WORKING ADJACENT TO EXISTING WATERCOURSE OR LIVE FIBRIL SEWER (WELL'S DISEASE)
4. WORKING ADJACENT TO EXISTING ADAPTED SURFACE WATER SEWER

ALD Design Ltd has followed its Design Risk Management process for Hazard Elimination and Risk reduction in developing the designs shown on this drawing. Abnormal or unusual residual risks may be shown above where it is considered that such risk may not normally be expected by competent persons engaged on work of this nature or type

GENERAL

1. All adoptable sewers and associated works are to comply fully with 'Design and Construction Guidance' & Local Practices
2. All highway works to be to adoptable standards and to comply fully with the Local Authority specification
3. All private drainage works are to comply fully with Part H of the Building Regulations
4. All existing invert levels to be checked by the Contractor at the start of works and any discrepancies notified to ALD Design
5. All levels are based on topographical survey information provided by others
6. All materials to bear the relevant B.S. Kitemark and comply fully with the specifications
7. All concrete & concrete products must use Sulphate resistant cement (unless the site investigation report proves that sulphate attack from soils and groundwater will not occur)
8. All opening notices etc. are to be obtained prior to commencement of works
9. All works are to be inspected by LA, NHBC or Relevant Water Authority as applicable

C.D.M. REGULATIONS 2015

In line with the above regulations we are obliged to inform the Client of their responsibilities under section CDM 15/1, and residual risks that may be encountered in the construction of these works. All design work has been carried out with Health and Safety aspects given full consideration. Wherever possible risks have been eliminated from the design, however due to the very nature of this type of work it is not possible to remove all the risks from the design. We would also respectfully remind the Client of his obligations to take all reasonable steps in ensuring that any competent Contractors who have a valid safety policy are employed. They should also provide satisfactory responses at tender stage as to the manner in which they will deal with the elements of risk involved in this type of work and in particular those highlighted by ALD Design below:-

1. Support / treatment for ALL excavation work
2. Guarding to edges of excavations to prevent people, materials and vehicles falling into excavation
3. Guarding of excavations outside working hours to prevent unauthorised access
4. Undermining to adjacent roads or structures
5. Confined space operations
6. Dealing with existing services
7. Traffic management on existing highways
8. Procedure to be followed in event of accident or emergency
9. Method of working where contaminated ground is present on site
10. Confirmation will be required that all operatives are adequately trained, copies of relevant training certificates to be supplied

The above list is by no means exhaustive but it does highlight operations that present a risk to contractors and the general public. For clarification on any item please contact ALD Design.

Rev.	Date	Amendment	Drawn	CHKD	Appd
G	20.06.20	Revised to layout PL10, revised S185 sewer locations	AP		
F	09.05.20	Revised following meeting with LUJ	AP		
E	14.10.20	Revised following additional survey work	AP		
D	29.08.20	Revised to layout Rev PL08	AP		
C	14.07.20	Updated following completion of the remainder of the pack	AP		
B	18.06.20	Revised proposed Levels	AP		
A	02.06.20	First Issue	AP		



3 Woodhurst Drive, Sandhals, Wigan, WNG 0PR, United Kingdom
Tel: +44 (0) 1257 886093

Client		 MCI A KEEPMOAT COMPANY			
Project Title					
Trub Farm Rochdale					
Status		Information			
Drawing Title					
S185 FW SEWER DIVERSION LAYOUT SHEET 1 OF 2					
Drawn	Date	Checked	Date	Approved	Date
AP	JUNE 25				
Scale	1:500	Orig Size	A0	Dimensions	
Project No.		Drawing File			
25013					
Drawing No.				Rev.	
30-02-01				G	

Scale 1:500

0

5

10

15

20

25m



Scale 1:500
0 5 10 15 20 25m

FOR CONTINUATION OF SITE SEE DRAWING SHEET 30-02-02